

The CITY OF MASSILLON, OHIO

THE UNDERSIGNED certifies that _____ personally and carefully examined the location of the proposed improvement; also that _____ examined the plans and specifications on file in the Office of the Director of Public Safety and Service and having made such examinations, the undersigned hereby proposes to do all the work and furnish all materials to complete the said improvement in accordance with the Plans and Specifications, under the direction and to the satisfaction of the City Engineer and the Director of Public Safety and Service, for the prices following, to wit:

Levee Infrastructure Improvement Project

Levee Infrastructure Improvement Project

STATE ITEM	DESCRIPTION	QUANTITY	UNIT	SEPARATE UNIT PRICES IN ARABIC NUMBERS				TOTAL PRICES WRITTEN IN ARABIC NUMBERS (C)	
				MATERIAL (A)		LABOR (B)			
				DOLLARS	CENTS	DOLLARS	CENTS	DOLLARS	CENTS
ROADWAY									
202 Spec	24" and Less Pipe Cleanout	3730	L.F.						
202 Spec	Greater than 24" Pipe Cleanout	2432	L.F.						
202	Manhole Removed	3	EACH						
202	Concrete Channel and Headwall Removed	1	LUMP SUM						
202	Pipe Removed	145	L.F.						
202	Plug and Fill Conduit	49	L.F.						
202	Structure Removed	1	EACH						
TOTAL ROADWAY									
DRAINAGE									
603	18" Type B Conduit	30	L.F.						
603	Concrete Collar	3	EACH						
604	Drainage Manhole Mass 1048A	1	EACH						
604	Catch Basin Type : ODOT 2-5 Cast-in-Place	1	EACH						
809	Wall Mounted 15" Automatic Drainage Gate	1	EACH						
810	18" Host Pipe Slip Lining	110	L.F.						
810	42" Host Pipe Slip Lining	105	L.F.						
810	48" Host Pipe Slip Lining	492	L.F.						
810	60" Host Pipe Slip Lining	270	L.F.						
810	66" Host Pipe Slip Lining	80	L.F.						
811SPEC	3'-42" Host Pipe Cast in Place Grouting Sleeve	2	EACH						
813	12x7'9" Concrete Culvert Joint Repair and Seal	12	EACH						
TOTAL DRAINAGE									

SANITARY									
603	14" DUCTILE IRON PIPE	10	L.F.						
603	20" DUCTILE IRON PIPE	10	L.F.						
603	24" DUCTILE IRON PIPE	10	L.F.						
603	18" SDR35	14	L.F.						
603	27" SDR35	8	L.F.						
603	30" SDR35	49	L.F.						
603	36" SDR35	8	L.F.						
603	42" SDR35	42	L.F.						
604Spec	Sanitary Manhole Mass 1048AGS(5'Dia.)	1	EACH						
604Spec	Sanitary Manhole Mass 1048AGS(6'Dia.)	2	EACH						
604Spec	Sanitary Manhole Mass 1048AGS(7'Dia.)	2	EACH						
604Spec	Sanitary Siphon Chamber	1	EACH						
604Spec	Sanitary Siphon Chamber Rehabilitation	5	EACH						
811	8" Cure in Place Pipe	450	L.F.						
811	10" Cured in Place Pipe	890	L.F.						
811	15" Cured in Place Pipe	440	L.F.						
811	18" Cured in Place Pipe	440	L.F.						
811	14" Replace Protective Coating (Epoxy)	460	L.F.						
811	20" Replace Protective Coating (Epoxy)	460	L.F.						
811	24" Replace Protective Coating (Epoxy)	460	L.F.						
TOTAL SANITARY									
INCIDENTALS									
604Spec	Field Office	1	LUMP SUM						
603	Construction Staking	1	LUMP SUM						
603	Mobilization	1	LUMP SUM						
TOTAL INCIDENTALS									
BASE BID TOTAL									