LOCATION MAP

LATITUDE: N 40°46'05" LONGITUDE: W 81°31'15"





PORTION TO BE IMPROVED \_\_\_\_ INTERSTATE & DIVIDED HIGHWAY\_\_\_\_\_ UNDIVIDED STATE & FEDERAL ROUTES OTHER ROADS....

0

	S.R. 21	ERIE ST
CURRENT ADT (2003)	23,047	15,264
DESIGN YEAR ADT (2023)	37,130	23,848
DESIGN HOURLY VOLUME (2023)	2,970	1.908
DIRECTIONAL DISTRIBUTION	0.50	0.50
TRUCKS (24 HOUR B&C)	11%	6%
DESIGN SPEED	55 MPH	35 MPH
LEGAL SPEED	50 MPH	35 MPH
DESIGN FUNCTIONAL CLASSIFICATION:		, 15,51 111,111
S.R. 21 - URBAN FREEWAY, ERIE ST URBAI	V COLLECTOR	
NHS PROJECT	VEC	410

DESIGN EXCEPTIONS

NONE REQUIRED

#### UNDERGROUND UTILITIES CONTACT BOTH SERVICES CALL TWO WORKING DAYS BEFORE YOU DIG 1-800-362-2764 (TOLL FREE) OHIO UTILITIES PROTECTION SERVICE NON-MEMBERS MUST BE CALLED DIRECTLY OIL & GAS PRODUCERS PROTECTIVE

SERVICE CALL: 1-800-925-0988 PLAN PREPARED BY:

W.E. QUICKSALL & ASSOCIATES CIVIL ENGINEERS NEW PHILADELPHIA, OHIO

# STATE OF OHIO DEPARTMENT OF TRANSPORTATION

STA-21-8.98

# CITY OF MASSILLON STARK COUNTY

INDEX OF SHEETS:

ENGINEER'S SEAL:

TITLE SHEET	1
MAINTENANCE OF TRAFFIC	2 - 6
S.R. 21 PLAN SHEET	7
MISCELLANEOUS DETAILS	8 - 11
STUCTURES OVER 20'	12 - 14

## **BUILDABLE UNIT #1**

SUPPLEMENTAL STANDARD CONSTRUCTION DRAWINGS SPECIFICATIONS 7/16/04 800 7/20/07 GR-2.1 1/16/04 DATE:\_ 1/19/07 ENGINEER'S SEAL: RM-4.2 10/20/06 MT-95.30 9/05/06 MT-95.40 10/20/06 MT-95.50 9/05/06 COLLING II MT-97.11 9/05/06 SPECIAL MT-101.60 9/20/06 MT-101.70 10/18/02 **PROVISIONS** MT-105.10 10/18/02 MT-105.11 10/18/02

#### PROJECT DESCRIPTION

REPLACE AND WIDEN THE DECK OF THE STA-21-0898 BRIDGE. THE BRIDGE CARRIES ERIE STREET OVER S.R. 21.

#### EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A MAINTENANCE NOTICE OF INTENT EARTH DISTURBED AREA: N/A MAINTENANCE

#### LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

#### 2005 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION. INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT DE-TOURS WILL BE PROVIDED AS INDICATED ON SHEET \_\_\_.

> APPROVED FOR CONSTRUCTION 1/25/08



Σ

#### MAINTENANCE OF TRAFFIC

0

0

 $\bigcirc$ 

 $\bigcirc$ 

THIS ITEM SHALL CONSIST OF MAINTENANCE OF TRAFFIC ON EXISTING ROADWAYS AND RAMPS IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS (OMUTCD), CURRENT EDITION, LATEST REVISION, THE SPECIFICATIONS AND THE FOLLOWING:

THE CONTRACTOR SHALL INFORM THE DISTRICT OFFICE (330) 786-2211, EIGHTEEN (18) DAYS PRIOR TO THE BEGINNING OF

INTERIM COMPLETION DATE: ALL WORK THAT WILL REQUIRE LANE CLOSURES ON S.R. 21, EXCEPT FOR THOSE IN ACCORDANCE WITH "STOPPAGE OF MAINLINE TRAFFIC (S.R. 21)" NOTE SHALL BE COMPLETED BEFORE JULY 1, 2008. SHOULD THE DBT FAIL TO MEET ANY OF THESE REQUIREMENTS, THE DBT SHALL BE ASSESSED LIQUIDATED DAMAGES IN ACCORDANCE WITH CMS 108.07.

CONES SHALL NOT BE ACCEPTABLE TRAFFIC CONTROL DEVICES FOR LANE RESTRICTIONS OR LANE REDUCTIONS THAT ARE IN OPERATION ONE HALF HOUR AFTER SUNSET OR ONE HALF HOUR BEFORE SUNRISE. ALL NIGHTTIME LANE RESTRICTIONS SHALL REQUIRE DRUMS OR BARRICADES AT A MAXIMUM SPACING OF FIFTY (50) FEET. WEIGHTED CHANNELIZERS MAY BE USED IN ACCORDANCE WITH THE ADDITIONAL NOTE PROVIDED HEREIN.

THE CONTRACTOR SHALL FURNISH, ERECT, MAINTAIN AND SUBSEQUENTLY REMOVE ALL FLAGS, BARRICADES, SIGNS, SIGN SUPPORTS AND FURNISH AND MAINTAIN ALL FLAGGERS, WATCHERS AND INCIDENTALS RELATED THERETO.

PAYMENT FOR ALL ITEMS REQUIRED BY THE OMUTCD. THE STANDARD CONSTRUCTION DRAWINGS, THE CONSTRUCTION AND MATERIAL SPECIFICATIONS SHALL BE INCLUDED IN THE LUMP SUM PAYMENT FOR ITEM 614, MAINTAINING TRAFFIC AND SHALL INCLUDE ALL LABOR, MATERIAL, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE REQUIRED WORK.

#### MOT RESTRICTIONS

SR-21 --- LANE CLOSURES:

DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AS PER THE PERMITTED LANE CLOSURE CHART. THE PERMITTED LANE CLOSURE CHART USED FOR THIS PROJECT SHALL BE THE MOST CURRENT CHART AVAILABLE ON THE DATE THIS

PROJECT SELLS.
SHOULD THE DBT FAIL TO MEET ANY OF THE REQUIREMENTS IN THE PERMITTED LANE CLOSURE CHART, THE DBT SHALL BE ASSESSED LIQUIDATED DAMAGES IN THE AMOUNT OF \$1,250 PER HOUR OR PORTION THEREOF THAT THE LANE REDUCTION REMAINS BEYOND THE SPECIFIED LIMIT.

THE PERMITTED LANE CLOSURE CHART CAN BE

FOUND AT: HTTP://PLCM.DOT.STATE.OH.US/
COMPLETE CLOSURE OF SR-21 SHALL ONLY BE
PERMITTED ON WEEKENDS FROM 12:00 AM TO 5:00
AM IN ACCORDANCE WITH THE "STOPPAGE OF MAINLINE TRAFFIC" NOTE HEREIN.

PERMANENT LANE CLOSURES (CLOSURE FOR MORE THAN 12 HOURS) ON SR-21 WILL NOT BE PERMITTED BETWEEN JULY 1, 2008 AND APRIL 1, 2009. ALL LANE CLOSURES BETWEEN JULY 1, 2008 AND APRIL 1, 2009 WILL HAVE TO BE SHORT-TERM OPERATIONS (12 HOURS OR LESS) AND ARE SUBJECT TO THE APPROVAL OF THE ENGINEER.

ERIE STREET --- TWO 12'-0" LANES WITH 2'-0" MINIMUM OFFSETS SHALL REMAIN OPEN AT ALL TIMES EXCEPT AS NOTED BELOW:

- EASTBOUND TRAFFIC MAY BE DETOURED FOR MAXIMUM OF 90 CONSECUTIVE CALENDAR DAYS. WESTBOUND MINIMUM LANE WIDTH DURING DETOUR:
- 10'-0" WITH 6" OFFSETS
- OFFICIAL (SIGNED) DETOUR ROUTE: SOUTHBOUND SR-21 / US-30 RAMPS / NORTHBOUND SR-21 AS SHOWN ON SHEET NO.\_\_\_\_\_
  THERE IS NO LOCAL DETOUR ROUTE
- THE DETOUR SIGNING SHALL BE PROVIDED

BE MADE DURING 2009.

ERECTED, MAINTAINED AND REMOVED BY THE DBT.

#### WEIGHTED CHANNELIZERS

THE WEIGHTED CHANNELIZER SHALL BE PREDOMINATELY ORANGE IN COLOR AND SHALL BE MADE OF A LIGHTWEIGHT. FLEXIBLE, AND DEFORMABLE MATERIAL. THEY SHALL BE AT LEAST 42 INCHES IN HEIGHT WITH A WEIGHTED BASE. THE MAY HAVE A "HANDLE" OR LIFTING DEVICE WHICH EXTENDS ABOVE THE 42 INCH MINIMUM HEIGHT

THE MARKINGS ON THE WEIGHTED CHANNELIZER SHALL BE HORIZONTAL, CIRCUMFERENTIAL, ALTERNATING ORANGE AND WHITE RETROREFLECTIVE STRIPES 6 INCHES WIDE. EACH WEIGHTED CHANNELIZER SHALL HAVE A MINIMUM OF TWO ORANGE AND TWO WHITE STRIPES. ANY
NON-RETROREFLECTIVE SPACES BETWEEN THE HORIZONTAL
ORANGE AND WHITE STRIPES SHALL NOT EXCEED 2 INCHES
WIDE. THE WEIGHTED CHANNELIZER SHALL HAVE A 4-INCH MINIMUM WIDTH, REGARDLESS OF ORIENTATION.

#### ON FREEWAYS AND MULTILANE HIGHWAYS:

- A. USE OF WEIGHTED CHANNELIZERS ON FREEWAYS AND MULTILANE HIGHWAYS SHALL BE LIMITED TO SHORT-TERM OPERATION, GENERALLY TWELVE HOURS OR LESS, FOR EITHER DAY OR NIGHT. UPON COMPLETION OF WORK WITHIN THE ABOVE NOTED TIME PERIOD, THE WEIGHTED CHANNELIZERS SHALL BE REMOVED. THE WEIGHTED CHANNELIZERS SHALL BE REMOVED. THE WEIGHTED CHANNELIZERS MAY AGAIN BE PLACED ON THE HIGHWAY WHEN THE WORK IS TO RESUME ON THE FOLLOWING DAY OR NIGHT. ANY LANE CLOSURE USING CHANNELIZATION DEVICES, EXPECTED TO REMAIN FOR MORE THAN TWELVE HOURS, SHALL REQUIRE THE USE OF DRUMS OR
- B. WHEN USED AT NIGHT, WEIGHTED CHANNELIZERS SHALL ONLY BE PLACED IN THE "TANGENT AREA". THE "TANGENT AREA" IS DEFINED AS THE AREA AFTER THE TRANSITION TAPER WHERE THE WORK TAKES PLACE. DRUMS SHALL BE USED IN THE TRANSITION TAPERS FOR NIGHT OPERATIONS.

ON OTHER HIGHWAYS:

THERE ARE NO DURATIONS OF WORK RESTRICTIONS FOR USE OF WEIGHTED CHANNELIZERS ON ALL OTHER TYPES OF HIGHWAYS, DAY OR NIGHT. ON THESE ROADWAYS THE WEIGHTED CHANNELIZER MAY BE USED IN THE TRANSITION TAPERS AS WELL AS IN THE TANGENT AREAS, DAY OR NIGHT.

MAXIMUM SPACING OF THE WEIGHTED CHANNELIZER SHALL BE 40 FFFT

STEPS SHOULD BE TAKEN TO ENSURE THAT THE WEIGHTED CHANNELIZERS WILL NOT BE BLOWN OVER OR DISPLACED BY WIND OR MOVING TRAFFIC. BALLASTS SHOULD NOT PRESENT A HAZARD IF THE WEIGHTED CHANNELIZERS ARE INADVERTENTLY STRUCK, NOR SHOULD THEY AFFECT THE VISIBILITY OF THE WEIGHTED CHANNELIZERS. ALL BALLASTS USED SHOULD BE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS

#### DETOUR NOTIFICATION (ERIE STREET)

THE CONTRACTOR SHALL ADVISE THE ODOT DISTRICT OFFICE (330-786-3148) EIGHTEEN (18) DAYS IN ADVANCE OF WHEN THE DETOUR ROUTE SHOULD BE IN EFFECT. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL DEVICES NECESSARY TO DEFINE THE ROUTE OF THE DETOUR AND SHALL MAINTAIN THE SAME THROUGHOUT THE DETOUR LIMITATION DATES. ALL WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED. OTHER THAN FOR THE DETOUR, SHALL BE FURNISHED, ERECTED, MAINTAINED, AND SUBSEQUENTLY REMOVED BY THE CONTRACTOR. PAYMENT FOR ALL WORK AND MATERIALS
REQUIRED TO ACCOMPLISH THIS TASK SHALL BE INCLUDED IN
THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING

#### DETOUR DURATION (ERIE STREET)

THE MAXIMUM LENGTH OF TIME FOR THE DETOUR ROUTE TO BE IN EFFECT SHALL BE 90 CONSECUTIVE DAYS. CONSTRUCTION WORK MAY BE PERFORMED BEFORE AND AFTER THE DETOUR LIMITATION DATES, BUT THERE SHALL BE NO RESTRICTIONS (LANE WIDTH REDUCTIONS, TEMPORARY ROADWAYS, OR ONE WAY TRAFFIC) TO THROUGH OR LOCAL TRAFFICE TO THE DETOUR OF THE PROPERTY. TRAFFIC. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO SCHEDULE AND PERFORM THE CONSTRUCTION WORK WITHIN THE DETOUR LIMITATION TIME. THE FAILURE OF THE CONTRACTOR TO MEET THE DETOUR LIMITATION DATES WILL CAUSE SEPARATE LIQUIDATED DAMAGES IN ACCORDANCE WITH 108.07 TO BE ASSESSED. THE CONTRACTOR WILL COMPLY WITH ALL PROVISIONS OF 108.07
OF THE DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS.

#### WINTER TRAFFIC LIMITATIONS

ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC BETWEEN NOVEMBER 15 AND APRIL 1. NOVEMBER 14 SHALL BE CONSIDERED TO CONSTITUTE AN INTERIM COMPLETION DATE AND LIQUIDATED DAMAGES AS SPECIFIED IN 108.07 SHALL BE ASSESSED FOR EACH CALENDAR DAY THAT THE ROADWAY REMAINS CLOSED TO TRAFFIC BEYOND THE SPECIFIED LIMIT THE CONTRACTOR MAY CLOSE LANES PRIOR TO APRIL 1 WITH WRITTEN APPROVAL FROM THE DISTRICT CONSTRUCTION ENGINEER.

#### CONTRACTOR'S EQUIPMENT - OPERATION AND STORAGE

A QUALIFIED FLAGGER SHALL BE EMPLOYED WHERE THE CONTRACTOR'S EQUIPMENT MUST MERGE WITH THE TRAFFIC STREAM. THE CONTRACTOR'S EQUIPMENT SHALL BE EQUIPPED WITH AT LEAST ONE AMBER FLASHING LIGHT. PAVERS ROLLERS AND OTHER EQUIPMENT MAY BE PARKED IN AREAS ALONG THE HIGHWAY WHEN PAVING OPERATIONS ARE SCHEDULED TO CONTINUE WITHIN THE NEXT WORKDAY.

OTHERWISE, THE EQUIPMENT SHALL BE STORED AT A STORAGE
AREA OUTSIDE THE R/W, THE LOCATION OF WHICH SHALL
HAVE PRIOR APPROVAL OF THE ENGINEER. WHEN PARKING
ALONG THE HIGHWAY, THE EQUIPMENT SHALL BE PLACED AND ALONG THE HIGHWAY, THE EQUIPMENT SHALL BE PLACED AND DELINEATED AS PER 614.03. NO EQUIPMENT SHALL BE PARKED IN THE MEDIAN OF THE HIGHWAY. ADEQUATE BARRICADES AND LIGHTS SHALL BE PLACED ON THE PAVEMENT SIDE OF THE EQUIPMENT TO IDENTIFY THE LIMITS OF THE EQUIPMENT. ALL OTHER EQUIPMENT, INCLUDING PRIVATE VEHICLES, SHALL BE STORED AT THE APPROVED CONTRACTOR'S STORAGE AREA. NO EQUIPMENT SHALL BE PARKED ON PRIVATE PROPERTY UNLESS PRIOR APPROVAL OF THE OWNER AND THE PROPERTY UNLESS PRIOR APPROVAL OF THE OWNER AND THE PROPERTY UNLESS PRIOR APPROVAL OF THE OWNER AND THE PROJECT ENGINEER/SUPERVISOR HAS BEEN GRANTED.

#### LAW ENFORCEMENT OFFICER WITH PATROL CAR

IN ADDITION TO THE REQUIREMENTS OF 614 AND THE LATEST EDITION OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (OMUTCD), A UNIFORMED LAW ENFORCEMENT OFFICER AND OFFICIAL PATROL CAR WITH WORKING TOP MOUNTED EMERGENCY FLASHING LIGHTS SHALL BE PROVIDED FOR CONTROLLING TRAFFIC AS DIRECTED BY THE ENGINEER FOR THE FOLLOWING TASKS:

- 1. FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED.
- 2. DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.
- 3. DURING A TRAFFIC SIGNAL INSTALLATION.

LAW ENFORCEMENT OFFICERS (L.E.O.'S) SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED. THE LEO'S ARE CONSIDERED TO BE EMPLOYED BY THE CONTRACTOR AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR ACTIONS. ALTHOUGH THEY ARE EMPLOYED BY THE CONTRACTOR, THE PROJECT ENGINEER SHALL HAVE CONTROL OVER THEIR PLACEMENT. THE OFFICIAL PATROL CAR SHALL BE A PUBLIC SAFETY VEHICLE AS REQUIRED BY THE OHIO

THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR THESE SERVICES WITH:

> CANTON PATROL POST 4710 SHUFFEL ROAD NORTH CANTON, OH 44720 PHONE: 330-433-6200

IF AFTER CONTACTING THE OHIO HIGHWAY PATROL, IT IS DETERMINED THAT THEY CANNOT SUPPLY THE LEO, THEN AN AUTHORIZED MUNICIPAL OR COUNTY POLICE OFFICER WITH A MARKED AND FLASHER-LIGHT EQUIPPED OFFICIAL POLICE OR PATROL CAR SHALL BE PROVIDED.

LAW ENFORCEMENT OFFICERS WITH PATROL CAR REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A LUMP SUM BASIS UNDER ITEM 614 MAINTAINING TRAFFIC. THE HOURS PAID SHALL INCLUDE MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

> APPROVED FOR CONSTRUCTION 1/25/08

S

4

EN

AIN

#### PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND REMOVE, WHEN NO LONGER NEEDED, 2 PORTABLE CHANGEABLE MESSAGE SIGNS [PCMS], ON SITE, FOR THE DURATION OF TIME SPECIFIED IN THIS NOTE, EACH SIGN SHALL BE OF A TYPE SHOWN ON A LIST OF APPROVED PCMS UNITS MAINTAINED BY THE DIRECTOR. THIS LIST IS AVAILABLE ON THE ODOT WEBSITE AT HTTP://www.DOT.STATE.OH.US/TESTLAB/APPLISTS/MISC/PCMS.HTM. THE CLASS 1 UNITS SHALL HAVE A MINIMUM LEGIBILITY DISTANCE OF 1250 FEET.

EACH SIGN SHALL BE TRAILER MOUNTED AND EQUIPPED WITH A FUNCTIONAL DIMMING MECHANISM TO DIM THE SIGN DURING DARKNESS AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE OF BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. PCMS TRAILERS SHOULD BE DELINEATED ON A PERMANENT BASIS BY AFFIXING RETROREFLECTIVE MATERIAL, IN A CONTINUOUS LINE ON THE FACE OF THE TRAILER AS SEEN BY ONCOMING ROAD USERS.

0

0

0

PLACEMENT, OPERATION, MAINTENANCE AND ALL ACTIVATION OF THE SIGNS BY THE CONTRACTOR SHALL BE AS DIRECTED BY THE ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE PCMS SHOULD NOT BE LOCATED IN THE MEDIAN OF THE HIGHWAY UNLESS IT IS PROTECTED FROM BOTH DIRECTIONS OF TRAFFIC. THE PCMS SHOULD BE LOCATED BEHIND GUARDRAIL WHEREVER POSSIBLE. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE ENGINEER, RELOCATE THE PCMS TO IMPROVE THE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS WILL BE OFF, FACING AWAY FROM ALL TRAFFIC AND SHALL DISPLAY ONE OR MORE HIGH INTENSITY YELLOW REFLECTIVE SHEETING SURFACES OF 9-INCH BY 15-INCH MINIMUM SIZE FACING TRAFFIC.

THE ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT AND TO REVISE SIGN MESSAGES, IF NECESSARY.

ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE CONTRACTOR. A LIST OF ALL PROPOSED PREPROGRAMMED MESSAGES WILL BE GIVEN TO THE ENGINEER PRIOR TO CONSTRUCTION. THE SIGN SHALL HAVE TWO DIFFERENT MEMORIES IPROM AND RAMI AND CAPABILITY TO STORE UP TO 99 MESSAGES IN EACH MEMORY. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS SHALL NOT BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. IN ORDER TO CONVEY A MAXIMUM OF INFORMATION AT A SINGLE GLANCE, ONLY THREE LINE PRESENTATION FORMATS WITH A MAXIMUM OF SIX MESSAGE PHASES WILL BE PERMITTED. NORMALLY, ONLY A MAXIMUM OF THREE MESSAGE PHASES SHOULD BE EMPLOYED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ AT LEAST ONCE.

THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DE-ACTIVATED OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.

THE PCMS SHALL CONTAIN A CELLULAR TELEPHONE DATA LINK WHICH WILL IIN ACTIVE CELLULAR AREASI ALLOW REMOTE SIGN ACTIVATION, DEACTIVATION, MESSAGE CHANGES, MESSAGE ADDITIONS AND REVISIONS TO TIME OF DAY PROGRAMS. THE SYSTEM SHALL ALSO PERMIT VERIFICATION OF CURRENT AND PROGRAMMED MESSAGES.

#### (CONTINUED...)

THE PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF 614. THE CONTRACTOR SHALL PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS WITH AN AUTHORIZED SERVICE AGENT FOR THE PCMS TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT IN THE SIGN BEING OUT OF SERVICE FOR MORE THAN 12 HOURS INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL TRAFFIC AND THE ENTIRE COST TO CONTROL TRAFFIC ACCRUED BY THE DEPARTMENT WILL BE DEDUCTED FROM MONEYS DUE, OR TO BECOME DUE THE CONTRACTOR ON HIS CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24 HOURS PER DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES. THE REQUIREMENT TO FURNISH, INSTALL, MAINTAIN AND REMOVE A PCMS UNIT ON THIS PROJECT SHALL NOT IN ANY WAY RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITIES AS OUTLINED IN 614.02.

PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC AND SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.

#### PORTABLE CONCRETE BARRIER. 32"

THIS WORK SHALL CONSIST OF FURNISHING, INSTALLING, MAINTAINING, AND SUBSEQUENTLY REMOVING A 32" PORTABLE CONCRETE BARRIER AT THE LOCATIONS PROVIDED IN THE PLAN. FOR DETAILS, SEE STANDARD CONSTRUCTION DRAWING RM-4.2.

PORTABLE CONCRETE BARRIER, 32" HIGH, WITH AN 18" MINIMUM HEIGHT GLARE SCREEN MAY BE USED AT THE OPTION OF THE CONTRACTOR. THE GLARE SCREEN SHALL BE CONSTRUCTED USING ONE (1) OF THE APPROVED SYSTEMS LISTED ON ODOT'S WEBSITE AT HTTP://WWW.DOT.STATE.OH.US/TESTLAB/APPLISTS/MISC/GLARESCREEN.HTM.

PADDLE OR INTERMITTENT TYPE GLARE SCREENS SHALL BE DESIGNED USING A 20 DEGREE CUT OFF ANGLE BASED ON TANGENT ALIGNMENT. THAT SPACING SHALL BE USED THROUGHOUT THE BARRIER LENGTH WITHOUT REGARD TO THE BARRIER CURVATURE.

THE GLARE SCREEN SYSTEM SHALL BE SECURELY FASTENED TO THE 32" PORTABLE CONCRETE BARRIER USING THE HARDWARE AND PROCEDURES SPECIFIED BY THE MANUFACTURER.

PORTABLE CONCRETE BARRIER WHICH HAS BEEN DAMAGED BEYOND REPAIR BY TRAFFIC SHALL BE REPLACED BY THE CONTRACTOR WITHIN TWENTY FOUR (24) HOURS OF THE INCIDENT WHICH CAUSED THE DAMAGE. REPLACEMENT BARRIER SHALL BE AS PER SECTION 622.04 OF THE SPECIFICATIONS.

PAYMENT SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO PERFORM THIS WORK AND SHALL BE PAID FOR ON A LUMP SUM BASIS UNDER ITEM 614 MAINTAINING TRAFFIC.

#### BARRIER REFLECTORS AND OBJECT MARKERS

BARRIER REFLECTORS AND OBJECT MARKERS SHALL BE INSTALLED ON ALL PORTABLE CONCRETE BARRIER USED FOR TRAFFIC CONTROL. BARRIER REFLECTORS, OBJECT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO THE APPROPRIATE PROPOSAL NOTE AND CMS 626 EXCEPT THAT THE SPACING SHALL BE 25 FEET. PAYMENT FOR ALL WORK AND MATERIALS REQUIRED TO ACCOMPLISH THIS TASK SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

#### NOTICE OF CLOSURE SIGNS

THESE SIGNS SHALL BE ERECTED BY THE CONTRACTOR AT LEAST ONE WEEK IN ADVANCE OF THE SCHEDULED ROAD OR RAMP CLOSURE. THE SIGNS SHALL BE ERECTED ON THE RIGHT HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE LOCATED IN THE FIELD SO AS NOT TO INTERFERE WITH ANY PERMANENT SIGNS. ON ROADWAYS THEY SHOULD BE ERECTED AT THE POINT OF CLOSURE. ON RAMPS THE SIGNS MAY BE ERECTED ANYWHERE ALONG IT; AS LONG AS THE SIGNS ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS THE SIGNS MAY BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING THE MOTORISTS.

PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE LUMP SUM BID ITEM 614 MAINTAINING TRAFFIC AND SHALL INCLUDE FURNISHING, ERECTING, MAINTAINING AND REMOVING THE SIGNS, INCLUDING SUPPORTS.

#### COVERING OF SIGNS

WHERE THE PLANS CALL FOR A PERMANENT SIGN TO BE COVERED, THE CONTRACTOR SHALL DO SO IN SUCH A MANNER AS TO AVOID DAMAGING THE PERMANENT SIGN WHEN THE COVER IS REMOVED. THE COVER SHALL BE TOTALLY OPAQUE. THE USE OF ADHESIVE TAPE APPLIED DIRECTLY TO A SIGN FACE IS STRICTLY PROHIBITED. THE CONTRACTOR SHALL PROVIDE ALL OF THE "CLOSED" PLAQUES NECESSARY.

#### STOPPAGE OF MAINLINE TRAFFIC (S.R. 21)

ANY TIME TRAFFIC MUST BE COMPLETELY STOPPED ON A FREEWAY OR INTERSTATE, IT SHALL BE DONE IN THE FOLLOWING MANNER: THE COMPLETE TRAFFIC STOPPAGE ON ALL LANES OF ANY DIRECTIONAL ROADWAY SHALL BE NO MORE THAN 10 MINUTES IN ANY ONE CONSECUTIVE 30 MINUTE PERIOD.

A MINIMUM OF TWO (2) LAW ENFORCEMENT OFFICERS (LEO) WITH PATROL CARS SHALL BE USED TO PACE MOTORISTS TO A STOP. THERE SHALL BE ONE LEO FOR EACH LANE ON THE FREEWAY.

AFTER TRAFFIC HAS BEEN SLOWED, ONE (1) PATROL CAR SHALL TRAVEL ALONG THE ROADWAY SHOULDER 500 FEET BEHIND THE BACKUP OF STOPPED VEHICLES. WHERE STOPPAGE OCCURS IN THE VICINITY OF FREEWAY ENTRANCES, THE CONTRACTOR SHALL PLACE FLAGGERS ON THE RAMPS TO STOP TRAFFIC. PATROL CARS SHALL HAVE FLASHING BEACONS TO PROVIDE ADEQUATE VISIBILITY TO APPROACHING MOTORISTS.

THE CONTRACTOR/PERMITTEE SHALL ERECT AND MAINTAIN "ROAD WORK AHEAD" (W20-1-48) ONE MILE AHEAD OF THE STOP LOCATION, "PREPARE TO STOP" (W3-H5-48) 3/4 MILE AHEAD OF THE STOP LOCATION, AND "STOP AHEAD" (W3-IA-48) SIGNS 1/4 MILE AHEAD OF THE STOP LOCATION. EACH SIGN SHALL BE EQUIPPED WITH A TYPE B FLASHING BARRICADE WARNING LIGHT IN ACCORDANCE WITH SECTION 7G-6 OF THE OMUTCD.

A PORTABLE CHANGEABLE MESSAGE SIGN, TYPE TO BE ON ODOT'S PREAPPROVED LIST, SHALL BE PLACED 1.5 TO 2 MILES IN ADVANCE OF THE CLOSURE OR AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER/PERMIT OFFICE AND THE ODOT PUBLIC INFORMATION OFFICE, 330-786-2211, THREE (3) DAYS PRIOR TO ANY MAINLINE TRAFFIC STOPPAGE.

#### TRAFFIC CONTROL INSPECTOR

THE CONTRACTOR SHALL DESIGNATE AN INDIVIDUAL OTHER THAN THE SUPERINTENDENT AND SUBJECT TO THE APPROVAL OF THE ENGINEER, TO CONTINUOUSLY INSPECT ALL TRAFFIC CONTROL DEVICES WHENEVER CONSTRUCTION WORK IS BEING PERFORMED WITHIN THE WORK LIMITS OF THE PROJECT. THE DESIGNATED INDIVIDUAL SHALL ALSO INSPECT ALL TRAFFIC DEVICES AT THE BEGINNING AND AT THE END OF EACH WORK DAY. THE DESIGNATED INDIVIDUAL OR A QUALIFIED REPRESENTATIVE SHALL ALSO BE AVAILABLE ON AN AROUND THE CLOCK BASIS TO REPAIR AND/OR REPLACE DAMAGED OR MISSING TRAFFIC CONTROL DEVICES. THESE INDIVIDUALS SHALL BE EQUIPPED WITH CELLULAR PHONES AND THEIR NAMES AND PHONE NUMBERS SHALL BE GIVEN TO THE PROJECT ENGINEER AT THE PRE-CONSTRUCTION MEETING. THE DESIGNATED INDIVIDUAL MAY HAVE OTHER CONSTRUCTION RELATED DUTIES AS LONG AS IMMEDIATE ATTENTION IS GIVEN TO TRAFFIC CONTROL. PAYMENT FOR THE SERVICES OF THE TRAFFIC CONTROL INSPECTOR SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

#### FLOODLIGHTING

FLOODLIGHTING OF THE WORK SITE FOR OPERATIONS CONDUCTED DURING NIGHTTIME PERIODS SHALL BE ACCOMPLISHED SO THAT THE LIGHTS DO NOT CAUSE GLARE TO THE DRIVERS ON THE ROADWAY. TO ENSURE THE ADEQUACY OF THE FLOODLIGHT PLACEMENT, THE CONTRACTOR AND THE ENGINEER SHALL DRIVE THROUGH THE WORK SITE EACH NIGHT WHEN THE LIGHTING IS IN PLACE AND OPERATIVE PRIOR TO COMMENCING ANY WORK. IF GLARE IS DETECTED, THE LIGHT PLACEMENT AND SHIELDING SHALL BE ADJUSTED TO THE SATISFACTION OF THE ENGINEER BEFORE WORK PROCEEDS.

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC.

APPROVED FOR CONSTRUCTION 1/25/08

#### WORK ZONE RAISED PAVEMENT MARKERS (ASPHALT)

WORK ZONE RAISED PAVEMENT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO CMS 614 OR CMS 621 AS SPECIFIED HEREIN. RAISED PAVEMENT MARKERS IN USE DURING THE SNOW-PLOWING SEASON SHALL CONFORM TO 621. RAISED PAVEMENT MARKERS IN USE DURING THE NON-SNOW-PLOW SEASON SHALL CONFORM TO EITHER 614

THE SNOW-PLOWING SEASON SHALL RUN FROM NOVEMBER 1 THROUGH MARCH 30.

IF PROJECT DELAYS, NOT THE FAULT OF ODOT, CAUSE THE WORK TO EXTEND INTO THE SNOW-PLOWING SEASON, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING WORK ZONE RAISED PAVEMENT MARKERS (WZRPMS) CONFORMING TO CMS 614, WITH RAISED PAVEMENT MARKERS CONFORMING TO 621, AS DETERMINED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE

THIS ITEM SHALL INCLUDE PURCHASE, INSTALLATION AND REMOVAL OF ITEM 614 WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN, INCLUDING FILLING OF ANY DEPRESSIONS CREATED IN THE PAVEMENT AS PER CMS

0

RESURFACING OF THE TRANSITION AREAS SHALL BE PERFORMED AT THE TIME THAT THE SURFACE COURSE IS BEING APPLIED TO THE ENTIRE PROJECT. PRIOR TO APPLICATION OF THE SURFACE COURSE ON THE PROJECT THE SURFACE COURSE OF THE EXISTING PAVEMENT WITHIN THE TRANSITION AREA SHALL BE REMOVED TO A DEPTH EQUIVALENT TO THE DEPTH OF THE PROPOSED SURFACE COURSE, AS DETERMINED BY THE ENGINEER.

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

#### WORK ZONE RAISED PAVEMENT MARKERS ON CONCRETE SURFACES

RAISED PAVEMENT MARKERS IN WORK ZONES, INSTALLED ON TO CONCRETE SURFACES, SHALL BE ITEM 614 WORK ZONE RAISED PAVEMENT MARKERS. WZRPMS ARE INTENDED FOR USE ONLY DURING THE NON-SNOW-PLOWING SEASON. WZRPMS SHALL NOT BE PROVIDED DURING THE SNOW-PLOWING

THE SNOW-PLOWING SEASON SHALL RUN FROM NOVEMBER 1

WHERE A TEMPORARY ALIGNMENT WILL REMAIN IN USE THROUGH THE WINTER, THE WZRPMS SHALL BE REMOVED PRIOR TO THE BEGINNING OF THE SNOW-PLOWING SEASON AND REPLACED APPROXIMATELY APRIL 1, OR AS OTHERWISE DETERMINED BY THE ENGINEER.

THIS ITEM SHALL INCLUDE PURCHASE, INSTALLATION AND REMOVAL OF ITEM 614 WORK ZONE RAISED PAVEMENT

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE BID FOR ITEM 614 MAINTAINING TRAFFIC.

#### ITEM 614, WORK ZONE IMPACT ATTENUATOR FOR 24' WIDE HAZARDS (UNIDIRECTIONAL OR BIDIRECTIONAL)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ONE OF THE FOLLOWING IMPACT ATTENUATORS:

1. THE QUADGUARD CZ, (24 INCHES WIDE SIX-BAY) WORK ZONE IMPACT ATTENUATOR MANUFACTURED BY ENERGY ABSORPTION SYSTEMS, INC., 35 EAST WACKER DRIVE, CHICAGO, IL 60601 (TELEPHONE: 312-467-6750).

THE LENGTH OF THE SIX-BAY QUADGUARD CZ IS 20'-9". INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AS DETAILED ON THE FOLLOWING PRE-APPROVED SHOP DRAWINGS:

DRAWING NUMBER	DRAWING NAME	DRAWING/ REVISION DATE	
QSCZCVR-T4	QUADGUARD CZ SYSTEM FOR CONSTRUCTION ZONES	5/13/99 REV. J	8/27/99
35-40-10	QUADGUARD SYSTEM CONCRETE PAD, CZ, QG	11/19/97 REV. D	8/27/99
35-40-16	QUADGUARD SYSTEM BACKUP ASSEMBLY, CZ, QG	7/30/99 REV. F	8/27/99
354051Z	QUADGUARD CZ SYSTEM NOSE ASSEMBLY, CZ, QG, 24, 30, 36	5/17/99	8/27/99
35-40-18	TRANSITION ASSEMBLY, 4 OFFSET, QG	6/25/99 REV. F	8/27/99
35400260	QUADGUARD SYSTEM PCMB ANCHOR ASSEMBLY	11/19/97 REV. C	8/27/99

2. THE TRACC (TRINITY ATTENUATING CRASH CUSHION) MANUFACTURED BY TRINITY INDUSTRY, 1170 N. STATE STREET, GIRARD, OHIO 44420 (TELEPHONE: 330-545-4373).

THE TRACC IS 21'-0" LONG AND 2'-7" WIDE.
INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN
THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AS DETAILED ON THE FOLLOWING PRE-APPROVED SHOP DRAWINGS:

DRAWING NUMBER	DRAWING NAME	DRAWING/ REVISION DATE	
SS450	CRASH-CUSHION ATTENUATING TERMINAL	3/12/99 REV. 1	8/27/99
SS455	TRACC TRANSITION TO W-BEAM MEDIAN	2/18/99	8/27/99
SS461	TRACC TRANSITION TO CONCRETE SAFETY	6/30/99 REV. 1	8/27/99
SS462	TRACC TRANSITION TO CONCRETE BARRIER	6/30/99	8/27/99

3. THE BARRIER SYSTEMS, INC. TAU-II IMPACT ATTENUATOR, DISTRIBUTED BY ROAD SYSTEMS INC., SALES SUPPORT, 2183 ELM TRACE, AUSTINTOWN, OH 44515, (TELEPHONE

THE TAU-II FOR THIS NOTE IS A PARALLEL 8-BAY UNIT (24' LONG AND 35" WIDE). INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AS DETAILED ON THE FOLLOWING PRE-APPROVED SHOP

DRAWING NUMBER	DRAWING NAME	DRAWING/ REVISION DATE	
A040416	UNIVERSAL TAU-II PARTS LIST	4/22/04	10/16/04
A040420	UNIVERSAL TAU-II FOUNDATION, FLUSH MOUNTED BACKSTOP	4/28/04	10/16/04
A040105	UNIVERSAL TAU-II FOUNDATION, PCB BACKSTOP (REFERENCED ON A04020)	1/07/04	10/16/04
B040239	APPLICATION, FLUSH MOUNTED BACKSTOP (TYPICAL FOR PARALLEL 60MPH UNIT)	4/21/04	10/16/04

(CONTINUED...)

4. THE GREAT CZ IMPACT ATTENUATOR MANUFACTURED BY ENERGY ABSORPTION SYSTEMS. INC.

THIS ATTENUATOR MAY BE USED UNTIL JANUARY 1, 2007 IF THE ITEM WAS PURCHASED BEFORE OCTOBER 1, 1998 AND IS IN THE CONTRACTOR'S INVENTORY.


THE CONTRACTOR SHALL PROVIDE A REPLACEMENT UNIT WHEN AN IMPACT IS SEVERE ENOUGH TO REQUIRE COMPLETE REPLACEMENT OF THE ATTENUATOR. THE CONTRACTOR SHALL HAVE A SPARE PARTS PACKAGE AVAILABLE ON THE PROJECT SITE AT ALL TIMES WHEN AN ATTENUATOR IS IN PLACE. THE CONTRACTOR SHALL PROVIDE A MINIMUM OF ONE COMPLETE SPARE PARTS PACKAGE FOR EVERY ONE TO SIX UNITS INSTALLED ON THE PROJECT SITE. FOR EXAMPLE, FIVE INSTALLED UNITS REQUIRE ONE SPARE PARTS PACKAGE AND SEVEN INSTALLED UNITS REQUIRE TWO SPARE PARTS PACKAGES.

WHEN BIDIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS.
PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE
UNIT PRICE BID AND SHALL INCLUDE ALL LABOR, TOOLS,
EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT, MAINTAIN AND REPAIR A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

#### COOPERATION BETWEEN CONTRACTORS


THE CONTRACTOR SHALL COOPERATE WITH AND COORDINATE HIS OPERATIONS PER CMS SECTION 105.08 WITH THE CONTRACTOR FOR PROJECT STA-21-8.25/12.39 WHICH WILL BE UNDER CONSTRUCTION CONCURRENTLY. ALL COORDINATION ISSUES SHALL BE BROUGHT TO THE ATTENTION OF AND RESOLVED WITH THE APPROVAL OF THE PROJECT ENGINEER.

> APPROVED FOR CONSTRUCTION 1/25/08



STA

APPROVED FOR CONSTRUCTION 1/25/08




S.R. 21 - PHASING TYPICAL


NON-WORK ZONE ACTIVITIES AND NIGHTTIME TREATMENT

 $\bigcirc$ 

0

 $\bigcirc$ 





0

0

10 HORIZONTAL SCALE IN FEET

CKED ST


SAH CHECKED ZRD

AN SHEET

ROADWAY PLAN S.R. 21


A-21-8.98

7





- ITEM 204 SUBGRADE COMPACTION
- ITEM 301 9" ASPHALT CONCRETE BASE, PG 64-22
- ITEM 304 6" AGGREGATE BASE, AS PER PLAN
- ITEM 407 TACK COAT (APPLIED AT 0.075 GAL./S.Y.)
- ITEM 407 TACK COAT FOR INTERMEDIATE COURSE (APPLIED AT 0.040 GAL./S.Y.)
- ITEM 408 PRIME COAT (APPLIED AT 0.40 GAL./S.Y.)
- ITEM 448 11/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22
- ITEM 448 13/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22
- 9) ITEM 622 CONCRETE BARRIER, TYPE B1



APPROVED FOR CONSTRUCTION 1/25/08

### EXISTING LEGEND

## S.R. 21 MEDIAN BARRIER DETAIL

STA. 474+14.00 TO STA. 474+65.00

- (A) EXISTING 9"± REINFORCED CONCRETE PAVEMENT
- EXISTING 6"± AGGREGATE BASE
- (C) EXISTING 3"± ASPHALT CONCRETE


0

0

 $\bigcirc$ 

≥


Ш



NORMAL 32 INCH SECTIONS

"W" = 6" [152] or 12" [305] barrier width, as specified in the plans.

All metric dimensions (in brackets []) are otherwise noted.



0

0

0

0

32" [813-mm] BARRIER BARRIER ELEVATION

JOINTS: Unsealed contraction joints spaced at 20' [6 m] maximum shall be constructed throughout the run of Concrete Barrier except that expansion joints shall be used at the center line of and around each bridge pier column and on either side of overhead sign supports, inlets and light pole foundations. If the inlet top is slip formed, the expansion joints adjacent to it may be omitted.

Contraction joints may be constructed with metal inserts inside the forms, preformed full width joint filler, a grooving tool, or by sawing. Inserts, tooled joints, and sawed joints shall have a 3" [75] minimum depth. All joints shall be constructed for the full height of the barrier including the footing. Sawing shall be done as soon as curing will allow, to prevent spalling.

FOOTING JOINTS: The vertical walls between the barrier footing and a concrete pavement or concrete base shall be provided with a sealed joint as shown on Sheet 2. Sealing material shall conform to CMS 705.04.

PCJ = Permissible Construction Joint

MEASUREMENT: Item 622, Concrete Barrier, including transitions and pier sections as detailed on the New Jersey Shape Barrier Transition drawing, is paid for in linear feet [meters] as one of the four types (A, B, C or D) or as Type A1 and B1, (for 50" [1270] high barrier), with appropriate deductions for other items such as:

Item 604 - I-3 Median Inlet

Item 625 - Light Pole Foundation or Pullbox Item 630 - Overhead Sign Support Foundation Item 630 - Barrier Wall Assembly

20 Lin Ft. [6 Meters]. 2.5 Lin. Ft. [1 Meter]. 10 Lin. Ft. [3 Meters]. 10 Lin. Ft. [3 Meters].

NOTES

TRANSITIONS: Linear transitions between the different types of barrier detailed on this Standard Drawing shall occur between contraction joints spaced no closer than 10' [3 m].

RACEWAY: The contractor shall ensure that the electrical raceway is clear of internal obstructions. Cost of the 4"[100] polyvinyl chloride raceway and No. 10 AWG copper-clad or aluminum-clad wire if needed for future installation of circuits shall be included in the unit cost per Linear Foot [Meter] for Item 622 - Concrete Barrier, Type \_\_\_\_.

STATION MARKING: The Station marking shall be impressed in the "green" concrete on both sides at the top of the barrier if specified in the plans. The cost shall be incidental to the unit cost per Linear Foot [Meter] bid for Item 622 - Concrete Barrier,

REFLECTORIZATION: Barrier reflectorization shall be installed in accordance with CMS 626.


#### LEGEND


APPROVED FOR CONSTRUCTION 1/25/08

1" [25] radius or 3/4" [19] chamfer.

2 Permissible 10" [250] radius.
3 Permissible 1" [25] radius.
4 #8 [#25M] epoxy coated Deformed Steel Bars, 1'-0" [305] long, spaced 4'-0" [1220] between successive Bars on a staggered pattern except in Type D. Omit Dowels when the top is constructed integrally with the Base.








#### 50" [1270-mm] BARRIERS - TYPICAL SECTIONS

See Type A and Type B Normal Section Details (Sheet 1) for dimensions that are not shown.



All metric dimensions (in brackets []) are in millimeters unless otherwise noted.




0

0

0

0

50" [1270-mm] BARRIER BARRIER ELEVATION



FOOTING JOINT DETAIL
See FOOTING NOTE on Sheet 1.

NOTES

50" [1270-mm] BARRIER: High barrier shall be built in locations specified in the plans. Construct the lower 32" [813] of the barrier base using the same dimensions as as shown in the corresponding Normal Section on Sheet 1. The upper 18" [457] may be constructed integrally with the bottom, or separately with #4 [#13M] rebar dowels at 4'-0" [1220] maximum spacing.

Start and end dowels 6" [150] from barrier contraction joints.

APPROVED FOR CONSTRUCTION 1/25/08


LEGEND
% "[19] chamfer.

- 1 1" [25] radius or ¾" [19] chamfer.
  2 Permissible 10" [250] radius.
- 3 Permissible 1" [25] radius.
- 4 #8 [#25M] epoxy coated deformed Steel Bars, 1'-0" [305] long, spaced 4'-0" [1220] between successive Bars on a staggered pattern except in Type D. Omit Dowels when the top is constructed integrally with the Base.

SAH CHECKED PDL

4" [100] Raceway, when required in the plans.

7" [178] (Typ.)



36" [915]

SECTION A-A

9" [230]

All metric dimensions (in brackets []) are in millimeters unless

#### NOTES

STANDARD BARRIERS: Types A, B, and C Concrete Barriers shall be constructed as shown on the New Jersey Shape Barrier insert or as detailed in the plans.


#### LEGEND

APPROVED FOR CONSTRUCTION 1/25/08

1" [25] radius or ¾" [19] chamfer.


Bridge Pier Column

- Permissible 10" [250] radius.
- Permissible 1" [25] radius.
- #8 [#25M] epoxy coated deformed Steel Bars, 12" [300] long, spaced 2' [600] between successive Bars on a staggered pattern. Dowel Bars shall begin 4' [1220] from the leading edge of the End Terminal. Omit Dowels when the top is constructed integrally
- 5 Expansion Joint, 3/4" [19] min. Preformed Filler, CMS 705.03.



#### SIGN SUPPORT TRANSITION

(For 50" [1270] Barriers, the upper 18" [457] varies from 6" or 12" [152 or 305] to 36" [915] in width.)



PLAN

### BRIDGE PIER TRANSITION

(With Sign Support)

 $\bigcirc$ 

0

0

0

#### REFERENCE SHALL BE MADE TO:

STANDARD DRAWINGS

SUPPLEMENTAL SPECIFICATIONS

#### DESIGN DATA

DESIGN LOADING:

HS25, CASE II AND ALT. MILITARY LOADING (SUPERSTRUCTURE) HS20-44 & ALT. MILITARY LOADING (WIDENED SUBSTRUCTURE) ORIGINAL HS15-44/CF-400 LOADING (SUBSTRUCTURE TO REMAIN)

FUTURE WEARING SURFACE (FWS) OF 60 PSF

CONCRETE CLASS 'C': COMPRESSIVE STRENGTH 4000 PSI (SUBSTRUCTURE)

REINFORCING STEEL: ASTM A615 OR A996 GRADE 60 MINIMUM YIELD STRENGTH 60,000 PSI. SPIRAL REINFORCEMENT MAY BE PLAIN BARS, ASTM A82 OR A615.

#### PROPOSED WORK

1. INSTALL NEW FOOTING AND COLUMN AT EACH PIER.

#### UTILITY LINES

THE UTILITIES SHALL BEAR ALL EXPENSE INVOLVED IN RELOCATING (INSTALLING) THE AFFECTED UTILITY LINES. THE CONTRACTOR AND UTILITIES ARE TO COOPERATE BY ARRANGING THEIR WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

#### FOUNDATION BEARING PRESSURE:

PIER FOOTINGS, AS DESIGNED, PRODUCE A MAXIMUM BEARING PRESSURE OF 2.0 TONS PER SQUARE FOOT. THE ALLOWABLE BEARING PRESSURE IS 2.0 TONS PER SQUARE FOOT.

#### FOOTING REFERENCE MONUMENTS

IN ADDITION TO THE REQUIREMENTS OF ITEM 511, INSTALL A REFERENCE MONUMENT AT EACH END OF EACH SPREAD FOOTING. THE REFERENCE MONUMENT SHALL CONSIST OF A #8, OR LARGER, EPOXY COATED REBAR EMBEDDED AT LEAST 6" INTO THE FOOTING AND EXTENDED VERTICALLY 4 TO 6 INCHES ABOVE THE TOP OF THE FOOTING. INSTALL A SIX INCH DIAMETER, SCHEDULE 40, PLASTIC PIPE AROUND THE REFERENCE MONUMENT. CENTER THE PIPE ON THE REFERENCE MONUMENT AND PLACE THE PIPE VERTICAL WITH ITS TOP AT THE FINISHED GRADE. THE PIPE SHALL HAVE A REMOVABLE, SCHEDULE 40, PLASTIC CAP. PERMANENTLY ATTACH THE BOTTOM OF THE FIPE TO THE TOP OF THE FOOTING. THE PIPE TO THE TOP OF THE FOOTING.

ESTABLISH A BENCHMARK TO DETERMINE THE ELEVATIONS OF THE REFERENCE MONUMENTS AT VARIOUS MONITORING PERIODS THROUGHOUT THE LENGTH OF THE CONSTRUCTION PROJECT. THE BENCHMARK SHALL BE THE SAME THROUGHOUT THE PROJECT AND SHALL BE INDEPENDENT OF ALL STRUCTURES.

RECORD THE ELEVATION OF EACH REFERENCE MONUMENT AT EACH MONITORING PERIOD SHOWN IN THE TABLE BELOW.

THE ORIGINAL COMPLETED TABLES WILL BECOME PART OF THE DISTRICT'S PROJECT PLAN RECORDS. SEND A COPY OF THE COMPLETED TABLES TO THE OFFICE OF STRUCTURAL ENGINEERING.

PROJECT NUMBER: 073000	MAXIMUM BEARING F	PRESSURE: 2.0 TSF				
BRIDGE NUMBER: STA-21-0898	STRUCTURE FILE NUMBER: 7600151					
BENCHMARK LOCATION:						
FOOTING LOCATION: NORTH COLUMN, PI	ER #1					
MONITORING PERIOD	LEFT MONUMENT	RIGHT MONUMENT				
AFTER FOOTING CONCRETE IS PLACED						
BEFORE PLACEMENT OF						
SUPERSTRUCTURE MEMBERS						
BEFORE DECK PLACEMENT		***************************************				
AFTER DECK PLACEMENT						
PROJECT COMPLETION						

PROJECT NUMBER: 073000	MAXIMUM BEARING F	PRESSURE: 1.9 TSF			
BRIDGE NUMBER: STA-21-0898	STRUCTURE FILE NUMBER: 7600151				
BENCHMARK LOCATION:					
FOOTING LOCATION: NORTH COLUMN, P.	IER #2				
MONITORING PERIOD	LEFT MONUMENT	RIGHT MONUMENT			
AFTER FOOTING CONCRETE IS PLACED					
BEFORE PLACEMENT OF					
SUPERSTRUCTURE MEMBERS					
BEFORE DECK PLACEMENT					
AFTER DECK PLACEMENT					
PROJECT COMPLETION					

DDO ICCT MUMBER 077000	<del></del>				
PROJECT NUMBER: 073000	MAXIMUM BEARING PRESSURE: 1.8 TSF				
BRIDGE NUMBER: STA-21-0898	STRUCTURE FILE NUMBER: 7600151				
BENCHMARK LOCATION:					
FOOTING LOCATION: NORTH COLUMN, PI	ER #3				
MONITORING PERIOD	LEFT MONUMENT	RIGHT MONUMENT			
AFTER FOOTING CONCRETE IS PLACED					
BEFORE PLACEMENT OF					
SUPERSTRUCTURE MEMBERS					
BEFORE DECK PLACEMENT					
AFTER DECK PLACEMENT					
PROJECT COMPLETION					

PAYMENT FOR ALL OF THE ABOVE TO BE INCLUDED WITH ITEM SPECIAL - STRUCTURE REHABILITATION.

#### **ABBREVIATIONS**

N.S	5	NEAR SIDE	MAX.	-	MAXIMUM	
F.5	ŝ	FAR SIDE	MIN.	_	MINIMUM	
R.A	4	REAR ABUTMENT	SPA.	-	SPACES	
F.A	1	FORWARD ABUTMENT	ST'D. DI		STANDARD DRAWING	
R.F	· -	REAR PIER	C.	-	CENTERLINE	
F.F	· -		€ F/F	_	FACE TO FACE	
CLI		CLEARANCE	0/0	_	OUT TO OUT	
DIA		DIAMETER	C/C	-	CENTER TO CENTER	
TY		TYPICAL	YR.	-	YEAR	
STA		STATION	O.R.	-	OUTSIDE RADIUS	
F	_	FLOW LINE	I.R.	-	INSIDE RADIUS	
EL.	-	ELEVATION	C.R.	_	COUNTY ROAD	
ELE		ELEVATION	T.R.	-	TOWNSHIP ROAD	
FWL		FORWARD	L.F.	_	LEFT FORWARD	
BRO		BEARING	R.F.	_	RIGHT FORWARD	
LB.		POUND	H.S.			
BN7		BENT	CVN	2. <del>55</del> .	HIGH STRENGTH	
STA		STRAIGHT		-	CHARPY V-NOTCH	
			CONST.	-	CONSTRUCTION	
LT.		LEFT	C.I.P.	-	CAST-IN-PLACE	
RT.		RIGHT			REINFORCED CONCRETE	
PSI	-	POUND/SQ. FT.	<i>TSF</i>	-	TON/SQ.FT.	

APPROVED FOR CONSTRUCTION 1/25/08

0

ST

21-8.98

V


VOTES - BUILDABLE I STA-21-0898 OVER S.R. 21

GENERAL NOTES

BRIDGE NO. :

OUICKSALL & ASSOCIATES, 554 WEST HIGH AVE. NEW PHILADELPHIA, OHIO CIVIL, ENGINEERS

12



0

0

BM-A, ELEV. = 996.42


"X" SET IN TOP OF CONC. FENCE POST BASE AT END OF LA R/W FENCE @ S.E. QUADRANT OF S.R. 21 & ERIE ST. INTERCHANGE.

BM-B, ELEV. = 987.00 CHISELED SQUARE ON S.E. CORNER OF


CONC. HEADWALL @ NORTH SIDE OF BURGER KING PARKING LOT AT S.W. QUADRANT OF S.R. 21 & ERIE ST. INTERCHANGE.

STA. 30+46.63 - OFF. 68.94' RT. ERIE ST.

STA. 21+77.27 - OFF. 121.11' RT. ERIE ST



SECTION B-B (PIER COLUMN)



#### VIEW A-A

NOTES:

- 1. P901, P902 & P903 COLUMN BARS SHALL EXTEND UP TO BOTTOM OF TOP LONGITUDINAL MAT OF REINFORCING STEEL IN CAP. BARS SHALL BE PLACED AS SHOWN TO NOT INTERFERE WITH PROPER PLACEMENT OF REINFORCING IN
- 2. ASSURE SPIRALS EXTEND FROM THE TOPS OF FOOTINGS TO THE LEVEL OF THE LOWEST HORIZONTAL REINFORCEMENT IN THE CAPS (21/2" ABOVE BOTTOM OF CAP).


APPROVED FOR CONSTRUCTION 1/25/08

W.E. OUICKSALL & ASSOCIATES, SEA WEST HIGH AVE. NEW PHILADELPHIA, OHIO CIVIL ENGINEERS

BUILDABLE UNIT #1 DETAIL
BRIDGE NO. STA-21-0898
ERIE STREET OVER S.R. 21

98 A-21-8 »

PD ST



		A	IUMBER			Ī .	Т	Г						
MARK					LENGTH	WEIGHT	TYPE			D	IMENSIC	ONS .		
	PIER #1	PIER #2	PIER #3	TOTAL			_	A	В	С	D	E	R	INC
					F	PIERS								
P601	12	12	12	36	8'- 2"	442	STR			<del> </del>		+		-
												1		
P701	16	16	16	48	9'- 8"	948	17	8'-2"						
P901				10	29'- 2"	992	16	27'-11 ½"			-	-	-	-
P902		10		10	20'- 5"	694	16	19'-2"			<del> </del>	<del>                                     </del>	<del> </del>	-
P903				10	24'- 11"	847		23'-8 1/4"		-			-	-
P904	10	10	10	30	9'- 11"	1012	1		8'-7 1/2"					
SP401	1			1	529'- 3"	354	27	0'-4 1/2"	2'-6"	24'-6"			-	
SP402		1		1 1	341'- 7"	228	27	0'-4 1/2"	2'-6"	15'-5"			-	
SP403			1	1 1	436'- 3"	291	27	0'-4 1/2"	2'-6"	20'-0"		<u> </u>		
													ļ	
							-						-	
												-		
							$\dashv$							
							$\neg$							
							_							
							$\dashv$							
							$\dashv$							
							$\dashv$							
							$\perp$							
							$\dashv$							
							-							
							$\dashv$							
							$\top$							

- BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED, AND THE FIRST TWO DIGITS WHERE FOUR ARE USED, INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE, A701 IS A NO. 7 AND A1014 IS A NO. 10 SIZE. BAR DIMENSIONS SHOWN ARE OUT TO OUT UNLESS OTHERWISE INDICATED. "R" INDICATES INSIDE RADIUS, UNLESS OTHERWISE NOTED. "STD" WRITTEN IN PLACE OF A DIMENSION INDICATES A STANDARD BEND AT THE END OF THE BAR. "STR" DENOTES STRAIGHT BARS.
- 2. ALL REINFORCING STEEL TO BE EPOXY COATED.

APPROVED FOR CONSTRUCTION 1/25/08

REINFORCING STEEL LIST - BUILDABLE UNIT BRIDGE NO. STA-21-0898 ERIE STREET OVER S.R. 21

STA-21-8.98 PID No. 23753

 $\bigcirc$ 

\_

0

LATITUDE: N 40°46'05" LONGITUDE: W 81°31'15"



S.R. 21 - URBAN FREEWAY, ERIE ST. - URBAN COLLECTOR NHS PROJECT......YES

DESIGN DESIGNATION		
	S.R. 21	ERIE
CURRENT ADT (2003)	23,047	15,26
DESIGN YEAR ADT (2023)	37,130	23,84
DESIGN HOURLY VOLUME (2023)	2,970	1,908
DIRECTIONAL DISTRIBUTION	0.50	0.50
TRUCKS (24 HOUR B&C)	11%	6%
DESIGN SPEED	55 MPH	35 MF
LEGAL SPEED	50 MPH	35 MF
DESIGN FUNCTIONAL CLASSIFICATION:		

DESIGN EXCEPTIONS

NONE REQUIRED

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES CALL TWO WORKING DAYS
BEFORE YOU DIG
CALL 1-800-362-2764 (TOLL FREE) OHIO UTILITIES PROTECTION SERVICE NON-MEMBERS MUST BE CALLED DIRECTLY
OIL & GAS PRODUCERS PROTECTIVE SERVICE CALL: 1-800-925-0988

PLAN PREPARED BY:

W.E. OUICKSALL & ASSOCIATES CIVIL ENGINEERS NEW PHILADELPHIA, OHIO

# STATE OF OHIO DEPARTMENT OF TRANSPORTATION

STA-21-8.98

# CITY OF MASSILLON STARK COUNTY

#### INDEX OF SHEETS:

ENGINEER'S SEAL:

BUILDABLE UNIT #6, #8 & #9
MAY 19, 2008

		¥									
			STA	ANDARD	CONSTR	RUCTION	N DRAWINGS			1	LEMENTAL FICATIONS
	BP-3.1	7/16/04	HW-2.2	4/21/05	TC-71.10	1/19/07		AS-1-81	7/19/02	800	
SIGNED:	_ BP-5.1	7/28/00			TC-72.20	1/21/05		BR-2-98	7/19/02	1	
DATE:	_ BP-7.1	7/28/00	RM-4.2	10/20/06	TC-82.10	4/19/02		GSD-1-96	7/19/02		
ENGINEER'S SEAL:								PCB-91	7/19/02		
ENGINEER 3 SEAL:	CB-2.2	7/15/05						SBR-1-99	7/19/02		
								SICD-1-96	7/19/02	I	
	DM-1.1	4/21/06						VPF-1-90	7/19/02		
	DM-1.2	10/21/05		-							
	DM-1.4	4/21/06	TC-41.10	10/19/07							
			TC-41.20	1/19/01						CE	
	GR-1.1	7/16/04									ECIAL
	GR-2.1	1/16/04	TC-41.50	1/19/01		w				PRO	VISIONS
	GR-3.1	4/18/03	TC-42.10	1/19/07							
	GR-4.2	7/21/06	TC-42.20	7/16/04							
SIGNED:	-							1			
DATE:	HW-21	4/21/06	TC-65 10	1/21/05				<del> </del>			

#### PROJECT DESCRIPTION

REPLACE AND WIDEN THE DECK OF THE STA-21-0898 BRIDGE. THE BRIDGE CARRIES ERIE STREET OVER S.R. 21.

#### EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: ... ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: ... ACRES
NOTICE OF INTENT EARTH DISTURBED AREA: ... ACRES

#### LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

#### 2005 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT DETOURS WILL BE PROVIDED AS INDICATED ON SHEET \_\_\_.

APPROVED FOR CONSTRUCTION 5/19/08



3/ 20/ 2000 12:30:30 PM


 $\bigcirc$ 

-A-21-8.98

NONE

E033(67

2



 $\bigcirc$ 

 $\bigcirc$ 

 $\bigcirc$ 




25+00

STA. PLAN CONTROL STA TRAFFIC ST.

ERIE

STA-21-8.98



HORIZONTAL 00 27

STA. T<sub>0</sub> 22+00 STA ST. ERIE

 $\bigcirc$ 

 $\bigcirc$ 

0



31+00 STA 0 CONTOL 27+00 TC STA

STA-21-8.98


ERIE





PLAN SIGNAL TRAFFIC

## APPROVED FOR CONSTRUCTION 5/19/08




## LOOP DETECTOR CHART

LOOP #	SIZE	# TURNS	MODE	DELAY	AMP #	PHASE
LD-I	6' x 35'	3	PRESENCE	2	1	1
LD-2	6' x 35'	3	PRESENCE	8	2	4

## ESTIMATED QUANTITIES

ITEM	QTY	UNIT	DESCRIPTION	
632	2	EACH	DETECTOR LOOP	
632	160	LIN. FT.	LOOP DETECTOR LEAD-IN CABLE	



#### DESIGN SPECIFICATIONS

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2002, AND THE ODOT BRIDGE DESIGN MANUAL.

#### DESIGN DATA

0

 $\bigcirc$ 

DESIGN LOADING:

HS20, CASE II AND ALT. MILITARY LOADING (SUPERSTRUCTURE) HS20-44 & ALT. MILITARY LOADING (WIDENED SUBSTRUCTURE) ORIGINAL HSI5-44/CF-400 LOADING (SUBSTRUCTURE TO REMAIN)

FUTURE WEARING SURFACE (FWS) OF 60 PSF

CONCRETE CLASS HP: COMPRESSIVE STRENGTH 4500 PSI (SUPERSTRUCTURE)

CONCRETE CLASS C: COMPRESSIVE STRENGTH 4000 PSI (SUBSTRUCTURE)

REINFORCING STEEL: ASTM A615 OR A996 GRADE 60 MINIMUM YIELD STRENGTH

60,000 PSI. SPIRAL REINFORCEMENT MAY BE PLAIN BARS, ASTM A82 OR A615.

STRUCTURAL STEEL: ASTM A709 GRADE 50, YIELD STRENGTH 50,000 PSI

#### DECK PROTECTION METHOD

EPOXY COATED REINFORCING STEEL 21/2" CONCRETE COVER

#### MONOLITHIC WEARING SURFACE

MONOLITHIC WEARING SURFACE IS ASSUMED, FOR DESIGN PURPOSES, TO BE I INCH THICK.

#### PROPOSED WORK

- I. INSTALL NEW FOOTING AND COLUMN AT EACH PIER.
- 2. WIDEN THE EXISTING ABUTMENTS AND PIERS TO ACCOMMODATE AN ADDITIONAL BEAM LINE ALONG THE NORTH SIDE OF THE BRIDGE, AND RAISE EXISTING BEAM
- 3. CONVERT THE EXISTING ABUTMENTS TO SEMI-INTEGRAL ABUTMENTS.
- 4. REMOVE THE EXISTING BEARINGS AND INSTALL NEW LAMINATED ELASTOMERIC
- 5. REPLACE AND WIDEN THE EXISTING SUPERSTRUCTURE TO 45'-6" TOE OF PARAPET TO TOE OF CURB.
- 6. INCREASE THE MINIMUM VERTICAL CLEARANCE OVER SR 21 TO 15'-7".
- 7. MAKE THE SLAB COMPOSITE WITH THE NEW ROLLED STEEL BEAMS.
- 8. CONSTRUCT NEW 42" CONCRETE BRIDGE RAILING PER STANDARD DRAWING SBR-1-99 WITH VANDAL PROTECTION FENCE ON THE LEFT SIDE OF THE BRIDGE.
- CONSTRUCT A 5'-O" SIDEWALK AND BRIDGE RAILING PER STANDARD DRAWING BR-2-98 WITH VANDAL PROTECTION FENCE ON THE RIGHT SIDE OF THE STRUCTURE.

#### EXISTING STRUCTURE VERIFICATION

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05, 105.02 AND 513.04.

#### UTILITY LINES

THE UTILITIES SHALL BEAR ALL EXPENSE INVOLVED IN RELOCATING (INSTALLING) THE AFFECTED UTILITY LINES. THE CONTRACTOR AND UTILITIES ARE TO COOPERATE BY ARRANGING THEIR WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

#### FOUNDATION BEARING PRESSURE:

NEW ABUTMENT FOOTINGS, AS DESIGNED, PROVIDE A MAXIMUM BEARING PRESSURE OF 1.25 TONS PER SOUARE FOOT. THE ALLOWABLE BEARING PRESSURE IS 1.25 TONS PER SQUARE FOOT.

NEW PIER FOOTINGS, AS DESIGNED, PRODUCE A MAXIMUM BEARING PRESSURE OF 2.00 TONS PER SQUARE FOOT. THE ALLOWABLE BEARING PRESSURE IS 2.00 TONS

#### ITEM SPECIAL - PORTIONS OF STRUCTURE REMOVED

#### DESCRIPTION

THIS WORK CONSISTS OF THE REMOVAL OF CONCRETE DECKS INCLUDING SIDEWALKS, SAFETY CURBS, PARAPETS, RAILINGS, DECK JOINTS AND OTHER APPURTENANCES FROM STEEL SUPPORTING SYSTEMS (BEAMS, GIRDERS, CROSS FRAMES, ETC.) AND PORTIONS OF THE CONCRETE SUBSTRUCTURE UNITS DENOTED IN THE PLANS. THE PROVISIONS OF ITEM 202 APPLY EXCEPT AS SPECIFIED BY THE FOLLOWING NOTES. THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE RAM TYPE OF EQUIPMENT IS PROHIBITED. SUBMIT CONSTRUCTION PLANS ACCORDING TO CMS 501.05.

#### PROTECTION OF STEEL SUPPORT SYSTEMS

BEFORE DECK SLAB CUTTING IS PERMITTED, DRAW THE OUTLINE OF PRIMARY STEEL MEMBERS IN CONTACT WITH THE BOTTOM OF THE DECK ON THE SURFACE OF THE DECK. DRILL SMALL DIAMETER PILOT HOLES 2 INCHES OUTSIDE THESE LINES TO CONFIRM THE LOCATION OF FLANGE EDGES. DECK CUTS OVER OR WITHIN 2 INCHES OF FLANGE EDGES SHALL NOT EXTEND LOWER THAN THE BOTTOM LAYER OF DECK SLAB REINFORCING STEEL. CUTS MADE OUTSIDE 2 INCHES OF FLANGE EDGES MAY EXTEND THE FULL DEPTH OF THE DECK. PERFORM WORK CAREFULLY DURING CUTTING OF THE DECK SLAB TO AVOID DAMAGING STEEL MEMBERS THAT MUST REMAIN UNTIL THE EXISTING STRUCTURAL STEEL SHALL BECOME THE PROPERTY OF THE

#### SUBSTRUCTURE CONCRETE REMOVAL

CUT LINE CONSTRUCTION JOINT PREPARATION. SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS I INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE. LEAVE THE EXISTING REINFORCING STEEL, IF REQUIRED IN THE PLANS, IN PLACE. INSTALL DOWEL BARS IF SPECIFIED. PRIOR TO CONCRETE PLACEMENT ABRASIVELY CLEAN JOINT SURFACES AND EXISTING EXPOSED REINFORCEMENT TO REMOVE LOOSE AND DISINTEGRATED CONCRETE AND LOOSE RUST. THOROUGHLYHUROUGHLY CLEAN THE JOINT SURFACE AND EXPOSED REINFORCEMENT OF ALL DIRT, DUST, RUST OR OTHER FOREIGN MATERIAL BY THE USE OF WATER, AIR UNDER PRESSURE, OR OTHER METHODS THAT PRODUCE SATISFACTORY RESULTS. EXISTING REINFORCING STEEL DOES NOT HAVE TO HAVE A BRIGHT STEEL FINISH, BUT REMOVE ALL PACK AND LOOSE RUST. THROUGHLY DRENCH EXISTING CONCRETE SURFACES WITH CLEAN WATER AND ALLOW TO DRY TO A DAMP CONDITION BEFORE PLACING CONCRETE.

#### REMOVAL METHODS

THE CONTRACTOR MAY REMOVE CONCRETE BY CUTTING AND BY MEANS OF HAND OPERATED PNEUMATIC HAMMERS EMPLOYING POINTED OR BLUNT CHISEL TYPE TOOLS. FOR REMOVALS OVER STRUCTURAL MEMBERS (PRESTRESSED BOX BEAMS, I-BEAMS, STEEL BEAMS, STEEL GIRDERS, ETC.), THE CONTRACTOR MAY USE A HAMMER HEAVIER THAN 35 POUNDS BUT NOT TO EXCEED 90 POUNDS UNLESS APPROVED BY THE ENGINEER. REMOVAL METHODS OVER STRUCTURAL MEMBERS SHALL ENSURE ADEQUATE DEPTH CONTROL TO AVOID DAMAGING STEEL MEMBERS THAT MUST REMAIN UNTIL REMOVED.

FOR SUBSTRUCTURE REMOVALS THE WEIGHT OF THE HAMMER SHALL NOT BE MORE THAN 35 POUNDS FOR REMOVALS WITHIN 18 INCHES OF PORTIONS TO BE PRESERVED. OUTSIDE THE 18 INCH LIMIT, THE CONTRACTOR MAY USE HAMMERS NOT EXCEEDING 90 POUNDS UPON THE APPROVAL OF THE ENGINEER. DO NOT PLACE PNEUMATIC HAMMERS IN DIRECT CONTACT WITH REINFORCING STEEL THAT IS TO BE RETAINED IN THE REBUILT STRUCTURE.

#### BASIS OF PAYMENT

PAYMENT FOR ALL THE ABOVE SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM SPECIAL - PORTIONS OF STRUCTURE REMOVED.

#### ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN

FILL THE VOID CREATED BY EXCAVATING FOR THE ABUTMENTS/WINGWALLS WITH TYPE B GRANULAR MATERIAL, 703.16.C. AFTER THE ABUTMENT BREASTMALLS ARE CONSTRUCTED, FILL THE VOID IMMEDIATELY BEHIND EACH ABUTMENT UP TO AN ELEVATION 1.5 FEET BELOW THE BEAM SEAT AND ON A 1:1 SLOPE UP TO THE SUBGRADE ELEVATION, PRIOR TO SETTING BEAMS ON THE ABUTMENTS.

ALL EMBANKMENT/BACKFILL MATERIAL UNDER THE APPROACH SLABS SHALL BE TYPE B GRANULAR MATERIAL PLACED AND COMPACTED IN 6 INCH LIFTS.

PAYMENT FOR ALL THE ABOVE SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM SPECIAL - STRUCTURE REHABILITATION.

#### MECHANICAL CONNECTORS

AN APPROVED TYPE OF MECHANICAL CONNECTOR FOR REINFORCING BARS SHALL BE PROVIDED. INSTALLATION OF CONNECTORS SHALL CONFORM WITH MANUFACTURER'S RECOMMENDED PROCEDURES. CONNECTORS SHALL BE EPOXY COATED. CONNECTORS WITH COATINGS WHICH HAVE BEEN DAMAGED OR WHICH OTHERWISE DO NOT MEET SPECIFICATIONS WITH RESPECT TO COLOR CONTINUITY AND UNIFORMITY MAY BE REPAIRED AS DIRECTED BY THE ENGINEER OR BE REPLACED WITH MATERIAL WHICH MEETS THE SPECIFICATIONS. CONNECTORS SHALL CONFORM WITH ITEM 509.

## ITEM 509 REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL, AS PER PLAN

REPLACE ALL EXISTING REINFORCING STEEL BARS WHICH ARE TO BE INCORPORATED INTO THE NEW WORK AND ARE DEEMED BY THE ENGINEER TO BE MADE UNUSABLE BY CONCRETE REMOVAL OPERATIONS WITH NEW EPOXY COATED REINFORCING STEEL OF THE SAME SIZE AT NO COST TO THE DEPARTMENT.

#### ITEM 511 - CLASS HP CONCRETE. AS PER PLAN

THE PROVISIONS OF ITEM 511 SHALL APPLY EXCEPT AS NOTED BELOW.

#### MIX OPTIONS

ALL SUPERSTRUCTURE, BRIDGE DECK, SIDEWALK, APPROACH SLABS AND PARAPET CONCRETE SHALL BE THIS MIX (HP4, AS PER PLAN). THE FOLLOWING PROPORTIONS WILL BE USED AS A STARTING MIX DESIGN.

> CONCRETE TABLE QUANTITIES PER CUBIC YARD AGGREGATES (SSD) MIX 4, AS PER PLAN (GGBF SLAG + MICROSILICA)

		*8	#57						
	FINE	COARSE	COARSE		CEMENT	GGBF	MICRO	MAX. WATER TO	AIR
	AGG	AGG (LB)	AGG (LB)	TOTAL	CONTENT	SLAG	SILICA	CEMENTITIOUS	CONTENT,
AGG TYPE	(LB)	•	•	(LB)	(LB)	(LB)	(LB)	RATIO	+/- 2%
GRAVEL	1370	650	790	2810	440	190	30	0.42	6
LIMESTONE	1370	655	800	2820	440	190	30	0.42	6
SLAG	1370	570	695	2635	440	190	30	0.42	6

ALL COURSE AGGREGATE SHALL HAVE AN ABSORPTION OF 1.00% OR GREATER AS DEFINED PER ASTM C127

#### BASIS OF PAYMENT

PAYMENT FOR ALL THE ABOVE SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM SPECIAL - STRUCTURE REHABILITATION.

#### **ABBREVIATIONS**

N.S.	-	NEAR SIDE	MAX.	-	MAXIMUM
F.S.	_	FAR SIDE	MIN.	-	MINIMUM
E.S.	-	EACH SIDE	SPA.	-	SPACES
PRS.		PAIRS	ST'D. DWG.	-	STANDARD DRAWING
R.A.		REAR ABUTMENT	C	-	CENTERLINE
F.A.		FORWARD ABUTMENT	€ F/F	-	
CLR.	-	CLEAR	0/0	-	OUT TO OUT
DIA.	-		C/C	-	CENTER TO CENTER
TYP.	-		YR.	-	YEAR
STA.		STATION	O.R.	-	OUTSIDE RADIUS
F	-	FLOW LINE	1.R.	-	INSIDE RADIUS
ĒL.		ELEVATION	C.R.	-	COUNTY ROAD
ELEV.		ELEVATION	T.R.	-	TOWNSHIP ROAD
FWD.	-	FORWARD	L.F.	-	LEFT FORWARD
BRG.		BEARING	R.F.	-	RIGHT FORWARD
LB.	-	POUND	H.S.	-	HIGH STRENGTH
BNT.	-	BENT	CVN	_	CHARPY V-NOTCH
STR.		STRAIGHT	CONST.	-	CONSTRUCTION
LT.	-	LEFT	C.I.P.	-	CAST-IN-PLACE
RT.		RIGHT			REINFORCED CONCRETE
PSI		POUND/SQ. IN.	TSF	-	
U.N.O.		UNLESS NOTED OTHERWISE	T & B	-	TOP & BOTTOM

APPROVED FOR CONSTRUCTION 5/19/08

98

21-8.

A

ST

ST ST


OUICKSALL 554 WES


W.E.


MVC

STRUCTURAL GENERAL NOTES

BRI







 $\bigcirc$ 

0

APPROVED FOR CONSTRUCTION 5/19/08

OUICKSALL 8 554 WEST P NEW PHILADEL CIVIL ENG

SUPERSTRUCTURE DETAILS
BRIDGE NO. STA-21-0898
ERIE STREET OVER S.R. 21

STA-21-8.98

 $\bigcirc$ 


0

0

 $\bigcirc$ 


								SCREED E	LEVATIONS									
LOCATION			SPA	N NUMBER 1	,		S	PAN NUMBER	7 2		SPAN NUMBER 3				SPAN NUMBER 4			
		€ BRG. 0.25 PT. 0.50 PT. SPLIC			SPLICE	€ BRG.	0.25 PT.	0.50 PT.	SPLICE	€ BRG.	BRG. 0.25 PT.	0.50 PT.	SPLICE	€ BRG.	0.25 PT.	0.50 PT.	0.75 PT.	€ BRG.
SCREED LINE A	STATION	23+96.27	24+06.52	24+16.77	24+27.77	24+37.27	24+50.02	24+62.77	24+76.27	24+88.27	25+03.02	25+17.77	25+34.77	25+47.27	25+57.52	25+67.77	25+78.02	25+88.27
SUREEU LINE A	ELEVATION	996.59	996.64	996.68	996.70	996.72	996.77	996.81	996.84	996.87	996.95	997.01	997.04	997.05	997.08	997.12	997.15	997.17
500550 4 115 0	STATION	24+00.21	24+10.46	24+20.71	24+31.71	24+41.21	24+53.96	24+66.71	24+80.21	24+92.21	25+06.96	25+21.71	25+38.71	25+51.21	25+61.46	25+71.71	25+81.96	25+92.2
SCREED LINE B	ELEVATION	996.76	996.80	996.84	996.86	996.88	996.93	996.97	997.00	997.03	997.11	997.18	997.20	997.21	997.24	997.28	997.32	997.33
	STATION	24+04.14	24+14.39	24+24.64	24+35.64	24+45.14	24+57.89	24+70.64	24+84.14	24+96.14	25+10.89	25+25.64	25+42.64	25+55.14	25+65.39	25+75.64	25+85.89	25+96.14
SCREED LINE C	ELEVATION	996.92	996.97	997.00	997.03	997.04	997.09	997.14	997.17	997.20	997.27	997.34	997.37	997.37	997.41	997.45	997.48	997.50
C00550 4 NF D	STATION	24+08.08	24+18.33	24+28.58	24+39.58	24+49.08	24+61.83	24+74.58	24+88.08	25+00.08	25+14.83	25+29.58	25+46.58	29+59.08	25+69.33	25+79.58	25+89.83	26+00.0
SCREED LINE D	ELEVATION	997.09	997.13	997.16	997.19	997.21	997.26	997.30	997.33	997.36	997.43	997.50	997.53	997.54	997.57	997.61	997.64	997.66
600550 4 N.S. S.	STATION	24+12.02	24+22.27	24+32.52	24+43.52	24+53.02	24+65.77	24+78.52	24+92.02	25+04.02	25+18.77	25+33.52	25+50.52	25+63.02	25+73.27	25+83.52	25+93.77	26+04.02
SCREED LINE E	ELEVATION	996.95	996.99	997.03	997.05	997.07	997.12	997.16	997.19	997.22	997.30	997.36	997.39	997.40	997.43	997.47	997.50	997.52
CCOSED LIVE S	STATION	24+15.95	24+26.20	24+36.45	24+47.45	24+56.95	24+69.70	24+82.45	24+95.95	25+07.95	25+22.70	25+37.45	25+54.45	25+66.95	25+77.20	25+87.45	25+97.70	26+07.95
SCREED LINE F	ELEVATION	996.81	996.85	996.88	996.91	996.93	996.97	997.02	997.05	997.08	997.15	997.22	997.25	997.26	997.29	997.33	997.36	997.38
SCREED LINE G	STATION	23+95.65	24+05.90	24+16.15	24+27.15	24+36.65	24+49.40	24+62.15	24+75.65	24+87.65	25+02.40	25+17.15	25+34.15	25+46.65	25+56.90	25+67.15	25+77.40	25+87.65
SCREED LINE G	ELEVATION	996.57	996.61	996.65	996.67	996.69	996.74	996.78	996.81	996.84	996.92	996.98	997.01	997.02	997.05	997.09	997.12	997.14
SCREED LINE H	STATION	24+08.81	24+19.06	24+29.31	24+40.31	24+49.81	24+62.56	24+75.31	24+88.81	25+00.81	25+15.56	25+30.31	25+47.31	25+59.81	25+70.06	25+08.31	25+90.56	26+00.81
SCREED LINE H	ELEVATION	997.06	997.11	997.14	997.16	997.18	997.23	997.27	997.30	997.34	997.41	997.47	997.50	997.51	997.54	997.58	997.62	997.64
SCREED LINE I	STATION	24+14.50	24+24.75	24+35.00	24+46.00	24+55.50	24+68.25	24+81.00	24+94.50	25+06.50	25+21.25	25+36.00	25+53.00	25+65.50	25+75.75	25+86.00	25+96.25	26+06.50
JUNEED LINE I	ELEVATION	996.86	996.90	996.93	996.96	996.98	997.02	997.07	997.10	997.13	997.20	997.27	997.30	997.31	997.34	997.38	997.41	997.43


SCREED ELEVATIONS SHOWN ARE FOR THE DECK SLAB SURFACE PRIOR TO CONCRETE PLACEMENT. ALLOWANCE HAS BEEN MADE FOR ANTICIPATED CALCULATED DEAD LOAD DEFLECTIONS.




STA-21-8.98 PID No. 23753

25/







0

0


0

- 2. CONCRETE SINGLE SLOPE PARAPET, SIDEWALK, SIDEWALK PARAPET AND FENCE ON EACH APPROACH SLAB CARRIED WITH APPROACH SLAB FOR
- 3. SEE STANDARD DRAWING AS-I-81 FOR ADDITIONAL APPROACH SLAB DETAILS AND NOTES.
- 4. SEE STANDARD DRAWINGS BR-2-98 AND SBR-1-99 FOR PARAPET ELEVATIONS AND SECTIONS SHOWING ADDITIONAL DIMENSIONS AND REINFORCING STEEL. THE TOP OF THE SIDEWALK PARAPET IS 2'-8" ABOVE THE TOP OF SIDEWALK BETWEEN END POSTS. STEEL RAILING IS NOT REQUIRED ON THE WALL.
- 5. CONTROL JOINTS IN CONCRETE RAILING, SEE DETAILS AND NOTES ON STD. DWGS. BR-2-98 AND SBR-1-99.
- 6. SEE STRUCTURE GENERAL NOTES, SHEETS 2-3/ FOR ADDITIONAL NOTES.
- 7. FOR SECTION A-A, SEE SHEET 26/

APPROVED FOR CONSTRUCTION 5/19/08

FORWARD APPROACH SLAB BRIDGE NO. STA-21-0898 ERIE STREET OVER S.R. 21 STA-21-8.98 No. 23753 PID 27

W.E. OUJCKSALL & ASSOCIATES, 554 WEST HIGH AVE. NEW PHILADELPHA, OHIO CIVIL ENGINEERS



 $\bigcirc$ 

MADE	NUMBER	, 51.07.	WEIGHT	30			D	IMENSION	IS		
MARK	TOTAL	LENGTH	WEIGHT	TYPE	A	В	С	D	Ε	R	INC
				<u> </u>	UPERSTA	RUCTURE					
D801	72	5'-0"	961	18	2'-9 5/8"	1'-0"	1'-0"				
R501	198	7′-5″	1532	23	1'-1"	3'-2"	3'-0"		2210	0'-2 3/4"	
R502	72	30'-0"	2253	STR							
R503	12	28'-3"	354	STR							
R504	198	9'-0"	1859	30	1'-6"	8"	3'-0"	2'-10"			
11007	,,,,		,,,,,,								
R601	198	3'-6"	1041	28	1'-6"	1'-1"					
R602	6	30'-0"	270	STR							
R603	1	30'-9"	46	STR							
R604	198	2'-5"	719	1	1'-1"	1'-6"					<u> </u>
11004	130	2 3	113	<u> </u>	' '	, ,					-
5401	468	30'-0"	9379	STR							
	78	25'-9"	1342	STR							-
5402	10	25-5	1342	SIN							
CEOL	62	12'-2"	787	3	3'-5"	2'-4"					
S501	62 62	7'-2"	463	2	2'-5"	2'-7"	2'-5"				
S502	6	12'-8"	79	3	3'-8"	2'-4"	2 0				-
5503		7'-5"	46	2	2'-5"	2'-10"	2'-5"				
S504	6	35'-9"	34304	STR	2 - 3	2 10	2 3				
S505	920	30'-0"	13705	STR							-
5506	438	28'-3"	2151	STR							-
S507	73	1'-6"	2151	SIK							
CE00	2 SERIES	- 2 903	1367	STR							0'-11
<i>S508</i>	OF 36	TO	1301	3/1							"
		34'-11"									
	2 SERIES	4'-2"	1000	670							0'-11
<i>S509</i>	OF 32	70	1266	STR							0 -11
		33'-9"	0071	CTO							-
5510	231	33'-6"	8071	STR							-
S511	952	19'-5"	19280	STR						-	-
	2 SERIES	2'-8"	7.00								0'-11
S512	OF 17	70	365	STR						1	0 -11
		17'-11"					-				
o= 1-	2 SERIES	1'-0"	401	CTC							0'-11
<i>S513</i>	OF 20	70	421	STR							0'-11
		19'-2"			0/ 10"		04 10#				
S514	198	2'-5"	499	2	0'-10"	1'-0"	0'-10"				
S515	198	2'-9"	568	2	0'-10"	1'-4"	0'-10"			-	-
S516	198	6'-9"	1394	17	5′-7″						
						<u></u>					
5801	24	35′-10″	2296	STR							-
5802	24	21'-2"	1356	STR				1			1

FOR BENDING DIAGRAMS AND REINFORCING NOTES, SEE SHEET 29/

 $\bigcirc$ 

0

 $\bigcirc$ 

W.E. OUICKSALL & ASSOCIATES, INC. 554 WEST HICH AVE. NEW PHILABEHMA, OHIO CIVIL ENGINEERS STA-21-8.98 PID No. 23753 30/

APPROVED FOR CONSTRUCTION 5/19/08



Route 21 Bridge Replacement (North of Lake Ave) August 7, 2006

Keith A. Dylewski, PE City Engineer 151 Lincoln Way East Massillon, OH 44640

> RE: STA-21-12.48 Stage 2 Plan PID 25433 Korda File: 2006-0007

Dear Mr. Dylewski:

Transmitted herewith, for your review and comment, are two sets of prints of the Stage 2 plan for the rehabilitation of the U.S. 21 bridge crossing of the Tuscarawas River/Railroads/Riverside Avenue at the Massillon North Corporation Line.

A portion of the south approach roadway work (pavement overlay) is located within the Massillon corporate limits. Also, the proposed Maintenance of Traffic plan requires temporary modifications in the Lake Avenue intersection. A copy of the proposed construction stage signal phasing is included.

Please direct any comments to the undersigned or to Neal C. Miesle, PE, District 4 project manager.

Respectfully,

KORDA/NEMETH ENGINEERING, INC. Consulting Engineers

Ronald W. Eifert, PE. PS.

Project Manager

RWE/ids Enclosures

xc: Neal C. Miesle, PE James L. Swartz, PE Michael Hobbs, PE Michael Loudiana(Director-Public Service)

## STA-21-12.48 PID No. 24533 STATE ROUTE 21 IMPROVEMENTS

# STAGE 2 MAINTENANCE OF TRAFFIC & TRAFFIC CONTROL CALCULATIONS & DETAILS

## PREPARED FOR:



&



## PREPARED BY:



July 19, 2006

# **Table Of Contents**

Horizontal Control	Section '
MOT Temporary Signal Calculations	Section 2
MOT and Traffic Control Cost Estimate	Section 3
Office of Traffic Engineering – Standard Construction Draw	
Ohio Department of Transportation – D-4 Preferences S	Section 5



SECTION 1

Chain CROSS01 contains: CR101 CUR CR01 CUR CR02 CR105

#### Beginning chain CROSS01 description

===

Point CR101

419,026.88 E N

2,237,598.27 Sta 10+00.00

Course from CR101 to PC CR01 N 25° 58' 30" W Dist 95.22

```
Curve Data
```

\*\_\_\_\_\*

Curve CR01

P.I. Station 12+21.97 N 419,226.43 E 2,237,501.05

Delta = 7° 35′ 38″ (RT)

Degree = 3° 00' 00"

Tangent = 126.75

Length 253.13

Radius = 1,909.86

External = 4.20

Long Chord = 252.94

Mid. Ord. = 4.19

P.C. Station 10+95.22 N 419,112.48 E 2,237,556.56 P.T. Station 13+48.35 N 2,237,461.08

419,346.71 E C.C. 419,948.96 E 2,239,273.50 N

Back = N 25° 58' 30" W

Ahead  $= N 18^{\circ} 22' 52'' W$ 

Chord Bear = N 22° 10' 41" W

#### Curve Data \*\_\_\_\_\*

Curve CR02

P.I. Station 14+75.10 N 419,466.99 E 2,237,421.11

Delta = 7° 35' 38" (LT)

Degree = 3° 00' 00"

Tangent = 126.75

Length = 253.13

Radius = 1,909.86

External = 4.20 Long Chord = 252.94

Mid. Ord. = 4.19

P.C. Station 13+48.35 N 419,346.71 E 2,237,461.08

P.T. Station 16+01.48 N 419,580.94 E 2,237,365.60

C.C. N 418,744.46 E 2,235,648.66 Back

= N 18° 22' 52" W

Ahead =  $N 25^{\circ} 58' 30'' W$ 

Chord Bear = N 22° 10' 41" W

Course from PT CR02 to CR105 N 25° 58' 30" W Dist 100.00

Point CR105 N 419,670.84 E 2,237,321.80 Sta 17+01.48

Ending chain CROSS01 description

#### Chain CROSS02 contains: CR201 CUR CR03 CUR CR04 CR205

#### Beginning chain CROSS02 description

===

Point CR201

N 419,042.64 E

2,237,630.63 Sta 20+00.00

Course from CR201 to PC CR03 N 25° 58' 30" W Dist 95.22

#### Curve Data

\*\_\_\_\_\*

Curve CR03

P.I. Station 22+21.97 N 419,242.19 E 2,237,533.41

Delta =  $7^{\circ} 35' 38'' (LT)$ 

Degree =  $3^{\circ} 00' 00''$ 

Tangent = 126.75

Length = 253.13

Radius = 1,909.86

External = 4.20Long Chord = 252.94

Mid. Ord. = 4.19

P.C. Station 20+95.22 N 419,128.25 E 2,237,588.93

P.T. Station 23+48.35 N 419,347.81 E 2,237,463.33 C.C. N 418,291.77 E 2,235,871.99

Back = N 25° 58' 30" W

Ahead = N 33° 34' 08" W

Chord Bear = N 29° 46' 19" W

#### Curve Data

\*\_\_\_\_\*

Curve CR04

P.I. Station 24+75.10 N 419,453.42 E 2,237,393.24

Delta =  $7^{\circ} 35' 38'' (RT)$ 

Degree =  $3^{\circ} 00' 00''$ 

Tangent = 126.75

Length = 253.13

Radius = 1,909.86

External = 4.20

Long Chord = 252.94

Mid. Ord. = 4.19

P.C. Station 23+48.35 N 419,347.81 E 2,237,463.33

P.T. Station 26+01.48 N 419,567.36 E 2,237,337.73

C.C. N 420,403.84 E 2,239,054.67

Back =  $N 33^{\circ} 34' 08'' W$ 

Ahead =  $N 25^{\circ} 58' 30'' W$ 

Chord Bear = N 29° 46' 19" W

Course from PT CR04 to CR205 N 25° 58' 30" W Dist 150.00

Point CR205 N 419,702.21 E 2,237,272.03 Sta 27+51.48

===

Ending chain CROSS02 description

#### Chain CROSS03 contains: CR301 CUR CR05 CUR CR06 CUR CR07

#### Beginning chain CROSS03 description

===

Point CR301 N 420,570.34 E 2,236,883.57 Sta 30+00.00

Course from CR301 to PC CR05 N 25° 58' 30" W Dist 100.35

#### Curve Data \*\_\_\_\_\*

Curve CR05

P.I. Station 33+26.06 N 420,863.47 E 2,236,740.76 Delta = 13° 28' 48" (LT) Degree = 3° 00' 00" Tangent = 225.71 Length 449.33 = Radius = 1,909.86 External = 13.29 Long Chord = 448.30 Mid. Ord. = 13.20 P.C. Station 31+00.35 N 420,660.56 E 2,236,839.62 P.T. Station 35+49.69 N 421,037.74 E 2,236,597.33 N 419.824.08 E 2,235,122.68

C.C. Back = N 25° 58' 30" W

Ahead = N 39° 27' 18" W Chord Bear = N 32° 42' 54" W

#### Curve Data

\*\_\_\_\_\*

Curve CR06

P.I. Station 36+46.51 N 421,112.50 E 2,236,535.80 5° 48' 16" (RT) Delta =

Degree 3° 00' 00" = Tangent = 96.83 Length = 193.48 Radius 1,909.86 = External = 2.45 Long Chord = 193.40 Mid. Ord. = 2.45

P.C. Station 35+49.69 N 421,037.74 E 2,236,597.33 P.T. Station 37+43.17 N 421,193.10 E 2,236,482.15 422,251.40 E 2,238,071.98

C.C. N = N 39° 27' 18" W Back

Ahead =  $N 33^{\circ} 39' 02'' W$ Chord Bear = N 36° 33' 10" W

Curve Data

\*\_\_\_\_\*

Curve CR07

P.I. Station 38+16.59 N 421,254.22 E 2,236,441.46

Delta 1° 54' 15" (LT) 1° 17' 49" Degree = Tangent = 73.42



```
Length =
                 146.83
Radius =
                4,417.80
External =
                  0.61
Long Chord =
                   146.82
Mid. Ord. =
                   0.61
P.C. Station
                37+43.17 N
                              421,193.10 E
                                               2,236,482.15
P.T. Station
                38+90.00 N
                            421,313.96 E
                                               2,236,398.77
C.C.
                   N
                          418,745.09 E
                                       2,232,804.62
Back
        = N 33° 39' 02" W
Ahead = N 35^{\circ} 33' 17'' W
Chord Bear = N 34° 36' 09" W
```

===

Ending chain CROSS03 description

Chain CROSS04 contains: CR401 CUR CR08 CUR CR09 CUR CR010

#### Beginning chain CROSS04 description

===

Point CR401 N 420,555.88 E 2,236,856.14 Sta 40+00.00

Curve Data

Course from CR401 to PC CR08 N 25° 58' 30" W Dist 183.11

```
*____*
Curve CR08
P.I. Station
                 42+68.18 N
                                 420,796.96 E
                                                  2,236,738.68
Delta
               5° 06' 03" (RT)
Degree
                3° 00' 00"
        =
Tangent =
                   85.07
Length
                  170.03
Radius
        =
                 1,909.86
External =
                   1.89
Long Chord =
                    169.97
Mid. Ord. =
                    1.89
P.C. Station
                 41+83.11 N
                                 420,720.49 E
                                                  2,236,775.94
P.T. Station
                 43+53.14 N
                                 420,876.45 E
                                                  2,236,708.37
                           421,556.96 E
                    N
                                            2,238,492.87
```

C.C. Back = N 25° 58' 30" W Ahead = N 20° 52' 27" W

Chord Bear = N 23° 25' 28" W

#### Curve Data \*\_\_\_\_\*

Curve CR09

P.I. Station 45+47.25 N 421,057.83 E 2,236,639.20

Delta = 11° 36' 26" (LT) 3° 00' 00" Degree = Tangent = 194.12 Length 386.91 =

Radius 1.909.86 External = 9.84 Long Chord = 386.25 Mid. Ord. = 9.79

P.C. Station 43+53.14 N 420,876.45 E 2,236,708.37 P.T. Station 47+40.04 N 421,221.58 E 2,236,534.95 C.C. N 420,195.94 E 2,234,923.86

= N 20° 52' 27" W Back = N 32° 28' 53" W Ahead

Chord Bear = N 26° 40' 40" W

#### Curve Data \*\_\_\_\_\*

Curve CR010

P.I. Station 48+37.54 N 421,303.82 E 2,236,482.60

Delta 2° 26' 27" (LT) = Degree = 1° 15' 07" Tangent = 97.49

```
Length =
                194.96
Radius =
                4,576.46
External =
                 1.04
Long Chord = Mid. Ord. =
                  194.94
                  1.04
P.C. Station
                47+40.04 N
                             421,221.58 E
                                               2,236,534.95
P.T. Station
                            421,383.76 E 2,236,426.79
                49+35.00 N
C.C.
                   N
                         418,763.90 E
                                       2,232,674.41
Back
        = N 32° 28' 53" W
Ahead = N 34° 55' 20" W
Chord Bear = N 33° 42' 07" W
```

===

Ending chain CROSS04 description

Chain BL21 contains: BL01 CUR BLC1 BL04

### Beginning chain BL21 description

Point BL01

N

418,315.57 E 2,237,964.83 Sta 642+00.00

Course from BL01 to PC BLC1 N 25° 58' 30" W Dist 2,256.20

Curve Data \*\_\_\_\_\*

Curve BLC1

P.I. Station 674+85.13 N

421,268.86 E 2,236,526.02

Delta = 15° 20' 30" (LT)

Degree = 0° 45′ 00"

Tangent = 1,028.93

Length 2,045.55

Radius 7,639.43 =

External = 68.98

Long Chord = 2,039.44

Mid. Ord. = 68.36

P.C. Station 664+56.20 N 420,343.86 E 2,236,976.67 P.T. Station 685+01.75 N 422,041.66 E 2,235,846.70

C.C. N 416,997.96 E 2,230,108.93

Back = N 25° 58' 30" W

= N 41° 19' 00" W Ahead

Chord Bear = N 33° 38' 45" W

Course from PT BLC1 to BL04 N 41° 19' 00" W Dist 2,288.71

Point BL04

423,760.64 E 2,234,335.65 Sta 707+90.46

Ending chain BL21 description

**SECTION 2** 

Analyst: LOB Agency: GPD Group

Inter.: S.R. 21 / Lake Ave Area Type: All other areas

Date: 7/6/2006 Period: AM Peak

Jurisd: ODOT Year : 2006

Project ID: STA. 21 - 12.48 E/W St: Lake Avenue

				SI				ECTION	SUMM	ARY				
		Ea: L	stbou: T			stbou			rthbou			uthbo		1
		П	1	R	L	$\mathbf{T}$	R	L	T	R	L	T	R	
No. Lar		1	1	0	1	1	0	1	1	1	1	2	0	
LGConfi	.g	L	TR		L	TR		L	$\mathbf{T}$	R	L	TR		
Volume Lane Wi	dth	19	313 12.0	25	315	167	131	14	330	175	63	463	15	
RTOR Vo		12.0	12.0	0	12.0	12.0	0	12.0	12.0	0	12.0	12.0	0	15.7
V					1			1		0 [			U	1
Duratio		0.25		Area				areas ions_						
Phase C		ation	ı 1	2	3	4			5	6	7	8	}	
EB Lef Thr				A			NB		A					
Rig				A A				Thru		A				
Ped				Α				Right Peds		A				
WB Lef	t		A	А			SB	Left	А					
Thr			A	A				Thru		А				
Rig			A	A			-	Right		A				
Ped: NB Rig							- FR	Peds						
SB Righ							EB WB	Right Right						
Green			11.0	16.0			I MD	RIGIIC	6.0	17.0				
Yellow			3.0	4.0					3.0	4.0				
All Red			1.0	2.0					1.0	2.0				
			Tn	terser	tion	Perfo	rmana	e Summ	Cyc.	le Leng	gth:	70.0	S	ecs
Appr/	Lane		Adj	Sat	Ra	tios	Tillatic	Lane	ary Group	Appr	roach			
Lane	Group			Rate	-		_		_					
Grp	Capac	city	(	s)	V/C	g/	C	Delay	LOS	Delay	LOS			
Eastbour			100	_										
L TR	243 429		106		0.09			21.4	C					
110	42)		107.	5	0.00	0.	23	44.2	D	43.0	D			
Westboun		121												
L	393		1809		0.89			37.0	D					
TR	786		1775	)	0.42	0.4	14	13.7	В	25.7	C			
Northbou	nd													
L	155		1805	5	0.10	0.0	9	29.8	C					
T	461		1900		0.80	0.2	2.4	34.3	C	30.6	C			
R Southbou	392		1615	5	0.49	0.2	2.4	23.8	C					
L	155		1805		0.45	0 0	. 0	20 -	~					
TR	874		3600		0.45	0.0		32.5 24.8	C C	25.7	С			
	Tnto				20 0									
	Inte.	rsect	ion L	етау :	= 30.0	) (se	c/veh	ı) In	terse	ction :	LOS =	C		

Analyst: LOB

Inter.: S.R. 21 / Lake Ave Area Type: All other areas

Agency: GPD Group Date: 7/6/2006 Period: Noon Peak

Jurisd: ODOT

Project ID: STA. 21 - 12.48

Year : 2006

E/W St: Lake Avenue

		SI	GNALIZE	ED INTERS	ECTION	SUMMA	ARY				
	Ea	stbound		bound		thbou		Sou	ıthboı	ind	1
	L	T R	L	T R	L	T	R	L	T	R	
No. Lan	_		1	1 0	1	1	1	1	2	0	
LGConfig	-	TR	L	TR	L	T	R	L	TR		
Volume	110	179 33		213 43		236	163	43	241	13	
Lane Wid		12.0	12.0 1	.2.0	12.0	12.0		12.0	12.0	^	
TION VO.	1		1		1		0			0	1 -
Duration	n 0.25	Area		all other al Operat							
Phase Co	ombinatio	n 1 2	3	4		5	6	7	8	 I	
EB Left		A		NB		A					
Thru		A			Thru		A				
Righ Peds		A			Right		A				
WB Left		A A		SB	Peds Left	7					
Thru		A A		35	Thru	A	А				
Righ		A A			Right		A				
Peds					Peds						
NB Righ				EB	Right						
SB Righ	nt			WB	Right						
Green Yellow		11.0 16.0				6.0	17.0				
		2 0 1 0									
		3.0 4.0				3.0	4.0				
All Red		3.0 4.0 1.0 2.0				3.0	4.0	ath.	70 0		2005
		1.0 2.0	ction P	erformanc	e Summa	3.0 1.0 Cyc	4.0 2.0 le Len	gth:	70.0	;	secs
All Red Appr/	Lane	1.0 2.0 Intersection Adj Sat	Rat	erformanc ios	e Summa Lane (	3.0 1.0 Cyc	4.0 2.0 le Len				secs
All Red  Appr/ Lane	Lane Group	Intersection Adj Sat Flow Rate	Rat	ios	Lane (	3.0 1.0 Cyc ary_ Group	4.0 2.0 le Leng	roach			secs
All Red  Appr/ Lane	Lane	Intersection Adj Sat Flow Rate	Rat	erformanc ios 	e Summa Lane ( ————————————————————————————————————	3.0 1.0 Cyc ary_ Group	4.0 2.0 le Leng			:	secs
Appr/ Lane Grp	Lane Group Capacity	Intersection Adj Sat Flow Rate (s)	Rat V/C	g/C	Delay	3.0 1.0 Cyc ary_ Group	4.0 2.0 le Leng	roach		:	secs
Appr/ Lane Grp Eastboun	Lane Group Capacity id 254	Intersection Adj Sat Flow Rate (s)	V/C 0.04	g/C 0.23	Lane (Delay 21.1	3.0 1.0 Cyc ary_ Group LOS	4.0 2.0 le Leng App:	roach y LOS		:	secs
Appr/ Lane Grp	Lane Group Capacity	Intersection Adj Sat Flow Rate (s)	Rat V/C	g/C	Delay	3.0 1.0 Cyc ary_ Group	4.0 2.0 le Leng	roach			secs
Appr/ Lane Grp  Eastboun L TR  Westboun	Lane Group Capacity ad 254 424	Intersect Adj Sat Flow Rate (s)  1112 1855	V/c 0.04 0.56	g/C 0.23 0.23	Delay 21.1 25.5	3.0 1.0 Cyc ary_ Group LOS	4.0 2.0 le Leng App:	roach y LOS		:	secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L	Lane Group Capacity ad 254 424 ad 481	1.0 2.0 Intersec Adj Sat Flow Rate (s)  1112 1855	Rat v/c 0.04 0.56	0.23 0.23	Delay 21.1 25.5	3.0 1.0 Cyc ary_ Group LOS C	4.0 2.0 le Leng App: Delay	roach y LOS C		:	secs
Appr/ Lane Grp  Eastboun L TR  Westboun	Lane Group Capacity ad 254 424	Intersect Adj Sat Flow Rate (s)  1112 1855	V/c 0.04 0.56	g/C 0.23 0.23	Delay 21.1 25.5	3.0 1.0 Cyc ary_ Group LOS	4.0 2.0 le Leng App:	roach y LOS C		:	secs
Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou	Lane Group Capacity ad 254 424 ad 481 820 and	1.0 2.0 Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1852	0.04 0.56 0.48 0.35	0.23 0.23 0.23	Delay  21.1 25.5  13.8 13.1	3.0 1.0 Cyc ary Group LOS C C	4.0 2.0 le Leng App: Delay	roach y LOS C		:	secs
Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous	Lane Group Capacity ad 254 424 ad 481 820 and 155	1.0 2.0 Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1805	Rat v/c 0.04 0.56 0.48 0.35	0.23 0.23 0.23 0.44 0.44	Delay  21.1 25.5  13.8 13.1	3.0 1.0 Cyc ary Group LOS C C	4.0 2.0 le Leng App: Delay 25.3	roach y LOS C		:	secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous L	Lane Group Capacity  ad 254 424  ad 481 820  ad 155 461	1.0 2.0 Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1805 1900	Rat v/c 0.04 0.56 0.48 0.35 0.14 0.57	0.23 0.23 0.23 0.44 0.44	Delay  21.1 25.5  13.8 13.1  30.0 24.9	3.0 1.0 Cyc ary_ Group LOS C C	4.0 2.0 le Leng App: Delay	roach y LOS C		:	secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous L T	Lane Group Capacity  ad 254 424  ad 481 820  ad 155 461 392	1.0 2.0 Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1805	Rat v/c 0.04 0.56 0.48 0.35	0.23 0.23 0.23 0.44 0.44	Delay  21.1 25.5  13.8 13.1	3.0 1.0 Cyc ary Group LOS C C	4.0 2.0 le Leng App: Delay 25.3	roach y LOS C			secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous L	Lane Group Capacity  ad 254 424  ad 481 820  ad 155 461 392	Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1900 1615	0.04 0.56 0.48 0.35 0.14 0.57 0.46	0.23 0.23 0.23 0.44 0.44 0.09 0.24 0.24	Delay  21.1 25.5  13.8 13.1  30.0 24.9 23.5	3.0 1.0 Cyc ary Group LOS C C C	4.0 2.0 le Leng App: Delay 25.3	roach y LOS C			secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous L T R Southboun	Lane Group Capacity  ad 254 424  ad 481 820  ad 155 461 392  ad	1.0 2.0 Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1805 1900	Rat v/c 0.04 0.56 0.48 0.35 0.14 0.57	0.23 0.23 0.23 0.44 0.44	Delay  21.1 25.5  13.8 13.1  30.0 24.9	3.0 1.0 Cyc ary_ Group LOS C C	4.0 2.0 le Leng App: Delay 25.3	roach y LOS C		:	secs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbous L T R Southboun L	Lane Group Capacity  ad 254 424  ad 481 820  ad 155 461 392  ad 155 872	Intersect Adj Sat Flow Rate (s)  1112 1855  1805 1805 1900 1615 1805	0.04 0.56 0.48 0.35 0.14 0.57 0.46 0.31 0.32	0.23 0.23 0.23 0.44 0.44 0.09 0.24 0.24 0.09 0.24	Delay  21.1 25.5  13.8 13.1  30.0 24.9 23.5  31.2 22.0	3.0 1.0 Cyc ary Group LOS C C C C C C C C C C C C C	4.0 2.0 le Lend App: Delay 25.3 13.4 24.6	C C		:	secs

Analyst: LOB Inter.: S.R. 21 / Lake Ave Agency: GPD Group Area Type: All other areas Date: 7/6/2006 Jurisd: ODOT

Date: 7/6/2006 Jurisd: ODOT
Period: PM Peak Year : 2006
Project ID: STA. 21 - 12.48

E/W St: Lake Avenue N/S St: S.R. 21

E/W DC. Lan	e Avenue				N/ S	DL.	5. K. Z	. T				
		SIC	GNALIZ	ED INT	TERSE	CTION	SUMMA	ARY				
	Eastbou			tbound			rthbou	-	Sou	thboun	d	
	L T	R	L	T	R	L	T	R	L		R	
No. Lanes	1 1	0	$\left  \right $	1	0	1	1	1	1.	2	0	
LGConfig	L TH		L	TR	0	L	T	R	L	TR		
Volume	15 280	32	319	290 9	2	50	483	1000 1000000			1	
Lane Width	12.0 12.0	323	12.0			12.0	12.0	12.0	12.0	12.0		
RTOR Vol		0		0	)			0		0		
Duration	0.25	Area T										
Phase Combin	nation 1	2	sig.	nal Op 4	erat	TOUS	5	6	7	8		
EB Left		A			NB	Left	A	A	*	Ü		
Thru		A				Thru		A	A			
Right		A				Right		A	A			
Peds WB Left	7	7		1	CD	Peds	7					
Thru	A A	A A		1	SB	Left Thru	A		А			
Right	A	A				Right			A			
Peds					-	Peds						
NB Right					EB	Right						
SB Right	10.0	17 0		1	WB	Right			4.0			
Green Yellow	12.0	17.0 4.0					7.0	8.0	12.0	)		
All Red	1.0	2.0					1.0	1.0	2.0			
	17.0							le Leng		30.0	sec	S
		ntersec			mance							
Appr/ Lane Lane Grou		j Sat w Rate		ios		Lane	Group	Appı	coach			
		(s)	v/c	g/C		Delay	LOS	Delay	LOS			
Eastbound												
L 208		8	0.08	0.2		25.4	C					
TR 397	18	70	0.87	0.23	1	49.4	D	48.3	D			
Westbound												
L 366	18	05	0.97	0.43	1	57.4	E			100 a	-, '-'	
TR 755	18	31	0.56	0.43	L	18.9	В	36.4	D	100		
Northbound												
L 429	18	05	0.13	0.24	1	24.1	C					
T 570	19		0.94	0.30		51.5	D	43.0	D			
R 485	16:	15	0.78	0.30	)	33.7	C					
Southbound	1.0	25	0 75	0.00	`	F1 0	-					
L 158 TR 538	180 358		0.75	0.09		54.0 42.1	D D	44.7	D			
330	330		0.01	0.13		74·1	D	44./	ט			

Intersection Delay = 42.2 (sec/veh) Intersection LOS = D

Analyst: LOB

Inter.: Lake Ave / Erie St

Area Type: All other areas

Agency: GPD Group Date: 7/6/2006

Jurisd: ODOT

Period: AM Peak

Year : 2006

Project ID: STA. 21 - 12.48 E/W St: Lake Avenue

		SI	GNALIZE	D INTERSE	ECTION	SUMMA	RY				
		stbound	West:	bound	Nor	thbou	nd	Sou	thbou	ınd	
	L	T R	L '	T R	L	T	R	L	T	R	
No. Lane	es 1	1 0	1	1 0	1	1	0	1	1	0	-
LGConfig		TR	L	TR	L	TR		L	TR		
Volume	214	492 19		25 29			43	28	118	225	
Lane Wid	The contraction is a standard contract to	12.0	12.0 1	2.0	12.0		0	12.0	12.0	0	
			1		1						
Duration	n 0.25			ll other al Operat							
	ombination		3	4		5	6	7	8	3	
EB Left Thru		A A A		NB	Left Thru	A A					
Righ		A			Right						
Peds					Peds						
WB Left Thru		A A		SB	Left Thru	A A					
Righ		A A			Right						
Peds					Peds						
NB Righ				EB	Right						
SB Righ Green	10	7.0 29.0		WB	Right	20.0					
						20.0					
Yellow		3.0 3.0				3.0					
Yellow All Red		3.0 3.0 1.0 2.0				2.0					
		1.0 2.0	ction Pe	erformanc	e Summa	2.0 Cycl	e Len	gth:	70.0	S	ecs
All Red Appr/	Lane	1.0 2.0 Interse	Rati	erformanc	e Summa Lane (	2.0 Cycl ary				S	ecs
All Red Appr/ Lane	Group	Interse Adj Sat Flow Rate	Rati	.os	Lane (	2.0 Cycl ary Group	App	roach		S	ecs
All Red Appr/ Lane		Interse Adj Sat Flow Rate	Rati			2.0 Cycl ary Group	App			S	ecs
Appr/ Lane Grp	Group Capacity 	Interse Adj Sat Flow Rate (s)	Rati v/c	g/C	Lane (	2.0 Cyclary Group LOS	App	roach		S	ecs
Appr/Lane Grp Eastboun L	Group Capacity id 403	Interse Adj Sat Flow Rate (s)	V/c 0.59	g/C 0.57	Delay	2.0 Cyclary Group LOS	App: Delay	roach y LOS		S	ecs
Appr/ Lane Grp	Group Capacity 	Interse Adj Sat Flow Rate (s)	Rati v/c	g/C	Lane (	2.0 Cyclary Group LOS	App	roach y LOS		S	ecs
Appr/Lane Grp Eastboun L	Group Capacity ad 403 783	Interse Adj Sat Flow Rate (s)  1805 1889	0.59 0.73	g/C 0.57 0.41	Delay 12.2 20.5	2.0 Cyclary Group LOS	App: Delay	roach y LOS		S	ecs
Appr/Lane Grp Eastboun L TR Westboun L	Group Capacity ad 403 783	1.0 2.0 Interse Adj Sat Flow Rate (s)  1805 1889	0.59 0.73	g/C 0.57 0.41	Delay  12.2 20.5	2.0 Cyclary Group LOS B C	App: Delay	roach y LOS B		S	ecs
Appr/Lane Grp Eastbount TR Westboun	Group Capacity ad 403 783	Interse Adj Sat Flow Rate (s)  1805 1889	0.59 0.73	g/C 0.57 0.41	Delay 12.2 20.5	2.0 Cyclary Group LOS	App: Delay	roach y LOS B		S	ecs
Appr/Lane Grp Eastboun L TR Westboun L	Group Capacity d 403 783 d 354 780	1.0 2.0 Interse Adj Sat Flow Rate (s)  1805 1889	0.59 0.73	g/C 0.57 0.41	Delay  12.2 20.5  9.6 18.3	2.0 Cyclary Group LOS B C	App: Delay	roach y LOS B		S	ecs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou	Group Capacity d 403 783 d 354 780 nd 168	Interse Adj Sat Flow Rate (s)  1805 1889  1805 1882	0.59 0.73 0.16 0.65	g/C 0.57 0.41 0.57 0.41	Delay  12.2 20.5  9.6 18.3	2.0 Cyclary Group LOS B C	App: Delay  18.1  17.4	roach y LOS B		St	ecs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou	Group Capacity d 403 783 d 354 780	1.0 2.0 Interse. Adj Sat Flow Rate (s)  1805 1889  1805 1882	0.59 0.73 0.16 0.65	g/C 0.57 0.41 0.57 0.41	Delay  12.2 20.5  9.6 18.3	2.0 Cyclary Group LOS B C	App: Delay	roach y LOS B		S	ecs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou	Group Capacity d 403 783 d 354 780 nd 168 518	1.0 2.0 Interse. Adj Sat Flow Rate (s)  1805 1889  1805 1882  589 1813	0.59 0.73 0.16 0.65	g/C 0.57 0.41 0.57 0.41	Delay  12.2 20.5  9.6 18.3	2.0 Cyclary Group LOS B C	App: Delay  18.1  17.4	roach y LOS B		S	ecs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou L TR	Group Capacity d 403 783 d 354 780 nd 168 518	1.0 2.0	0.59 0.73 0.16 0.65 0.07 0.31	0.57 0.41 0.57 0.41 0.29 0.29	Delay  12.2 20.5  9.6 18.3  18.4 19.9	2.0 Cyclary_ Group LOS B C	App: Delay  18.1  17.4	roach y LOS B		Si	ecs
All Red  Appr/ Lane Grp  Eastboun L TR  Westboun L TR  Northbou L TR	Group Capacity d 403 783 d 354 780 nd 168 518	1.0 2.0 Interse. Adj Sat Flow Rate (s)  1805 1889  1805 1882  589 1813	0.59 0.73 0.16 0.65	g/C 0.57 0.41 0.57 0.41 0.29 0.29	Delay  12.2 20.5  9.6 18.3  18.4 19.9	2.0 Cyclary_ Group LOS B C	App: Delay  18.1  17.4	roach y LOS B		S	ecs

Analyst: LOB Inter.: Lake Ave / Erie St Agency: GPD Group Area Type: All other areas Date: 7/6/2006 Jurisd: ODOT

Date: 7/6/2006 Jurisd: ODOT Period: Noon Peak Year : 2006


Project ID: STA. 21 - 12.48

E/W	E/W St: Lake Avenue						N/S	S St: S	S.R.	21				
				S	IGNALI	ZED I	NTERSE	ECTION	SUMM	ARY				
-		Ea:	stbou	nd	We	stbou	nd	Nor	thbo	und	So	uthbo	und	1
		L	T	R	L	$\mathbf{T}$	R	L	$\mathbf{T}$	R	L	Т	R	
No.	Lanes	1	1	0	1	1	0	1	1	0	1	1	0	-
LGC	onfig	L	TR		L	TR		L	TR		L	TR		
Vol	ume	126	311	15	105	310	35	19	118	67	18	71	133	
Lane	e Width	12.0	12.0		12.0	12.0		12.0	12.0		12.0	12.0		-
RTO	R Vol			0			0			0			0	1
Dura	ation	0.25		Area	Type:		other Operat				***************************************	1		
Phas	se Combin	nation	1 1	2	3	4	1		5	6	7	8	В	
	Left		A	A			NB	Left	A					
	Thru			A				Thru	A					
	Right Peds			A				Right Peds	Α					
WB	Left		А	А			SB	Left	А					
***	Thru		4.1	A			1 55	Thru	A					
	Diabe			7				Diaba						

1	, D	TELL	A	A	IVD	THELL	A		
		Thru		A		Thru	A		
		Right		A		Right	A		
		Peds				Peds			
V	IB	Left	A	A	SB	Left	A		
		Thru		A		Thru	A		
		Right		A	~	Right	A		
		Peds				Peds			
N	IB	Right			EB	Right			
S	B	Right			WB	Right			
G	ree	en	 7.0	29.0			20.0		
Y	el	low	3.0	3.0			3.0		
A	11	Red	1.0	2.0			2.0		

Cycle Length: 70.0 secs \_Intersection Performance Summary\_ Appr/ Lane Adj Sat Ratios Lane Group Approach Lane Flow Rate Group V/C g/C Delay LOS Capacity Delay LOS Grp (s) Eastbound 499 1805 0.28 0.57 8.3 A 1887 TR 782 0.46 0.41 15.3 13.4 В В Westbound 516 0.23 1805 0.57 8.0 A TR 775 1871 0.49 0.41 15.6 13.8 В B Northbound 298 1042 0.07 0.29 18.3 В TR 513 1797 0.40 0.29 20.7 20.5 Southbound 317 0.06 18.3 1110 0.29 L В TR 490 1714 0.46 0.29 21.3 C 21.0

Intersection Delay = 15.9 (sec/veh) Intersection LOS = B



Analyst: LOB Agency: GPD Group Date: 7/6/2006

Inter.: Lake Ave / Erie St Area Type: All other areas

Period: PM Peak

Jurisd: ODOT Year : 2006

Project ID: STA. 21 - 12.48

E/W St: Lake Avenue

***************************************					ECTION SUMMA			
	L Ea	stbound T R		bound T R	Northbou L T	nd R	Southl L T	oound R
No. Lan LGConfi Volume Lane Wi RTOR Vo	g L 285 .dth 12.0	1 0 TR 588 27 12.0	1 L 122 5 12.0 1	1 0 TR 13 43 2.0	1 1 L TR 24 137 12.0 12.0	0 78 0	1 1 L 27 27 123 12.0 12.	TR 3 209
Duratio	on 0.25	Area		ll other al Operat			1	
Phase C EB Lef Thr Rig Ped WB Lef Thr Rig Ped NB Rig SB Rig Green Yellow All Red	u ht s t u ht s ht	n 1 2 A A A A A A A A A A A A A A A A A A	3	4 NB	Left A Thru A Right A Peds Left A Thru A Right A Peds Right A Peds Right Right Right 22.0 3.0 2.0	6 le Len	7 gth: 80.	8 0 secs
Appr/	Lane	Adj Sat	Rati		e Summary Lane Group			
Lane Grp	Group Capacity	Flow Rate (s)	v/c	g/C	Delay LOS	Dela	y LOS	
Eastbour L TR	nd 361 826	1805 1887	0.88	0.60	34.4 C			
TIV		100/	0.83	0.44	26.8 C	29.2	С	
Westbour L TR	314 822	1805 1878	0.83 0.43 0.75		26.8 C	29.2		
Westbou	314 822	1805	0.43	0.60	13.6 В		C	
Westbour L TR Northbou	314 822 und 155 494	1805 1878 563	0.43 0.75	0.60	13.6 B 22.8 C	21.1	C	



raffic Home Publications List	Latest Revisions	Old or Superseded	Plan Insert
	Information	Publications	Sheets

# Office of Traffic Engineering Standard Construction Drawings

Description	Standard detail drawings related to the design and use of traffic control devices used in ODOT plans.
	These are ODOT standards drawings for use on ODOT construction projects. However, these drawings are also recommended for ODOT force account work as appropriate, and they are available to others as a reference.
Misc. Information	
Ordering this Manual	Contacts.
Feedback	you are welcome to contact members of the section with questions or comments through the Contacts.

Highway Lighting (HL)	Maintenance of Traffic (MT)	Traffic Control (TC)
NAME OF THE PARTY	<u> </u>	

	File Size	(Kilobytes)		1
Drawing No.	Adobe Acrobat 4.0 (.pdf)	Microstation (.dgn)	Description / Title	Date
	286	55	SCD Index	04/21/06
Highway Lighting	g Standard Co	onstruction Drav	vings	0 1/21/00
HL-10.11	86	371	Light Pole Styles	01/16/04
HL-10.12	226	490	Light Pole Details	01/21/05
HL-10.13	89	<u>50</u>	Pole Base Details	01/17/03
HL-10.31	143	<u>72</u>	Light Tower Details	07/20/01
HL-20.11	264	<u>281</u>	Foundation And Trench Details	04/19/02
HL-20.13	230	389	Foundation & Junction Box Details Median Mounted Light	01/21/05
HL-20.14	220	<u>964</u>	Structure Lighting I	01/21/05
HL-20.21	<u>155</u>	<u>114</u>	Light Tower Foundations	01/21/05
HL-30.11	173	<u>285</u>	Pull Box Details I	01/21/05
HL-30.21	75	106	Roadway Conduit Details I	04/19/02
HL-30.22	<u>189</u>	<u>851</u>	Roadway Conduit Details II	01/21/05
HL-30.31	163		Structure Conduit Details I	01/21/05
HL-30.32	109	<u>251</u>	Structure Conduit Details II	04/19/02
HL-30.33	<u>46</u>		Structure Conduit Details Details III	01/21/05
HL-40.10	<u>155</u>		Power Service Pole Mounted	04/19/02
HL-40.20	<u>59</u>		Power Service Ground Mounted	01//16/04
				01//10/04



		104	188	Grounding Details	07/20/01
	HL-50.21	245	814	Structure Grounding Steel Beam Bridge	01/21/05
	HL-60.11	99	338	Pole Wiring I	01/16/04
	HL-60.12	112	287	Pole Wiring II	01/21/05
	HL-60.21	44	93	Tower Wiring Details	01/21/05
	HL-60.31	171	257	Control Center Wiring	07/20/01
	Maintenance of	Traffic Stand	ard Constructi	on Drawings (return to top)	
*	MT-35.10	90, 383	170	Flashing Arrow Panel	04/20/01
*	MT-95.30	249	110	Closing Right Or Left Lane Of A Multi-Lane Divided Highway With Drums	
	MT-95.31	217	87	Closing Right Lane Of A Multi-Lane Undivided Highway With Drums	07/16/04
	MT-95.32	220	84	Closing Left Lane Of A Multi-Lane Undivided Highway With Drums	07/16/04
*	MT-95.40	214	112	Closing Right Or Left Lane Of A Multi-Lane Divided Highway With Portable Concrete Barrier	07/16/04
According to your case, and any	MT-95.41	213	<u>106</u>	Closing Right Lane Of A Multi-Lane Undivided Highway With Portable Concrete Barrier	07/16/04
and investors and	MT-95.60	200	124	Closure of Two-Way left Turn Lane	04/19/02
	MT-95.61	208	120	Closure Of Right Lane Of Three Lane Section With Two-Way Left Turn Lane	04/19/02
*	MT-95.70	252	193	Two-Lane, Two-Way Operation For Use On Four Lane Divided Roadways (Portable Concrete Barrier-PCB)	04/19/02
ere transit on a party	MT-95.80	286	224	Two-Lane, Two-Way Operation For Use On Four Lane Divided Roadways (Asphalt Curb Divider)	04/19/02
	MT-95.81	98	96	Two-Lane, Two-Way Operations For Use On Four Lane Divided Roadways (Asphalt Curb Divider With Delineation)	04/19/02
*	MT-95.82	<u>55</u>	41	Adjustment For Two Lane, Two-Way Operation On Four Lane Divided Roadways	04/19/02
A STATE OF THE STA	MT-96.10	201	<u>136</u>	Signalized Closing 1 Lane Of A 2 Lane Highway With Drums	04/19/02
	MT-96.11	<u>214</u>	<u>170</u>	Signalized Closing 1 Lane Of A 2 Lane Highway With PCB	04/19/02
ALT ( V. Managary & Street, and A. V. Aller	MT-96.20	84	88	Details For Signalized Closing 1 Lane Of A 2 Lane Highway - Side Mounted	04/19/02
and a crypton specific (a) become (A.C.)	MT-96.21	<u>78</u>	90	Details For Signalized Closing 1 Lane Of A 2 Lane Highway - Overhead Mounted	04/19/02
	MT-96.25	137	33	Pre-Timed-Wiring Diagram For Signalized Closing 1 Lane Of A 2 Lane Highway	04/20/01
Ļ	MT-96.26	166	<u>50</u>	Actuated-Wiring Diagram For Signalized Closing 1 Lane Of A 2 Lane Highway	04/20/01
And the second of the second	MT-97.10	<u>188</u>	81	Flaggers Closing 1 Lane Of A 2 Lane Highway For Stationary Operations	04/19/02
Trans. C. States of the Park Control	MT-97.11	174	<u>95</u>	r aving Operations	04/19/02
	MT-97.12	177	<u>97</u>	Flaggers Closing 1 Lane Of A 2 Lane Highway For Paving Operations (FED)	04/19/02
400	MT-98.12	181	<u>85</u>	Lane Closure In Deceleration Lane	04/19/02

	MT-98.13	220	115	Lane Closure Before Exit Gore	04/19/02	
	MT-98.14	201	118	Lane Closure At Exit Gore	04/19/02	
	MT-98.15	164	70	Lane Closure At Entrance Ramp: Plan A	07/16/04	
	MT-98.16	306	133	Lane Closure At Entrance Ramp: Plan B	04/19/02	
	MT-98.17	151	78	Typical Lane Closure In Deceleration Lane And Ramp For Closing Inside Portion Of Curve	10/18/02	
	MT-98.18	188	86	Typical Lane Closure In Ramp For Closing In Ramp For Closing Outside Portion Of Curve	10/18/02	
	MT-98.19	94	58	Exit Ramp Closure	10/18/02	
*	MT-99.20M (metric)	294	42	Traffic Control For Long Line Pavement Marking Operations	01/30/95	
	MT-99.50	91	<u>70</u>	Freeway/Expressway Closure Using Drums	10/18/02	
	MT-99.51	112	92	Freeway/Expressway Closure Using Temporary Concrete Median Barrier	10/18/02	
	MT-99.60	183	98	Short Duration Closing of Rural Divided Highway	10/18/02	
*	MT-100.00	<u>184</u>	<u>135</u>	Temporary Crossover Lighting System	04/19/02	
*	MT-101.20	275	<u>32</u>	Temporary Raised Pavement Markers	10/18/02	
*	MT-101.70	44	<u>25</u>	Portable Concrete Barrier	10/18/02	
	MT-102.10	308	<u>183</u>	Transition Plan For Use Of Shoulder With PCB	10/18/02	
	MT-102.20	287	176	Transition Plan For Use Of Shoulder With Drum	10/18/02	
*	MT-105.10	270	34	Temporary Sign Support	10/18/02	
*	MT-105.11	100	174	Temporary Sign Support	10/18/02	
	MT-110.10	268	49	Detour Of Pedestrians To Temporary Walkway On Roadway	10/18/02	
2000	MT-110.20	247	<u>50</u>	Detour Of Pedestrians To Other Side Of Street	10/18/02	
Action Services	MT-110.30	242	<u>54</u>	Detour Of Pedestrians To Another Facility	10/18/02	
	MT-120.00	207	138	New Signal Activation	03/01/00	
]	Traffic Control Standard Construction Drawings (return to top)					
	TC-07.65	244	324	Aluminum Truss Overhead Sign Support	07/18/03	
THE STATE WATER WATER	TC-09.10	185	263	Semi-Overhead Sign Support	01/19/01	
And the factories	TC-09.30	<u>213</u>	282	Center Mount Overhead Sign Support	01/19/01	
_	TC-12.30	330	213	Cantilever Overhead Sign Support	01/19/01	
L	TC-15.115	<u>213</u>	275	Steel Truss Overhead Sign Support	07/18/03	
L	TC-16.20	<u>253</u>	239	Single Arm Overhead Sign Support	01/19/01	
L	TC-17.10	<u>156</u>	<u>258</u>	Span Wire Overhead Sign Support	01/19/01	
	TC-18.24	<u>129</u>	142	Flush Structure Mounted Sign Support	01/18/02	
	TC-18.26	<u>278</u>	294	Skewed Structure Mounted Sign Support	01/18/02	
	TC-21.10	132	115	Sign Support Foundations	01/19/01	
	TC-21.20	272	212	Foundations	01/19/01	
A Marian Commence	TC-21.40	<u>121</u>	<u>181</u>	Concrete Barrier Median Overhead Sign Support Foundations	01/18/02	
L	TC-21.41	167	214	Barrier Wall Assembly For Sign Supports	01/18/02	
and the same of th	TC-22.10	<u>119</u>	<u>137</u>	Miscellaneous Overhead Sign Support Details	01/19/01	
April 1410 gran	TC-22.20	212	<u>180</u>	Sign Attachment Assemblies	01/19/01	
.	TC-31.21	<u>252</u>	268	Mercury Vapor Sign Lighting Details	04/20/01	
	TC-32.10	102	160	Sign Service Details I	04/19/02	
-	TC-32.11	196		Sign Service Details II		

	1	ii .	u .	II .	_
. *	TC-41.10	302	231	Structural Beam Sign Supports	01/19/01
华	TC-41.20	146	208	Yielding Post	01/19/01
	TC-41.40	123	<u>185</u>	Special Sign Attachments and Supports	07/16/04
	TC-41.41	99	<u>162</u>	Special Sign Attachments	01/19/01
	TC-41.50	99	120	"One Way" Sign Support Details	07/16/04
	TC-42.10	147	93	Typical Sign Placement Guide Signs	01/19/01
*	TC-42.20	170	368	Typical Flat Sheet Sign Placement	07/16/04
	TC-51.11	146	144	Aluminum Bolted-Extrusheet Panel Sign	04/20/01
	TC-51.12	143	158	Aluminum Bolted-Extrusion Panel Sign	04/20/01
*	TC-52.10	147	143	Sign Blank Details I	04/20/01
*	TC-52.20	276	<u>173</u>	Sign Blank Details II	04/20/01
	TC-61.10	<u>136</u>	238	Delineator Details	01/19/01
	TC-65.10	91	<u>196</u>	Raised Pavement Marker Placement Details	01/21/05
	TC-65.11	<u>264</u>	900	Raised Pavement Marker Spacing Details	01/21/05
*	TC-71.10	216	<u>157</u>	Word and Symbol Pavement Markings	01/21/05
	TC-72.20	112	<u>263</u>	Freeway Entrance and Exit Markings	01/21/05
*	TC-73.10	69	<u>60</u>	Pavement Marking Details	01/19/01
and the second	TC-81.10	325	259	Strain Pole Details	05/01/00
	TC-81.20	<u>205</u>	<u>619</u>	Single Arm Overhead Signal Support	01/16/04
	TC-82.10	<u>261</u>	340	Vehicle Detector Installation Details	04/19/02
	TC-83.10	222	<u>180</u>	Pole Mountings For Controller And Power Service	05/01/00
	TC-83.20	<u>207</u>	148	Controller Foundation And Pedestals	01/16/04
And department of the	TC-84.20	<u>182</u>	231	Messenger Wire Details	05/01/00
Capper Control (A)	TC-84.21	89	77	Messenger Wire Details II	03/06/00
	TC-85.10	<u>194</u>	<u>158</u>	Pole Mountings For Signal Heads	04/19/02
	TC-85.20	<u>228</u>	<u>321</u>	Overhead Signal Attachments	05/01/00

return to top of page

