

SEDIMENT CONTROL DEVICES MUST BE INSTALLED PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTINUED INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL DEVICES. THE CONTRACTOR SHALL FOLLOW THE REQUIREMENTS SET FORTH ON THE APPROVED.

THE APPROVED STORMWATER POLLUTION PREVENTION PLAN IF APPLICABLE, OR AS DETAILED ON

THE CONSTRUCTION PLANS, AND AS SPECIFIED BY THE CITY OF MASSILLON."

COPYRIGHT

THIS DRAWING AND ITS

DESIGN ARE THE PROPERTY

AUTHORIZED REPRODUCTION

OR USE OF THIS DOCUMENT

IS PROHIBITED.

OF THE ARCHITECT. UN-

NEW OFFICE BUILDING

For

HAMEL INSURANCE 956 FIRST STREET, N.E. MASSILLON, OHIO 44646

Prepared by

Roger A. Westfall 9465 Rohrland, N.W. Massillon, Ohio 44647 (330) 832-8389



Project #01-101

2/10/02

CODE DATA

SOLELY DUE TO THE FACT THESE DOCUMENTS ARE DEVELOPED FOR

IF QUESTIONS ARISE DURING PRODUCT SELECTIONS AS TO CODE COMPLIANCE, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY

THE ARCHITECT IMMEDIATELY FOR CLARIFICATION (PRIOR TO

BUILDING PERMITS TO SHOW COMPLIANCE.

IMPLEMENTING SUCH WORK IN PLACE)

SCOPE OF WORK--CONSTRUCT A NEW WOOD FRAME & VINYL/BRICK/STONE FACILITY ON A LOT WITH AN EXISTING OFFICE TO BE REMOVED.


USE GROUP B (BUSINESS) CONSTRUCTION CLASSIFICATION--5B (NON-PROTECTED) BUILDING HEIGHT--12'-0" (AVERAGE) BUILDING AREA--55'-4" X 40'-4" = 2224 SF ALLOWABLE AREA PER TABLE 503 = 2 STORY 30' HT. AREA 7200 SF OCCUPANT LOAD--15 PERSONS (ACTUAL) RESTROOMS--ONE ADAAG FACILITY ONE STAFF FACILITY


BUILDING SETBACKS--SHOWN ON SITE PLAN ASSUMPTIVE SOIL BEARING CAPACITY 2000 PSF 2 REMOTE EXITS PROVIDED + ONE EXTERIOR STAIR FROM BASEMENT GRADE LEVEL ACCESS + 2 HANDICAPPED PARKING SPACES NO FIRE SUPPRESSION PROVIDED--UNOCCUPIED BASEMENT HAS EXTERIOR STAIR AS EXEMPTION FROM WINDOWLESS STORY


25 PSF Roof Top Chord LL = Top Chord DL = 15 PSF 40 PSF Total = = 15 PSF Wind Load Ground Snow Load = 25 PSF (80 m.p.h.) Seismic Design: Av = .077Aa = .10Seismic Hazard Group = Group I Structural System = Braced Frame Performance Category = C Soil Profile = \$4 Response Factor R = 8Deflection Amplification rC = 450 PSF Uniform Live Load Floor Load


2000 PSF Max. Concentrated Loads A permit must be obtained from the City prior to any work being performed inside the City's right of way. The Contractor must notify the City Engineer's Office 48 hours prior to any construction inside the City's right of way in order to coordinate


ZONTING CLASSIFICATION ____ O-1 DEEVISED 5.26-02 1 PEVISED 4-3-02

















SPECIFICATIONS FOR TEMPORARY SEEDINGS

SPECIFIC	ATIONS FOR TE	MPORARY SE	EDINGS .
KIND OF SEED	SEEDING DATES	PER 1000 SQ. FT.	PER ACRE
OATS	MARCH 1 - JUNE 15	3 POUNDS	4 BUSHEL
OATS AND SUDANGRASS	JUNE 16 - AUG. 15	2 POUNDS 2 POUNDS	2 BUSHEL, 2 BUSHEL
RYE OR WHEAT	AUG. 16 - NOV. 1	3 POUNDS	2 BUSHEL

I. AFTER NOVEMBER I USE MULCH ONLY. APPLY THE MULCH AT A RATE OF 3 TON PER ACRE.

2. THESE SEEDING DATES ARE IDEAL WITH THE USE OF MULC

EROSION CONTROL NOTES

- 1. THE EROSION CONTROL MEASURES DESCRIBED HEREIN ARE TYPICAL. THE SITEWORK CONTRACTOR SHALL USE THE SITE PLAN AS A GUIDE TO CONTROL EROSION. IN THE EVENT OF ADVERSE WEATHER CONDITIONS, ETC., ADDITIONAL MEASURES SHOULD BE TAKEN TO ESTABLISH AND MAINTAIN PROTECTIVE VEGETATION. EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO THE START OF ANY EARTHWORK.
- REGULAR INSPECTION AND CONTINUOUS MAINTENANCE WILL BE REQUIRED AS NECESSARY
 UNTIL PERMANENT VEGITATIVE COVER HAS BEEN ESTABLISHED AND EROSION HAS BEEN
 CONTROLLED. THIS INCLUDES BUT NOT LIMITED TO RESEEDING, MULCHING, EARTH FILLING,
 ETC.
- 3. DISTURBED AREAS AND EXPOSURE TIME OF EXCAVATION IN THOSE AREAS BEFORE PERMANENT GROUND COVER IS COMPLETE SHALL BE KEPT TO A MINIMUM, REPLACE ANY EXISTING TOPSOIL ERODED DURING THE CONSTRUCTION.
- 4. TEMPORARY EROSION CONTROL SHALL CONFORM TO ODOT 207, TEMPORARY SOIL EROSION AND SEDIMENT CONTROL AS TYPIFIED ON THE PLANS AND ODOT STANDARD CONSTRUCTION DRAWING DETAIL MC-11. SILT FENCES OR BALE INLET FILTERS ARE TO BE CONSTRUCTED IN FRONT OF ALL STORM INLETS, HEADWALLS AND PIPE OUTLETS. OTHER EROSION CONTROL ITEMS, SUCH AS SEDIMENT PITS, MAY BE REQUIRED TO CONTAIN WATER RUN-OFF DEPENDING ON THE SCOPE AND LOCATION OF DISTURBED AREAS.
- 5. THE ESTABLISHMENT OF PERMANENT GROUND COVER SHALL CONFORM TO ODOT ITEM 659, SEEDING AND MULCHING.
- 6. IF SMALL HILLS OR GULLIES DEVELOP, TEMPORARY DIVERSIONS OF EARTH FILL OR STRAW BALES SHOULD BE INSTALLED UNTIL SATISFACTORY SEEDING IS ESTABLISHED. DIVERSION DITCHES SHALL BE CONSTRUCTED AT THE TOP OF 2:1 SLOPES.
- 7. TO ASSIST IN EROSION CONTROL, ALL TREES AND VEGETATION OUTSIDE OF GRADED AREAS SHALL REMAIN.
- 8. TEMPORARY STRAW BALE SEDIMENT CONTROL DIKES SHALL BE AS DETAILED, SILT FENCE FABRIC SHALL BE EXXON GTF-1005 OR APPROVED EQUAL.
- 9. ADJACENT ROADS SHALL BE KEPT FREE OF DIRT AND DEBRIS AT ALL TIMES.
- 10. COMPLETED SITE CONSTRUCTION WITH EARTH EXPOSED LONGER THAN 45 DAYS SHALL BE TEMPORARILY SEEDED WITHIN 7 DAYS (SEE SCHEDULES).
 11. CONTRACTOR SHALL KEEP A COPY OF THE SOIL EROSION CONTROL PLAN AT THIS CONSTRUCTION SITE AT ALL TIMES.
- 12. EROSION CONTROL WORK SHALL BE REMOVED WHEN IT HAS SERVED ITS USEFULNESS SO AS NOT TO BLOCK OR IMPEDE THE PERMANENT STORM FLOW AND DRAINAGE PATHS.

COPYRIGHT

THIS DRAWING AND ITS
DESIGN ARE THE PROPERTY
OF THE ARCHITECT. UNAUTHORIZED REPRODUCTION
OR USE OF THIS DOCUMENT
IS PROHIBITED.

NEW OFFICE BUILDING
HAMEL INSURANCE

956 FIRST ST. MESSILLON

ROGER A. WESTFALL

REGISTERED ARCHITECT

9465 ROHRAND NW.



SITE PETAILS

PROJ. NO. 01-101

DRAWING NO.

