

SCALE: HORIZ: 1"=30"

CONTOUR INTERVAL=1'

ELEVATION=1008.31

RELOCATE POLE -

SAN. M.H

T/C 1007.81 FL 8" 999.38

CALL TOLL FREE 800-362-2764

OHIO UTILITIES PROTECTION SERVICE

NON-MEMBERS

MUST BE CALLED DIRECTLY

THAN 3' AT THE SUBBASE LEVEL

IT MUST BE CURED AT LEAST 48 HRS.

CONCRETE BASE SHALL BE OF 1:2:4, 6 BAG MIX, PORTLAND

CEMENT CONCRETE USING HIGH EARLY STRENGTH CEMENT AND

HORIZ: 1"=30' JAD oF LOT RO, UTILITY PLAN

- WALNUT

MASSILLON, COU

SEING PART OF C


H O H

SCALE: 1" = 30'

- 1. INLET PROTECTION SHALL BE CONSTRUCTED EITHER BEFORE UPSLOPE LAND DISTURBANCE BEGINS OR BEFORE THE STORM DRAIN BECOMES OPERATIONAL
- 2. THE EARTH AROUND THE INLET SHALL BE EXCAVATED COMPLETELY TO A DEPTH AT LEAST 18
- 3. THE WOODEN FRAME SHALL BE CONSTRUCTED OF 2 IN BY 4 IN. CONSTRUCTION GRADE LUMBER. THE 2 IN. BY 4 IN. POSTS SHALL BE DRIVEN 18 IN. INTO THE GROUND AT FOUR CORNERS OF THE INLET AND THE TOP PORTION OF 2 IN. BY 4 IN. FRAME ASSEMBLED USING THE OVERLAP JOINT SHOWN. THE TOP OF THE FRAME SHALL BE AT LEAST 6 IN. BELOW ADJACENT ROADS IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC.
- 4. WIRE MESH SHALL BE OF SUFFICIENT STRENGTH TO SUPPORT FABRIC WITH WATER FULLY IMPOUNDED AGAINST IT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY TO
- 5. GEOTEXTILE SHALL HAVE AN EQUIVALENT OPENING SIZE OF 20 - 40 SIEVE AND BE RESISTANT TO SUNLIGHT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY. IT SHALL EXTEND FROM THE TOP OF THE FRAME TO 18 IN. BELOW THE INLET NOTCH ELEVATION. THI GEOTEXTILE SHALL OVERLAP ACROSS ON SIDE OF THE INLET SO THE ENDS OF THE CLOTH ARE NOT FASTENED TO THE SAME POST.
- BACKFILL SHALL BE PLACED AROUND THE INLET IN COMPACTED 6 IN. LAYERS UNTIL THE EARTH IS EVEN WITH NOTCH ELEVATION ON ENDS AND TOP ELEVATION ON SIDES.
- A COMPACTED EARTH DIKE OR A CHECK DAM SHALL BE CONSTRUCTED IN THE DITCH LINE BELOW THE INLET IF THE INLET IS NOT IN A DEPRESSION AND IF RUNOFF BYPASSING THE INLET WILL NOT FLOW TO A SETTLING POND. THE TOP OF EARTH DIKES SHALL BE AT LEAST 6 IN. HIGHER THAN THE TOP OF THE FRAME.

INLET PROTECTION IN SWALES. DITCH LINES OR YARD INLETS

(IP)



1. STONE SIZE - TWO-INCH STONE SHALL BE USED, OR RECYCLED CONCRETE EQUIVALENT.

2. LENGTH - THE CONSTRUCTION ENTRANCE SHALL BE AS LONG AS REQUIRED TO STABILIZE HIGH TRAFFIC AREAS BUT NOT LESS THAN 50 FT. (EXCEPT ON SINGLE RESIDENCE LOT WHERE A 30-FT. MINIMUM LENGTH APPLIES.

3. THICKNESS - THE STONE LAYER SHALL BE AT LEAST 6 IN. THICK.

4. WIDTH - THE ENTRANCE SHALL BE AT LEAST 10 FT. WIDE, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.

5. BEDDING - A GEOTEXTILE SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL HAVE A GRAB TENSILE STRENGTH OF AT LEAST 200 LB. AND A MULLEN BURST STRENGTH OF AT LEAST 190 LB.

6. CULVERT - A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE FROM BEING DIRECTED OUT ONTO PAVED SURFACES.

7. WATER BAR - A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF NEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.

8. MAINTENANCE - TOP DRESSING OF ADDITIONAL STONE WALL SHALL BE APPLIED AS CONDITIONS DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING.

9. CONSTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND PREVENT OFF-SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION SITE SHALL BE RESTRICTED FROM MUDDY AREAS.

CONSTRUCTION ENTRANCE

SITE INFORMATION

SITE DESCRIPTION - EXISTING - WOODED LOT

PROPOSED - BUILDING & PARKING

TOTAL AREA OF SITE - 2.21 AC. AREA OF SITE TO UNDERGO EXCAVATION - 2.7± AC.

PRE-CONSTRUCTION RUNOFF COEFFICIENT - 0.3 POST-CONSTRUCTION RUNOFF COEFFICIENT - 0.7

SCHEDULE OF MAJOR CONSTRUCTION COMMENCEMENT - WINTER 2001 COMPLETION - SPRING 2002

RECEIVING STREAM AND SURFACE WATERS OVERLAND FLOW TO DITCH, THEN CITY STORM SEWER WHICH OUTLETS INTO THE TUSCARAWAS RIVER.

EXISTING SOILS ON SITE CHILI & CONOTTON GRAVELY LOAMS, 25 TO 50 PERCENT SLOPES, MODERATLEY ERODED

CHILI URBAN LAND COMPLEX, UNDULATING

TEMPORARY SEEDING SPECIES SELECTION			
SEEDING DATES	SPECIES	LB./1,000 FT. ²	PER ACRE
MARCH 1 TO AUGUST 15	OATS	3	4 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	PERENNIAL RYGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
AUGUST 16 TO NOVEMBER 1	RYE	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	WHEAT	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	PERENNIAL RYEGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
NOVEMBER 1 TO SPRING SEEDING	USE MULCH ONLY, SO	DDDING PRACTICES OF	DORMANT SEEDING.
NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.			

	PERMA	NENT SEEDIN	G		
SEED MIX	SEEDING RATE				
	LB./AC.	LB./AC. LB./1,000		NOTES:	
GENERAL USE					
CREEPING RED FESCUE DOMESTIC RYEGRASS KENTUCKY BLUEGRASS	20-40 10-20 10-20	1/2-1 1/4-1/2 1/4-1/2			
TALL FESCUE	40	1			
DWARF FESCUE	40	1			
ST	EP BANKS	OR CUT SLO	PES		
TALL FESCUE	40	1			
CROWN VETCH TALL FESCUE	10 20	1/4	DO N	NOT SEED LATER THAN	AUGUST.
FLAT PEA TALL FESCUE	20 20	1/2 1/2	DO N	NOT SEED LATER THAN	AUGUST.
ROAD DITCHES AND SWALES					
TALL FESCUE	40	1			
DWARF FESCUE KENTUCKY BLUEGRASS	90 5	2 1/4			
LAWNS					
KENTUCKY BLUEGRASS PERENNIAL RYEGRASS	60 60	1 1/2			
KENTUCKY BLUEGRASS CREEPING RED FESCUE	60 60	1 1/2 1 1/2		FOR SHADED AREAS.	
NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.					

NENT	SEEDING	


TRAPS SHALL BE INSTALLED AND STABILIZED WITH TEMPORARY SEEDING PRIOR TO GRADING THE RES
OF THE CONSTRUCTION SITE.


1. STRUCTURAL EROSION AND SEDIMENT CONTROL

- 2. TEMPORARY SEED SHALL BE APPLIED BETWEEN CONSTRUCTION OPERATIONS ON SOIL THAT WILL NOT BE GRADED OR RE-WORKED FOR 45 DAYS OR MORE. THESE IDLE AREAS SHOULD BE SEEDED AS SOON AS POSSIBLE AFTER GRADING OR SHALL BE SEEDED WITHIN 7 DAYS. SEVERAL APPLICATIONS OF TEMPORARY SEEDING ARE NECESSARY ON TYPICAL CONSTRUCTION PROJECTS.
- 3. THE SEED BED SHOULD BE PULVERIZED AND LOOSE TO ENSURE THE SUCCESS OF ESTABLISHING VEGETATION. HOWEVER, TEMPORARY SEEDING SHALL NOT BE POSTPONED IF IDEAL SEED BED PREPARATION IS NOT POSSIBLE.
- 4. SOIL AMENDMENTS APPLICATIONS OF TEMPORARY VEGETATION SHALL ESTABLISH ADEQUATE STANDS OF VEGETATION WHICH MAY REQUIRE THE USE OF SOIL AMENDMENTS. SOIL TESTS SHOULD BE TAKEN ON THE SITE TO PREDICT THE NEED FOR LIME AND FERTILIZER.
- 5. SEEDING METHOD SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDROSEEDER. WHEN FEASIBLE, SEED THAT HAS BEEN BROADCAST SHALL BE COVERED BY RAKING OR DRAGGING AND THEN LIGHTLY TAMPED INTO PLACE USING A ROLLER OF OF CULTIPACKER. IF HYDROSEEDING IS USED, THE SEED AND FERTILIZER WILL BE MIXED ON-SITE AND THE SEEDING SHALL BE DONE IMMEDIATELY AND WITHOUT INTERRUPTION.

TEMPORARY SEEDING

(SEE SITE PLAN) **EXCAVATED** (SEE SITE PLAN) 2:1 SIDE SLOPES PLAN VIEW TOP WIDTH





DEWATERING PIPE SECTION

SEDIMENT TRAPS

SEDIMENT TRAP NOTES:

- 1. SEDIMENT TRAPS SHALL BE CONSTRUCTED AND OPERATIONAL BEFORE UPSLOPE LAND DISTURBANCE
- 2. THE AREA UNDER THE EMBANKMENT SHALL BE CLEARED, GRUBBED, AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED AS NEEDED TO FACILITATE SEDIMENT CLEANOUT.
- 3. FILL MATERIAL USED FOR THE EMBANKMENT SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVERSIZED STONES, ROCKS, ORGANIC MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED. MAXIMUM HEIGHT OF THE EMBANKMENT SHALL BE 5 FT. AS MEASURED FROM THE SURROUNDING GROUND.
- 4. CUT-AND-FILL SLOPES SHALL BE 2:1 OR FLATTER.
- DIKES DIRECTING WATER TO THE TRAP SHALL BE HIGHER THAN THE HEIGHT OF THE EMBANKMENT.
- 6. TEMPORARY SEEDING SHALL BE ESTABLISHED ON ALL NON-SUBMERGED AREAS OF THE SEDIMENT
- 7. THE STORAGE VOLUME SHALL BE ACHIEVED TO THE DIMENSIONS SHOWN IN THE PLANS TO ACHIEVE 67 CY OF STORAGE VOLUME BELOW THE CREST OF THE OUTLET FOR EVERY ACRE OF CONTRIBUTING DRAINAGE AREA.
- 8. THE OUTLET SPILLWAY SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN IN THE PLANS.
- 9. GEOTEXTILE SHALL BE PLACED OVER THE BOTTOM AND SLOPES OF THE OUTLET SPILLWAY. GEOTEXTILE SHALL CONTINUE DOWNSTREAM OF THE FMBANKMENT TO FORM AN APRON ON THE SURROUNDING GROUND. TO PREVENT RUNOFF FROM FLOWING UNDER THE GEOTEXTILE, THE SECTIONS PLACED NEAREST THE FRONT SHALL OVERLAP FOLLOWING SECTIONS. SECTIONS OF GEOTEXTILE SHALL OVERLAP AT LEAST 2 FT.
- 10. ROCK USED IN THE OUTLET SPILLWAY SHALL BE PLACED 1 FT. THICK ON THE GEOTEXTILE. THE ROCK SHALL BE BETWEEN TYPE C AND TYPE D ROCK WHERE Dso IS ABOUT 8 IN.
- 11. SEDIMENT SHALL BE REMOVED AND THE SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS FILLED ONE-HALF THE POND'S ORIGINAL DEPTH. REMOVED SEDIMENT SHALL BE SPREAD IN A SUITABLE AREA AND STABILIZED SO IT WILL NOT
- 12. THE STRUCTURE AND ACCUMULATED SEDIMENT SHALL BE PERMANTLY STABILIZED WHEN THE DRAINAGE AREA HAS BEEN STABILIZED.

EROSION CONTROL NOTES

- 1. ALL PROPERTIES ADJACENT TO THE SITE OF SOIL-DISTURBING ACTIVITY SHALL BE PROTECTED TO THE MAXIMUM EXTENT PRACTICABLE. FROM SOIL EROSION AND SEDIMENT RUNOFF AND DRAINAGE, INCLUDING, BUT NOT LIMITED TO PRIVATE PROPERTIES, NATURAL AND ARTIFICIAL WATERWAYS, WETLANDS, STORM SEWERS AND PUBLIC LANDS.
- 2. CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL PRACTICES USED TO SATISFY THIS REQUIREMENT SHALL CONFORM, AS A MINIMUM, TO STATE OF OHIO STANDARDS AS SET FORTH IN THE MOST-CURRENT EDITION OF THE RAINWATER AND LAND DEVELOPMENT MANUAL, DEFINED BY THE OHIO DEPARTMENT OF NATURAL RESOURCES DIVISION OF SOIL AND WATER CONSERVATION AND NATURAL RESOURCE CONSERVATION SERVICE AND SHALL CONFORM TO THE MOST CURRENT OHIO ENVIRONMENTAL PROTECTION AGENCY, OHIO REVISED CODE CHAPTER 6111 REQUIREMENTS.
- 3. EROSION AND SEDIMENT CONTROL PLAN APPROVALS ISSUED IN ACCORDANCE WITH THESE RULES DO NOT RELIEVE THE OWNER OF RESPONSIBILITY FOR OBTAINING ALL OTHER NECESSARY PERMITS AND OR APPROVALS FROM FEDERAL STATE, AND/OR COUNTY AGENCIES. IF REQUIREMENTS VARY, THE MOST STRINGENT REQUIREMENTS SHALL BE FOLLOWED.
- 4. EROSION AND SEDIMENT CONTROL PRACTICES AT THE SITE, AND AS IDENTIFIED IN THE ESC PLAN SHALL COMPLY WITH THE FOLLOWING:
- A. AN APPROVED EROSION AND SEDIMENT CONTROL PLAN OR APPROVAL LETTER FROM THE STARK SWCD SHALL BE LOCATED ON SITE FOR REVIEW.
- B. LIMITS TO CLEARING AND GRADING SHALL BE SHOWN ON ESC PLANS. LIMITS TO CLEARING AND GRADING SHALL BE CLEARLY MARKED ON SITE WITH SIGNAGE, FLAGGING, AND/OR
- C. INSTALL EROSION AND SEDIMENT PERIMETER CONTROLS AS A FIRST ACTION OF CONSTRUCTION AS SPECIFIED BY CONSTRUCTION SEQUENCE. THIS SHALL INCLUDE AND IS NOT LIMITED TO PROTECTIVE BMP'S FOR STREAM CORRIDORS AND CROSSINGS, WETLANDS, SITE ENTRANCE, SEDIMENT TRAPS & BASINS, BARRIERS, AND DIVERSION DIKES.
- D. CONCENTRATED STORM WATER RUNOFF SHALL PASS THROUGH A SEDIMENT CONTROL DEVICE BEFORE EXITING THE SITE BOUNDARIES. CONCENTRATED RUNOFF FROM BARE SOIL AREAS SHALL BE DIVERTED INTO A SETTLING POND OR SEDIMENT CONTROL STRUCTURE, OR OTHER APPROVED SEDIMENT BARRIER BEFORE LEAVING THE SITE.
- E. EARTHEN STRUCTURES SUCH AS DAMS, BASINS, STREAM MODIFICATIONS AND WATER DIVERSIONS SHALL BE SEEDED AND MULCHED WITH IN SEVEN (7) DAYS OF THE COMPLETION OF INSTALLATION. DAMS SHALL CONFORM TO THE OHIO DAM LAWS (ORC 1521.06).
- F. STABILIZATION OF CRITICAL AREAS WITHIN 50 FEET OF ANY STREAM OR WETLAND SHALL BE TEMPORARILY STABILIZED WITHIN TWO (2) DAYS OF DISTURBANCE IF AREA WILL REMAIN INACTIVE FOR FOURTEEN (14) DAYS OR LONGER. CONSTRUCTION VEHICLES SHALL AVOID STREAMS AND THE 50 FOOT BUFFER AREAS. IF AN ACTIVE DRAINAGEWAY MUST BE CROSSED BY CONSTRUCTION VEHICLES REPEATEDLY DURING CONSTRUCTION, A TEMPORARY STREAM CROSSING SHALL BE CONSTRUCTED ACCORDING TO THE SPECIFICATIONS IN THE RAINWATER & LAND DEVELOPMENT BOOK. CONSTRUCTION OF BRIDGES, CULVERTS OR SEDIMENT CONTROL STRUCTURES SHALL NOT PLACE SOIL, DEBRIS AND OTHER FINE PARTICULATE MATERIAL INTO OR CLOSE TO THE WATER RESOURCE IN SUCH A MANNER THAT IT MAY SLOUGH, SLIP OR ERODE.
- G. STORM SEWER INLETS (AND SANITARY) SHALL BE PROTECTED SO THAT SEDIMENT-LADEN RUNOFF WILL NOT ENTER THE STORM SEWER SYSTEM WITHOUT FIRST BEING FILTERED AND/OR TREATED.
- H. RE-VEGETATE SOIL. TEMPORARY SOIL STABILIZATION SHALL OCCUR WITHIN SEVEN (7) DAYS AFTER ROUGH GRADING IF THE AREA WILL REMAIN IDLE LONGER THAN THIRTY (30) DAYS. PERMANENT SOIL STABILIZATION SHALL BE INSTALLED WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. PERMANENT VEGETÁTION IS A GROUNDCOVER DENSE ENOUGH TO COVER 80% OF THE SOIL SURFACE AND MATURE ENOUGH TO SURVIVE WINTER WEATHER CONDITION.

I. SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED TO PREVENT SOIL LOSS. STABILIZATION SHALL BE REQUIRED IF STOCKPILES ARE LOCATED WITHIN CRITICAL AREAS

- NEAR STREAMS OR WETLANDS, OR IF DETERMINED BY THE STARK SWCD THAT SEDIMENT FROM STOCKPILES WILL LEAVE THE SITE. J. UNSTABLE SOILS PRONE TO SLIPPING OR SLOUGHING SHALL NOT BE CLEARED, GRADED, EXCAVATED, FILLED OR HAVE LOADS IMPOSED UPON THEM UNLESS THE WORK IS PLANNED BY A QUALIFIED PROFESSIONAL ENGINEER AND INSTALLED IN ACCORDANCE WITH THE ESC
- PLAN. CUT AND FILL SLOPES SHOULD BE DESIGNED TO MINIMIZE EROSION PROBLEMS. ADEQUATE SLOPE DESIGN INCLUDES USE OF ROUGH SOIL SURFACE ALONG THE FACE OF THE SLOPE; WATER DIVERSION ALONG THE TOP OF THE SLOPE AWAY FROM THE FACE; TERRACES TO REDUCE SLOPE LENGTH; DELIVERY OF CONCENTRATED STORM WATER FLOWS TO THE BASE OF THE SLOPE VIA ADEQUATE CHANNEL OR PIPE; AND DRAINAGE FOR WATER SEEPS IN THE SLOPE THAT ENDANGER SLOPE STABILITY.
- K. SOIL SHALL BE REMOVED FROM PAVED SURFACES AND/OR PUBLIC ROADS AT THE END OF EACH DAY IN SUCH A MANNER THAT DOES NOT CREATE OFF-SITE SEDIMENTATION IN ORDER TO ENSURE SAFETY AND ABATE OFF-SITE SOIL LOSS. COLLECTED SEDIMENTS SHALL BE PLACED IN A STABLE LOCATION ON SITE OR TAKEN OFF-SITE TO A STABLE LOCATION.
- L. STABILIZE DISTURBED OR MODIFIED DRAINAGE WAYS. REDUCE EROSION EFFECTS OF STORM WATER BY USING AND/OR MAINTAINING GRASSED SWALES, INFILTRATION STRUCTURES, OR WATER DIVERSIONS.
- M. SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED ONCE EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF A 0.5" OR GREATER RAINFALL EVENT. A WRITTEN LOG OF THESE INSPECTIONS AND IMPROVEMENTS TO CONTROLS SHALL BE KEPT ON SITE. THE INSPECTIONS SHALL INCLUDE THE DATE OF INSPECTION, NAME OF INSPECTOR, WEATHER CONDITIONS, ACTIONS TAKEN TO CORRECT ANY PROBLEMS AND THE DATE CORRECTIVE ACTIONS WERE TAKEN.
- N. TRENCHES FOR UNDERGROUND UTILITY LINES AND PIPES SHALL BE TEMPORALLY STABILIZED WITHIN SEVEN (7) DAYS IF THEY ARE TO REMAIN INACTIVE FOR THIRTY (30) DAYS. TRENCH DEWATERING DEVICES SHALL DISCHARGE IN A MANNER THAT FILTERS SOIL-LADEN WATER BEFORE DISCHARGING IT TO A RECEIVING DRAINAGE DITCH OR POND. IF SEEDING, MULCHING , OR OTHER EROSION AND SEDIMENT CONTROL MEASURES WERE PREVIOUSLY INSTALLED, THESE PROTECTIVE MEASURES SHALL BE REINSTALLED.
- 5. CONTRACTOR'S CONSTRUCTION SEQUENCE:
- A. INITIAL CLEARING AND GRUBBING TO GAIN ACCESS, AND INSTALLATION OF PERIMETER CONTROLS WITHIN SEVEN (7) DAYS OF CLEARING AND GRUBBING.
- B. CLEARING AND GRUBBING FOLLOWED BY EXCAVATION OF SEDIMENT TRAPS AND BASINS; TEMPORARY SOIL STABILIZATION FOR THESE SEDIMENT SETTLING DEVICES WITHIN FOURTEEN (14) DAYS OF EXCAVATION.
- C. MAINTENANCE INSPECTION SCHEDULE AND PARTY RESPONSIBLE FOR INSPECTION AND REPAIR OF EROSION AND SEDIMENT CONTROL DEVICES.
- D. PRE-WINTER STABILIZATION MEETING IF PROJECT IS TO BE THROUGH THE WINTER.
- E. FINAL GRADING AND PERMANENT SOIL STABILIZATION WITHIN 30 DAYS OF FINISHING FINAL GRADE.
- F. REMOVAL OF TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES.

ST/ 57 APC OF LOT Õ 50 WALNUT DE. S

SCALE:

