

SECTION A-A

PEAK WATER ELEVATIONS  
IN DETENTION BASIN:  
10 YEAR = 976.99  
25 YEAR = 977.53  
100 YEAR = 978.24

R=60.00'  
Δ=24°37'28"  
T=13.10'  
C=25.59'  
B=N 72°46'15" W  
A=25.79'

WARMINGTON  
CIRCLE S.E.

LEGEND

- R/W - RIGHT-OF-WAY
- W - WATER LINE
- S - SANITARY SEWER LINE
- ST - STORM SEWER LINE
- G - GAS LINE
- UE - UNDERGROUND ELECTRIC
- OE - OVERHEAD ELECTRIC
- UT - UNDERGROUND TELEPHONE
- OT - OVERHEAD TELEPHONE
- OE&T - OVERHEAD ELEC. & TELE.
- X - FENCE
- ⊙ - GAS LINE MARKER
- ⊙ - WATER LINE MARKER
- ⊙ - POWER POLE
- ⊙ - GENERAL POLE
- ⊙ - LIGHT POLE
- ⊙ - ANCHOR
- ⊙ - SIGN
- ⊙ - CATCH BASIN (C.B.)
- ⊙ - MAN HOLE (AS LABELED)
- ⊙ - TRAFFIC CONTROL BOX
- ⊙ - FIRE HYDRANT
- ⊙ - VALVE
- ⊙ - EDGE OF PAVEMENT
- ⊙ - SPOT ELEV. TOP & BOTTOM OF CURB
- ⊙ - SPOT ELEV. EDGE OF PAVEMENT
- ⊙ - SEDIMENT TRAP
- ⊙ - ROCK CONSTRUCTION ENTRANCE
- ⊙ - INLET PROTECTION
- ⊙ - SILT FENCE

FOR SOIL EROSION CONTROL DETAILS, SEE SHEET 3

SITE INFORMATION:

ZONED: I-1 INDUSTRIAL  
FRONT YARD SETBACK: 60'  
SIDE & REAR YARD SETBACK: NONE  
PARKING REQUIRED: 1 SPACE PER 200 S.F. OF GROSS FLOOR AREA  
19,097/200 = 96 SPACES  
PARKING PROVIDED: 95 REGULAR SPACES (9' X 18')  
4 HANDICAP SPACES  
99 TOTAL SPACES

RECORR REALTY CORP.  
O.R. VOL. 1116, PG. 894

NOTE:

CONTRACTOR IS NOT EXEMPT FROM COMPLIANCE WITH STARK COUNTY EROSION/CONTROL SEDIMENT REGULATIONS. CONTRACTOR TO INSTALL AND MAINTAIN EROSION/SEDIMENT CONTROL PRACTICES TO PREVENT SEDIMENT FROM DEPOSITING INTO LOCAL STORM SEWERS, DITCHES OR ONTO ADJACENT PROPERTIES AND STREET RIGHT-OF-WAYS. REFER TO SHEET 3 FOR SILT FENCE, INLET PROTECTION AND SEEDING DETAILS AS NEEDED.

ISSUED

SEP. 23 2002

HAMMONTREE & ASSOC., LTD.


NOTES:

- 1/2 INCH IRON BAR WITH H&A CAP SET
- UTILITY LOCATIONS SHOWN HEREON WERE COMPILED FROM PLAN INFORMATION AND/OR FIELD LOCATION OF SURFACE UTILITY STRUCTURES. EXACT LOCATIONS OF UNDERGROUND UTILITIES ARE UNKNOWN.

CONTOUR INTERVAL = 1 FOOT

BENCHMARK

NORTH FLANGE BOLT OF  
FIRE HYDRANT, 110' NORTH OF CL RR TRACKS, AND 45' EAST  
OF CL US RT 21  
ELEVATION = 982.36




UNDERGROUND UTILITIES  
2 WORKING DAYS  
BEFORE YOU DIG  
CALL TOLL FREE 800-362-2764  
OHIO UTILITIES INFORMATION SERVICE  
NON-MEMBERS  
MUST BE CALLED DIRECTLY

R=358.06'  
Δ=06°15'04"  
T=19.55'  
C=39.05'  
B=N 88°14'26" W  
A=39.07'

LANDMARK INC.  
VOL. 3830, PG. 613

SCALE: 1" = 30'




MASSILLON 12

SITE GRADING & SEDIMENT CONTROL PLAN  
TRACTOR SUPPLY COMPANY - ERIE STREET  
SITUATED IN THE CITY OF MASSILLON, COUNTY OF STARK, STATE  
OF OHIO AND BEING PART OF MASSILLON CITY OUT LOT #595


HAMMONTREE & ASSOCIATES, LTD.  
ENGINEERS, PLANNERS, SURVEYORS  
CANTON PITTSBURGH AKRON  
5233 STONEHAM ROAD, NORTH CANTON, OHIO 44720  
PHONE: CANTON (330) 499-8617 AKRON (330) 499-3644  
TOLL FREE: 1-800-HAMMONTREE-engineers.com












1. INLET PROTECTION SHALL BE CONSTRUCTED EITHER BEFORE UPSLOPE LAND DISTURBANCE BEGINS OR BEFORE THE STORM DRAIN BECOMES OPERATIONAL.
2. THE EARTH AROUND THE INLET SHALL BE EXCAVATED COMPLETELY TO A DEPTH OF AT LEAST 18 IN.
3. THE WOODEN FRAME SHALL BE CONSTRUCTED OF 2 IN. BY 4 IN. CONSTRUCTION GRADE LUMBER. THE 2 IN. BY 4 IN. POSTS SHALL BE DRIVEN 18 IN. INTO THE GROUND AT FOUR CORNERS OF THE INLET AND THE TOP PORTION OF 2 IN. BY 4 IN. FRAME ASSEMBLED USING THE OVERLAP JOINT SHOWN. THE TOP OF THE FRAME SHALL BE AT LEAST 6 IN. BELOW ADJACENT ROADS IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC.
4. WIRE MESH SHALL BE OF SUFFICIENT STRENGTH TO SUPPORT FABRIC WITH WATER FULLY IMPOUNDED AGAINST IT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY TO THE FRAME.
5. GEOTEXTILE SHALL HAVE AN EQUIVALENT OPENING SIZE OF 20 - 40 SIEVE AND BE RESISTANT TO SUNLIGHT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY. IT SHALL EXTEND FROM THE TOP OF THE FRAME TO 18 IN. BELOW THE INLET NOTCH ELEVATION. THE GEOTEXTILE SHALL OVERLAP ACROSS ON SIDE OF THE INLET SO THE ENDS OF THE CLOTH ARE NOT FASTENED TO THE SAME POST.
6. BACKFILL SHALL BE PLACED AROUND THE INLET IN COMPACTED 6 IN. LAYERS UNTIL THE EARTH IS EVEN WITH NOTCH ELEVATION ON ENDS AND TOP ELEVATION ON SIDES.
7. A COMPACTED EARTH DIKE OR A CHECK DAM SHALL BE CONSTRUCTED IN THE DITCH LINE BELOW THE INLET IF THE INLET IS NOT IN A DEPRESSION AND IF RUNOFF BYPASSING THE INLET WILL NOT FLOW TO A SETTLING POND. THE TOP OF EARTH DIKES SHALL BE AT LEAST 6 IN. HIGHER THAN THE TOP OF THE FRAME.


### INLET PROTECTION IN SWALES, DITCH LINES OR YARD INLETS

N.T.S.


IP



### PLAN VIEW



### OUTLET PROFILE



### OUTLET PROFILE

### DEWATERING PIPE SECTION

### SEDIMENT TRAPS

ST

PERMANENT SEEDING			
SEED MIX	SEEDING RATE		NOTES:
	LB./AC.	LB./1,000 FT. <sup>2</sup>	
GENERAL USE			
CREEPING RED FESCUE	20-40	1/2-1	
DOMESTIC RYEGRASS	10-20	1/4-1/2	
KENTUCKY BLUEGRASS	10-20	1/4-1/2	
TALL FESCUE	40	1	
DWARF FESCUE	40	1	
STEEP BANKS OR CUT SLOPES			
TALL FESCUE	40	1	
CROWN VETCH	10	1/4	DO NOT SEED LATER THAN AUGUST.
TALL FESCUE	20	1/2	
FLAT PEA	20	1/2	DO NOT SEED LATER THAN AUGUST.
TALL FESCUE	20	1/2	
ROAD DITCHES AND SWALES			
TALL FESCUE	40	1	
DWARF FESCUE	90	2 1/4	
KENTUCKY BLUEGRASS	5		
LAWNS			
KENTUCKY BLUEGRASS	60	1 1/2	
PERENNIAL RYEGRASS	60	1 1/2	
KENTUCKY BLUEGRASS	60	1 1/2	FOR SHADED AREAS.
CREEPING RED FESCUE	60	1 1/2	
NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.			

### PERMANENT SEEDING


S

TEMPORARY SEEDING SPECIES SELECTION			
SEEDING DATES	SPECIES	LB./1,000 FT. <sup>2</sup>	PER ACRE
MARCH 1 TO AUGUST 15	OATS	3	4 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	PERENNIAL RYEGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
AUGUST 16 TO NOVEMBER 1	RYE	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	WHEAT	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
NOVEMBER 1 TO SPRING SEEDING	PERENNIAL RYEGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.			

1. STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SUCH AS DIVERSIONS AND SEDIMENT TRAPS SHALL BE INSTALLED AND STABILIZED WITH TEMPORARY SEEDING PRIOR TO GRADING THE REST OF THE CONSTRUCTION SITE.
2. TEMPORARY SEED SHALL BE APPLIED BETWEEN CONSTRUCTION OPERATIONS ON SOIL THAT WILL NOT BE GRADED OR RE-WORKED FOR 45 DAYS OR MORE. THESE IDLE AREAS SHOULD BE SEED AS SOON AS POSSIBLE AFTER GRADING OR SHALL BE SEED WITHIN 7 DAYS. SEVERAL APPLICATIONS OF TEMPORARY SEEDING ARE NECESSARY ON TYPICAL CONSTRUCTION PROJECTS.
3. THE SEED BED SHOULD BE PULVERIZED AND LOOSE TO ENSURE THE SUCCESS OF ESTABLISHING VEGETATION. HOWEVER, TEMPORARY SEEDING SHALL NOT BE POSTPONED IF IDEAL SEED BED PREPARATION IS NOT POSSIBLE.
4. SOIL AMENDMENTS - APPLICATIONS OF TEMPORARY VEGETATION SHALL ESTABLISH ADEQUATE STANDS OF VEGETATION WHICH MAY REQUIRE THE USE OF SOIL AMENDMENTS. SOIL TESTS SHOULD BE TAKEN ON THE SITE TO PREDICT THE NEED FOR LIME AND FERTILIZER.
5. SEEDING METHOD - SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDROSEEDER. WHEN FEASIBLE, SEED THAT HAS BEEN BROADCAST SHALL BE COVERED BY RAKING OR DRAGGING AND THEN LIGHTLY TAMPED INTO PLACE USING A ROLLER OR OF CULTIPACKER. IF HYDROSEEDING IS USED, THE SEED AND FERTILIZER WILL BE MIXED ON-SITE AND THE SEEDING SHALL BE DONE IMMEDIATELY AND WITHOUT INTERRUPTION.

### TEMPORARY SEEDING

TS



### PLAN VIEW

### PROFILE

1. STONE SIZE - TWO-INCH STONE SHALL BE USED, OR RECYCLED CONCRETE EQUIVALENT.
2. LENGTH - THE CONSTRUCTION ENTRANCE SHALL BE AS LONG AS REQUIRED TO STABILIZE HIGH TRAFFIC AREAS BUT NOT LESS THAN 50 FT. (EXCEPT ON SINGLE RESIDENCE LOT WHERE A 30-FT. MINIMUM LENGTH APPLIES).
3. THICKNESS - THE STONE LAYER SHALL BE AT LEAST 6 IN. THICK.
4. WIDTH - THE ENTRANCE SHALL BE AT LEAST 10 FT. WIDE, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
5. BEDDING - A GEOTEXTILE SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL HAVE A GRAB TENSILE STRENGTH OF AT LEAST 200 LB. AND A MULLEN BURST STRENGTH OF AT LEAST 190 LB.
6. CULVERT - A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE FROM BEING DIRECTED OUT ONTO PAVED SURFACES.
7. WATER BAR - A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF NEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.
8. MAINTENANCE - TOP DRESSING OF ADDITIONAL STONE WALL SHALL BE APPLIED AS CONDITIONS DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING.
9. CONSTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND PREVENT OFF-SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION SITE SHALL BE RESTRICTED FROM MUDDY AREAS.


### CONSTRUCTION ENTRANCE

N.T.S.

RCE

### EROSION CONTROL NOTES

1. ALL PROPERTIES ADJACENT TO THE SITE OF SOIL-DISTURBING ACTIVITY SHALL BE PROTECTED TO THE MAXIMUM EXTENT PRACTICABLE, FROM SOIL EROSION AND SEDIMENT RUNOFF AND DRAINAGE, INCLUDING, BUT NOT LIMITED TO PRIVATE PROPERTIES, NATURAL AND ARTIFICIAL WATERWAYS, WETLANDS, STORM SEWERS AND PUBLIC LANDS.
2. CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL PRACTICES USED TO SATISFY THIS REQUIREMENT SHALL CONFORM, AS A MINIMUM, TO STATE OF OHIO STANDARDS AS SET FORTH IN THE MOST-CURRENT EDITION OF THE RAINWATER AND LAND DEVELOPMENT MANUAL, DEFINED BY THE OHIO DEPARTMENT OF NATURAL RESOURCES DIVISION OF SOIL AND WATER CONSERVATION AND NATURAL RESOURCE CONSERVATION SERVICE AND SHALL CONFORM TO THE MOST CURRENT OHIO ENVIRONMENTAL PROTECTION AGENCY, OHIO REVISED CODE CHAPTER 6111 REQUIREMENTS.
3. EROSION AND SEDIMENT CONTROL PLAN APPROVALS ISSUED IN ACCORDANCE WITH THESE RULES DO NOT RELIEVE THE OWNER OF RESPONSIBILITY FOR OBTAINING ALL OTHER NECESSARY PERMITS AND OR APPROVALS FROM FEDERAL STATE, AND/OR COUNTY AGENCIES. IF REQUIREMENTS VARY, THE MOST STRINGENT REQUIREMENTS SHALL BE FOLLOWED.
4. EROSION AND SEDIMENT CONTROL PRACTICES AT THE SITE, AND AS IDENTIFIED IN THE ESC PLAN SHALL COMPLY WITH THE FOLLOWING:
  - A. AN APPROVED EROSION AND SEDIMENT CONTROL PLAN OR APPROVAL LETTER FROM THE STARK SWCD SHALL BE LOCATED ON SITE FOR REVIEW.
  - B. LIMITS TO CLEARING AND GRADING SHALL BE SHOWN ON ESC PLANS. LIMITS TO CLEARING AND GRADING SHALL BE CLEARLY MARKED ON SITE WITH SIGNAGE, FLAGGING, AND/OR FENCING ETC.
  - C. INSTALL EROSION AND SEDIMENT PERIMETER CONTROLS AS A FIRST ACTION OF CONSTRUCTION AS SPECIFIED BY CONSTRUCTION SEQUENCE. THIS SHALL INCLUDE AND IS NOT LIMITED TO PROTECTIVE BMP'S FOR STREAM CORRIDORS AND CROSSINGS, WETLANDS, SITE ENTRANCE, SEDIMENT TRAPS & BASINS, BARRIERS, AND DIVERSION DIKES.
  - D. CONCENTRATED STORM WATER RUNOFF SHALL PASS THROUGH A SEDIMENT CONTROL DEVICE BEFORE EXITING THE SITE BOUNDARIES. CONCENTRATED RUNOFF FROM BARE SOIL AREAS SHALL BE DIVERTED INTO A SETTLING POND OR SEDIMENT CONTROL STRUCTURE, OR OTHER APPROVED SEDIMENT BARRIER BEFORE LEAVING THE SITE.
  - E. EARTHEN STRUCTURES SUCH AS DAMS, BASINS, STREAM MODIFICATIONS AND WATER DIVERSIONS SHALL BE SEEDDED AND MULCHED WITHIN SEVEN (7) DAYS OF THE COMPLETION OF INSTALLATION. DAMS SHALL CONFORM TO THE OHIO DAM LAWS (ORC 1521.06).
  - F. STABILIZATION OF CRITICAL AREAS WITHIN 50 FEET OF ANY STREAM OR WETLAND SHALL BE TEMPORARILY STABILIZED WITHIN TWO (2) DAYS OF DISTURBANCE IF AREA WILL REMAIN INACTIVE FOR FOURTEEN (14) DAYS OR LONGER. CONSTRUCTION VEHICLES SHALL AVOID STREAMS AND THE 50 FOOT BUFFER AREAS. IF AN ACTIVE DRAINAGEWAY MUST BE CROSSED BY CONSTRUCTION VEHICLES REPEATEDLY DURING CONSTRUCTION, A TEMPORARY STREAM CROSSING SHALL BE CONSTRUCTED ACCORDING TO THE SPECIFICATIONS IN THE SEDIMENT CONTROL DEVELOPMENT BOOK. CONSTRUCTION OF BRIDGES, CULVERTS OR RAINWATER & LAND DEVELOPMENT BOOK. CONSTRUCTION OF BRIDGES, CULVERTS OR PARTICULATE MATERIAL INTO OR CLOSE TO THE WATER RESOURCE IN SUCH A MANNER THAT IT MAY SLOUGH, SLIP OR ERODE.
  - G. STORM SEWER INLETS (AND SANITARY) SHALL BE PROTECTED SO THAT SEDIMENT-LADEN RUNOFF WILL NOT ENTER THE STORM SEWER SYSTEM WITHOUT FIRST BEING FILTERED AND/OR TREATED.
  - H. RE-VEGETATE SOIL. TEMPORARY SOIL STABILIZATION SHALL OCCUR WITHIN SEVEN (7) DAYS AFTER ROUGH GRADING IF THE AREA WILL REMAIN IDLE LONGER THAN THIRTY (30) DAYS. PERMANENT SOIL STABILIZATION SHALL BE INSTALLED WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. PERMANENT VEGETATION IS A GROUND COVER DENSE ENOUGH TO COVER 80% OF THE SOIL SURFACE AND MATURE ENOUGH TO SURVIVE WINTER WEATHER CONDITION.
5. CONTRACTOR'S CONSTRUCTION SEQUENCE:
  - A. INITIAL CLEARING AND GRUBBING TO GAIN ACCESS, AND INSTALLATION OF PERIMETER CONTROLS WITHIN SEVEN (7) DAYS OF CLEARING AND GRUBBING.
  - B. CLEARING AND GRUBBING FOLLOWED BY EXCAVATION OF SEDIMENT TRAPS AND BASINS; TEMPORARY SOIL STABILIZATION FOR THESE SEDIMENT SETTLING DEVICES WITHIN FOURTEEN (14) DAYS OF EXCAVATION.
  - C. MAINTENANCE INSPECTION SCHEDULE AND PARTY RESPONSIBLE FOR INSPECTION AND REPAIR OF EROSION AND SEDIMENT CONTROL DEVICES.
  - D. PRE-WINTER STABILIZATION MEETING IF PROJECT IS TO BE THROUGH THE WINTER.
  - E. FINAL GRADING AND PERMANENT SOIL STABILIZATION WITHIN 30 DAYS OF FINISHING FINAL GRADE.
  - F. REMOVAL OF TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES.
6. SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED TO PREVENT SOIL LOSS. STABILIZATION SHALL BE REQUIRED IF STOCKPILES ARE LOCATED WITHIN CRITICAL AREAS NEAR STREAMS OR WETLANDS, OR IF DETERMINED BY THE STARK SWCD THAT SEDIMENT FROM STOCKPILES WILL LEAVE THE SITE.
7. UNSTABLE SOILS PRONE TO SLIPPING OR SLOUGHING SHALL NOT BE CLEARED, GRADED, EXCAVATED, FILLED OR HAVE LOADS IMPOSED UPON THEM UNLESS THE WORK IS PLANNED BY A QUALIFIED PROFESSIONAL ENGINEER AND INSTALLED IN ACCORDANCE WITH THE ESC PLAN. CUT AND FILL SLOPES SHOULD BE DESIGNED TO MINIMIZE EROSION PROBLEMS.
8. ADEQUATE SLOPE DESIGN INCLUDES USE OF ROUGH SOIL SURFACE ALONG THE FACE OF THE SLOPE; WATER DIVERSION ALONG THE TOP OF THE SLOPE AWAY FROM THE FACE; TERRACES TO REDUCE SLOPE LENGTH; DELIVERY OF CONCENTRATED STORM WATER FLOWS TO THE BASE OF THE SLOPE VIA ADEQUATE CHANNEL OR PIPE; AND DRAINAGE FOR WATER SEEPS IN THE SLOPE THAT ENDANGER SLOPE STABILITY.
9. SOIL SHALL BE REMOVED FROM PAVED SURFACES AND/OR PUBLIC ROADS AT THE END OF EACH DAY IN SUCH A MANNER THAT DOES NOT CREATE OFF-SITE SEDIMENTATION IN ORDER TO ENSURE SAFETY AND ABATE OFF-SITE SOIL LOSS. COLLECTED SEDIMENTS SHALL BE PLACED IN A STABLE LOCATION ON SITE OR TAKEN OFF-SITE TO A STABLE LOCATION.
10. STABILIZE DISTURBED OR MODIFIED DRAINAGE WAYS. REDUCE EROSION EFFECTS OF STORM WATER BY USING AND/OR MAINTAINING GRASSSED SWALES, INFILTRATION STRUCTURES, OR WATER DIVERSIONS.
11. SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED ONCE EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF A 0.5\"/>



### DETAILS:

### NOTES:

1. SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS.
2. ALL SILT FENCE SHALL BE PLACED AS CLOSE TO THE CONTOUR AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS WHICH MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH.
3. TO PREVENT WATER PONDED BY THE SILT FENCE FROM FLOWING AROUND THE ENDS, EACH END SHALL BE CONSTRUCTED UPSLOPE SO THAT THE ENDS ARE AT A HIGHER ELEVATION.
4. WHERE POSSIBLE, SILT FENCE SHALL BE PLACED ON THE FLATTEST AREA AVAILABLE.
5. WHERE POSSIBLE, VEGETATION SHALL BE PRESERVED FOR 5 FT. (OR AS MUCH AS POSSIBLE) UPSLOPE FROM THE SILT FENCE. IF VEGETATION IS REMOVED, IT SHALL BE RE-ESTABLISHED WITHIN 7 DAYS FROM THE INSTALLATION OF THE FENCE.
6. SOIL STOCKPILES OR OTHER SOURCES OF SEDIMENT SHALL HAVE SILT FENCE PROTECTION.
7. THE SILT FENCE SHALL BE PLACED IN A TRENCH CUT A MINIMUM OF 6\"/>

### CRITERIA FOR SILT FENCE MATERIALS

1. FENCE POSTS - THE LENGTH SHALL BE A MINIMUM OF 32\"/>

FABRIC PROPERTIES	VALUES	TEST METHOD
GRAB TENSILE STRENGTH	90 LB. MINIMUM	ASTM D 1682
MULLEN BURST STRENGTH	190 P.S.I. MINIMUM	ASTM D 3786
SLURRY FLOW RATE	0.3 GAL./MIN./FT. <sup>2</sup> MAXIMUM	
EQUIVALENT OPENING SIZE	40-80	US STD. SIEVE CW-02215
ULTRAVIOLET RADIATION STABILITY	90% MINIMUM	ASTM-G-26

### SILT FENCE

N.T.S.

SF

DESIGNED BY: JDS CHECKED BY: BHB REVISION BY: BHB  
 DRAWN BY: LJP REVIEWED BY: BHB  
 F.B. PAGE: 1  
 COPYRIGHT: 2002 DATE: 8/19/02  
 N.T.S.

SEDIMENT CONTROL NOTES & DETAILS




TRACTOR SUPPLY COMPANY - ERIE STREET  
 SITUATED IN THE CITY OF MASSILLON, COUNTY OF STARK, STATE  
 OF OHIO AND BEING PART OF MASSILLON CITY OUT LOT #595

© HAMMOND & ASSOCIATES, LTD.  
 ENGINEERS, PLANNERS, SURVEYORS  
 CANTON PITTSBURGH AKRON  
 5233 STONEHAM ROAD, NORTH CANTON, OHIO 44720  
 PHONE: CANTON (330)/489-8817 AKRON (330)/633-7274  
 TOLL FREE: 1-800-384-8817 FAX: (330)/489-0149  
 www.hammond-engineers.com

3  
4


54/41







**NOTE:**  
 ANCHOR CURB WITH (2) 1'-6" 5/8" IRON REBAR


**TYPICAL PRECAST PARKING CURB STOP DETAIL**  
 NO SCALE



**CONCRETE CRADLE DETAIL**  
 NO SCALE



**HANDICAPPED PARKING LOGO DETAIL**  
 N.T.S.



**HANDICAPPED PARKING SIGN**  
 N.T.S.

SITE DETAILS  
**TRACTOR SUPPLY COMPANY - ERIE STREET**  
 SITUATED IN THE CITY OF MASSILLON, COUNTY OF STARK, STATE OF OHIO AND BEING PART OF MASSILLON CITY OUT LOT #595

© HAMMONTREE & ASSOCIATES, LTD.  
 ENGINEERS, PLANNERS, SURVEYORS  
 CANTON PITTSBURGH AKRON  
 5233 STONEHAM ROAD, NORTH CANTON, OHIO 44720  
 PHONE: CANTON (330)/499-8817 AKRON (330)/633-7274  
 TOLL FREE: 1-800-394-8817 FAX: (330)/499-0149  
 www.hammontree-engineers.com