SITE NOTES

- I. ALL WORK REQUIRED TO COMPLETE THIS IMPROVEMENT SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE DETAILED CONSTRUCTION PLANS AND SPECIFICATIONS, THE LATEST EDITION OF THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS, AND THE MOST CURRENT CITY STANDARDS AND SPECIFICATIONS, EXCEPT AS HEREIN AMENDED/MODIFIED. IN THE CASE OF A CONFLICT BETWEEN THE SPECIFICATIONS/REQUIREMENTS, THE MORE STRICT OF THE SPECIFICATIONS WILL GOVERN, AS DETERMINED BY THE ENGINEER. STATE OF OHIO, DEPARTMENT OF TRANSPORTATION STANDARD CONSTRUCTION DRAWINGS SHALL APPLY TO THIS IMPROVEMENT (EXCEPT AS SPECIFICALLY MODIFIED BY THESE CONSTRUCTION DOCUMENTS).
- 2. THE CONTRACTOR SHALL MAINTAIN A SAFE WORKING ENVIRONMENT AT THE PROJECT SITE AT ALL TIMES. THE CONTRACTOR SHALL PROPERLY SUPPORT AND/OR MAINTAIN ALL EXCAVATIONS PER APPUCABLE SAFETY REQUIREMENTS AND COMPLY WITH ALL O.S.H.A. REGULATIONS. THIS SHALL INCLUDE STRICT SAFETY REQUIREMENTS AND COMPLY WITH ALL O.S.H.A. REGULATIONS. THIS SHALL INCLUDE STRICT COMPLIANCE WITH ALL APPLICABLE REGULATIONS/REQUIREMENTS REGARDING TRENCH SAFETY. ADEQUATE BARRICADES, WARNING LIGHTS. SIGNS. FENCING, ETC. SHALL BE ERECTED AROUND THE CONSTRUCTION AREA DURING ALL NON-WORKING HOURS TO ALERT PERSONS OF THE POTENTIAL DANGER ASSOCIATED WITH THE AREA UNDER CONSTRUCTION AS WELL AS TO PREVENT ACCESS BY UNAUTHORIZED PERSONNEL TO THE CONSTRUCTION SITE/AREA TRENCHES SHALL BE BACKFILLED AT THE END OF EACH WORK DAY OR PROPERLY SECURED AS APPROVED BY THE CITY. IT SHALL BE THE CONSTRUCTION PERSONNEL PUBLIC AS WELL AS ALL CONSTRUCTION PERSONNEL PUBLIC STREETS SHALL BE KEPT CLEAN AND FREE OF DEBRIS (MUD. STONE, ETC.) AT ALL TIMES. THE CONTRACTOR SHALL ALERT ALL LOCAL EMERGENCY AGENCIES (FIRE, POLICE, AMBULANCE, ETC.) OF THE NATURE OF THE PROPOSED PROJECT PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITY, ACCESS FOR EMERGENCY VEHICLES SHALL BE MAINTAINED AT ALL TIMES.
- 3. CONTRACTOR MUST OBTAIN A PERMIT FROM THE CITY PRIOR TO ANY WORK BEING PERFORMED INSIDE THE CITY'S RIGHT-OF-WAY. THE CONTRACTOR MUST NOTIFY THE CITY ENGINEER'S OFFICE 48 HOURS PRIOR TO ANY CONSTRUCTION INSIDE THE CITY'S RIGHT-OF-WAY IN ORDER TO COORDINATE INSPECTIONS.
- 4. ALL WORK REQUIRED FOR THIS IMPROVEMENT SHALL BE INSPECTED BY THE CITY. OR THEIR DESIGNATED REPRESENTATIVE. THE CONTRACTOR SHALL GIVE A 72 HOUR MOTICE BEFORE STARTING ANY WORK ON THIS PROJECT AND SHALL KEEP THE CITY INFORMED OF HIS/HER CONSTRUCTION SCHEDULE. NO WORK SHALL BE PERFORMED UNLESS AN AUTHORIZED INSPECTOR IS PRESENT.
- 5. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO LOCATE, ISOLATE, PROTECT AND SUPPORT ANY EXISTING UTILITIES/FACILITIES WITHIN OR ADJACENT TO THE PROJECT SITE WHICH MAY BE ENCOUNTERED DURING THE COMPLETION OF THE PROPOSED IMPROVEMENTS. SUPPORT/PROTECTION OF EXISTING UTILITIES/FACILITIES SHALL BE AS DIRECTED BY THE OWNERS OF THE RESPECTIVE UTILITIES AND APPROVED BY THE ENGINEER, UTILITIES MUST BE KEPT IN SERVICE AT ALL TIMES.
- 6. THE CONTRACTOR SHALL MAINTAIN TRAFFIC ADJACENT TO THE PROJECT AS DESCRIBED BELOW AND IN ACCORDANCE WITH THE REQUIREMENTS OF THE OHIO DEPARTMENT OF TRANSPORTATION MANUAL OF CONSTRUCTION AND MATERIALS SPECIFICATIONS ITEM 614 MAINTAINING TRAFFIC THE CONTRACTOR CONSTRUCTION AND MATERIALS SPECIFICATIONS ITEM 614 MAINTAINING TRAFFIC. THE CONTRACTOR SHALL FURNISH, MAINTAIN, AND REMOVE ALL SIGNS, FLAGS, FLAGMEN, WATCHMEN, BARRICADES, SIGN SUPPORTS, CONES, BARRELS, AND INCIDENTALS IN CONFORMANCE WITH THE MOST RECENT REVISIONS OF THE CURRENT EDITION OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS. INTERFERENCE WITH VEHICULAR TRAFFIC SHALL BE KEPT TO A MINIMUM AT ALL TIMES, ALL OPEN TRENCHES AND EXCAVATIONS SHALL BE PROTECTED WITH DRUMS, BARRICADES, OR BARRIERS, ACCESS SHALL BE MAINTAINED AT ALL TIMES FOR EMERGENCY AND FIRE DEPARTMENT VEHICLES, ANY TEMPORARY ROADMAY CLOSING MUST BE APPROVED BY THE ENGINEER AND THE PUBLIC AGENCY HAVING JURISDICTION OF THE ROADMAY IN WRITTING WITH PRIOR NOTIFICATION GIVEN TO FIRE, POLICE AND OTHER EMERGENCY AGENCIES. TRAFFIC MUST BE MAINTAINED AT ALL TIMES IN A SAFE MANNER.
- 7. A PRECONSTRUCTION MEETING WITH THE DEVELOPER.CONTRACTOR.STARK COUNTY CONSERVATION DISTRICT.AND THE CITY ENGINEER IS REQUIRED FOR THIS PROJECT PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY. THE CONTRACTOR SHALL CONTACT THE CITY ENGINEER AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO THE ANTICIPATED MEETING DATE.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE TO CLOSELY EXAMINE THE PROJECT SITE AND ALL ADJACENT AREA(S) AND APPRAISE HIMSELF OF ANY ITEMS AND/OR CONDITIONSTHAT COULD AFFECT HIS/HER BID AND/OR ABILITY TO COMPLETE THE PROPOSED IMPROVEMENTS. THIS SITE INSPECTION/EVALUATION SHALL BE COMPLETED PRIOR TO SUBMITTING A PROPOSAL OR BID.

EROSION CONTROL NOTES

- I. A PRECONSTRUCTION MEETING MUST BE SCHEDULED BY THE OWNER AND CONTRACTOR WITH THE COUNTY CONSERVATION DISTRICT AND/OR LOCAL AUTHORITY PRIOR TO INITIATION OF THE CONSTRUCTION CONTRACTOR TO NOTIFY OWNER OF APPLICABLE DATE FOR MEETING BEFORE MOBILIZATION OF EQUIPMENT ONTO SITE PROPERTY.
- 2. REFER TO THE OHIO EPA APPROVED NPDES PERMIT, SOIL EROSION AND SEDIMENTATION CONTROL PLANS, AND NARRATIVE FOR ADDITIONAL INFORMATION AND CALCULATIONS. OWNER TO PROVIDE ALL INFORMATION PERTAINING TO CONTROL MEASURES.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLATION, MAINTENANCE, AND REMOVAL OF EROSION CONTROL MEASURES UNTIL SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMPS MUST BE MAINTAINED PROPERLY, EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSPECTED ONCE EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF 0.5 OR GREATER RAINFALL CONTRACTOR TO MAINTAIN A DAILY LOG OF INSPECTION REPORTS ONSITE. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING AND RENETTING MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMPS FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPS, OR MODIFICATIONS OF THOSE INSTALLED WILL BE REQUIRED.
- CONTRACTOR ASSUMES ALL LIABILITY FOR FINES, AND CORRECTIVE MEASURES IMPOSED BY REGULATORY AGENCIES THROUGHOUT
- 5. SOIL LIMITATIONS SHOWN ARE APPROXIMATE. INFORMATION SHOWN
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE TO SEED AND MULCH WITHIN SEVEN (7) DAYS ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITY HAS OCCURRED BUT WILL TEMPORARILY REMAIN IDLE FOR A PERIOD OF MORE THAN 30 DAYS, AND OTHER DISTURBED AREAS WHERE EROSION MAY BECOME A PROBLEM AS DETERMINED BY THE ENGINEER. THE CONTRACTOR SHALL REFER TO THE EROSION AND SEDIMENTATION CONTROL PLAN FOR ADDITIONAL REQUIREMENTS.
- 7. EROSION AND SEDIMENT BMP'S MUST BE CONSTRUCTED.STABILIZED. AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN THE TRIBUTARY AREAS OF THOSE BMPS.
- 8. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED. TEMPORARY EROSION AND SEDIMENT BMPS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPS MUST BE STABILIZED IMMEDIATELY.
- 9. VEHICLES AND EQUIPMENT MAY NOT ENTER OR EXIT CONSTRUCTION AREAS VIA ENTRANCES NOT SERVICED BY A ROCK CONSTRUCTION
- 10. STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET. STOCKPILE SLOPES MUST BE 2:10R FLATTER.
- II. PRIOR TO FINAL ACCEPTANCE OF THE PROJECT BY THE CITY, THE CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT ALL SWALES. DITCHES, STORM SEWERS, CATCH BASINS, STORM MANHOLES, SANITARY SEWERS, SANITARY MANHOLES, GUTTERS, AND OTHER IMPROVEMENTS ARE CLEAN AND FREE OF ANY AND ALL DEBRIS.
- 12. COORDINATE AND TRANSITION PHASE I EROSION CONTROL MEASURES WITH ALL FUTURE CONSTRUCTION PHASES TO BE UNDERTAKEN BY OWNER.
- 13. ALL CONSTRUCTION VEHICLES MUST ENTER AND EXIT USING ONLY THE CONSTRUCTION ENTRANCE.

DESIGN DATA

SCOPE OF WORK:

CONSTRUCTION OF A PRE-ENGINEERED WELDING/FABRICATING SHOP, GARAGE/WAREHOUSE AREA AND ADMINISTRATIVE OFFICES: AREA A -- FABRICATING SHOP

AREA B -- ADMINISTRATIVE OFFICE 16' X 56' 896 SF GARAGE/WAREHOUSE AREA 30' X 51' 1530 SF TOTAL BUILDING AREA =

LOCATED IN NEOCOM I INDUSTRIAL PARK, PART OF O.L. 569 IN THE CITY OF MASSILLON, OH

DESIGNED IN COMPLIANCE WITH 2002 OBC

USE GROUP S2/F2 (NON SEPARATED)

CONSTRUCTION CLASSIFICATION 2B (UNPROTECTED)

ALLOWABLE AREA PER TABLE 503 = 23,000 SF FIRE SUPPRESSION NOT REQUIRED

BUILDING SETBACKS: FRONTAGE = 1091 WEST SIDE = 70' EAST SIDE = 400' = 115'

5 EXITS AREA B 3 EXITS

AREA C = 3 EXITS OCCUPANCY PER TABLE 1003.2.2.2:

FABRICATING AREA 6000 SF + 200 GROSS **GARAGE/BUSINESS** 1530 SF + 500 GROSS OFFICE/BUSINESS TOTAL OCCUPANCY =

CORRIDOR RATINGS = 0 RATING--RATING LESS THAN 30 PERSONS IN OFFICE AREA

TOILET ROOMS = SEPARATE ADA MALE/FEMALE FACILITIES

SLAB ON GRADE FLOOR = ADA ACCESSIBLE

ACTUAL BUILDING HEIGHT = 23' ONE STORY

ALLOWABLE BUILDING HEIGHT = 3 STORIES

PRE-ENGINEERED BUILDING DESIGN LOADS PER BRAEMAR BUILDING SYSTEMS, LTD. GERALD R. CARSTENS, E-39262

ROOF SLOPE (RISE/12) 2.00/2.00 DEAD LOAD (PSF LIVE LOAD (PSF) 20.0 COLLAT, LOAD (PSF) SNOW LOAD (PSF) 20.0 WIND SPEED (MPH) 90.0 WIND CODE **OHBC 95** CLOSED/OPEN IMPORTANCE - WIND 1.0 IMPORTANCE - SEISMIC SEISMIC COEFF (Aa) 0.24 **DESIGNER = (330) 699-0047**

PRESUMPTIVE SOIL BEARING CAPACITY SAND, SILTY SAND, CLAYEY SAND

ELECTRICAL SERVICE

GENERAL SITE PLAN NOTES

SITE DATA USED IN DEVELOPMENT OF THIS SITE PLAN WAS OBTAINED FROM NEOCOM I INDUSTRIAL PARK - NO. 1 GRADING PLAN AS PREPARED BY HAMMONTREE & ASSOCIATES, LTD. (330) 499-8817 DATED 7/9/02 (PART OF O.L. 569 IN THE CITY OF MASSILLON,

3000 PSF

600 AMP

INSTALLATION

OF A MINIMUM 32 LONG.

I) SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS.
2) VEGETATION SHALL BE PRESERVED FOR 5 FT.(OR AS MUCH AS POSSIBLE) UPSLOPE
-STAPLES FROM THE SILT FENCE. IF VEGETATION IS REMOVED, IT SHALL BE REESTABLISHED
WITHIN 7 DAYS FROM THE INSTALLATION OF THE SILT FENCE.
3) SILT FENCE FABRIC SHALL BE ODOT TYPE C GEOTEXTILE FABRIC.
4) DIG A 6 x 6 TRENCH FOR THE FENCE AT LOCATIONS SHOWN ON THE PLANSTHE
TRENCH SHALL BE CUT WITH A TRENCHER, CABLE LAYING MACHINE, OR OTHER
SUITABLE DEVICE WHICH WILL ENSURE AN ADEQUATELY UNIFORM TRENCH DEPTH.
5) STAKES SPACED & 10' MAXIMUM. USE 2'X2' WOOD OR EQUIVALENT STEEL STAKES
OF A MINIMUM 32' LONG.

6) FILTER FABRIC FENCE MUST BE PLACED AT LEVEL EXISTING GRADE BOTH ENDS OF THE BARRIER MUST BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT OVERLAP FOLD AND STAPLE FABRIC ENDS AT THE

T) LAY THE BOTTOM 8 OF CONTROL FABRIC INTO THE TRENCH. BACKFILL THE TRENCH

END STAKES OF EACH SECTION BEFORE DRIVING STAKE INTO THE GROUNDTO PREVENT SEDIMENT BYPASS.


_T) LAY THE BOTTOM 8"OF CONTROL FABRIC INTO THE TRENCH. BACKFILL THE TRENCH
WITH NATIVE SOIL AND COMPACT TO PRE-EXCAVATED DENSITY.

8) SEDIMENT MUST BE REMOVED WHEN ACCUMULATIONS REACH!/2THE ABOVE GROUND
HEIGHT OF THE FENCE. SILT FENCE SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE
FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVERTOPS THE SILT FENCE, FLOWS UNDER
OR AROUND THE ENDS,OR IN ANY OTHER WAY BECOMES A CONCENTRATED FLOW,ONE OF
THE FOLLOWING SHALL BE PERFORMED, AS APPROPIATE: 1) THE LAYOUT OF THE SILT FENCE
SHALL BE CHANGED, 2) ACCUMULATED SEDIMENT SHALL BE REMOVED, 3) REPLACED WITH A
ROCK FILTER OUTLET, OR 4) OTHER PRACTICES SHALL BE INSTALLED.

- 2 PARKING LOT PAVEMENT TO PROVIDE UNIFORM DRAINAGE TO THE CATCH BASINS. CONTRACTOR TO ESTABLISH FINISH GRADES LEVEL WITH FINISH BUILDING FLOOR ELEVATION OF 1006' AND SLOPE UNIFORMLY AWAY FROM THE BUILDING WITH A POSITIVE SLOPE TO THE CATCH BASIN TOP ELEVATION OF 1005.5.
- 3 REPORT ANY DISCREPANCY OR CONFLICTS WITH GRADES AND/OR PROPOSED ELEVATIONS TO THE ARCHITECT IMMEDIATELY DURING BUILDING LAYOUT.

COPYRIGHT

THIS DRAWING AND ITS DESIGN ARE THE PROPERTY OF THE ARCHITECT. UN-**AUTHORIZED REPRODUCTION** OR USE OF THIS DOCUMENT IS PROHIBITED.



GENERAL NOTE:

THE PRE-ENGINEERED BUILDING STRUCTURE (BRAEMAR BUILDING SYSTEMS) AND BUILDING SHELL CONTRACTOR (RILEY BUILDING COMPONENTS, INC.) IS NOTED ON THESE CONSTRUCTION DRAWINGS FOR "REFERENCE ONLY". THESE ARE SEPARATE CONTRACTS FOR CONSTRUCTION BETWEEN THE OWNER AND SUPPLIER/ CONTRACTOR. THE ARCHITECT HAS NO RESPONSIBILITY FOR THE CONTENT OF THEIR DESIGN (SHOP DRAWINGS), CONSTRUCTION MEANS, ETC. AND IS TO BE HELD HARMLESS FROM ANY ERRORS/ OMISSIONS ON THEIR PART FOR LACK OF COORDINATION OF ARCHITECTURAL DOCUMENTS. ANY/ALL REFERENCES ON THESE DRAWINGS TO THESE SUPPLIERS OR ANY SUBSTITUTE SUPPLIERS IS SUBJECT TO APPROVAL BY THE OWNER PRIOR TO CONSTRUCTION. ARCHITECTURAL DIMENSIONS WERE BASED SOLELY ON INFORMA-TION PROVIDED BY RILEY BUILDING COMPONENTS, INC. THROUGH **BRAEMAR BUILDING SYSTEMS.**

NEW STEEL FABRICATING SHOP FOR **KEAMENDED TECH** dba KENDEL WELDING 1700 NAVARRE ROAD, S.E. MASSILLON, OH 44646

Prepared by:


Roger A. Westfall, A.I.A. 8954 Appleknoll Street, N.W. Massillon, OH 44646 Phone: (330) 832-8389

BUILDING SHELL PACKAGE Prepared by:

Riley Building Company Daniel C. Riley **2548 Glenshire Circle** Uniontown, OH 44685 Phone: (330) 699-0046

PRE-ENGINEERED BUILDING STRUCTURE Prepared by:

BRAEMAR, BUILDING SYSTEMS Job No. M3-685A, M3-785B, M3-685C 925 West Kenyon Avenue Englewood, CO 80110 Phone: 1-888-480-5552 Engineer of Record--Gerald R. Carstens #E-39262



Project No. 04-102

4-01-04

DRAWING INDEX

- 1 COVER, DESIGN DATA, EROSION CONTROL
- 2 SITE PLAN, NOTES, & DETAILS
- 3 SITE DETAILS
- **FOUNDATION PLAN & NOTES**
- 5 FLOOR PLAN & NOTES
- **EXTERIOR ELEVATIONS**
- **EXTERIOR ELEVATIONS & BUILDING SECTION**
- **DETAILS**
- PLUMBING PLAN
- 10 PLUMBING DETAILS
- 11 HVAC PLAN
- 12 HVAC DETAILS
- 13 ELECTRICAL PLAN
- 14 ELECTRICAL DETAILS
- 15 SPECIFICATIONS DETAILS

FABRIC FILTER FENCE - TYPICAL

JOINING FENCE SECTIONS

-WOOD ,STAKE

-FILTER FABRIC

IN FRONT

EXIST.GROUND

-COMPACTED

BACKFILL

OF BARRIER

NO SCALE

2" x 2" STAKE -



