



**LEGEND**

- R/W- RIGHT-OF-WAY
- W- WATER LINE
- S- SANITARY SEWER LINE
- ST- STORM SEWER LINE
- G- GAS LINE
- UE- UNDERGROUND ELECTRIC
- OE- OVERHEAD ELECTRIC
- UT- UNDERGROUND TELEPHONE
- OT- OVERHEAD TELEPHONE
- OET&C- OVERHEAD ELECTRIC, TELEPHONE & CABLE
- X-X- FENCE
- GAS LINE MARKER
- TELEPHONE LINE MARKER
- POWER POLE
- TELEPHONE POLE
- TELEPHONE, LIGHT POLE
- TELEPHONE, POWER POLE
- GENERAL POLE
- LIGHT POLE
- LIGHT, POWER POLE
- LIGHT, POWER, TELEPHONE POLE
- LIGHT, POWER, TELEPHONE, CABLE T.V. POLE
- ANCHOR
- SIGN
- CATCH BASIN (C.B.)
- MAN HOLE (AS LABELED)
- TRAFFIC CONTROL BOX
- FIRE HYDRANT
- VALVE (AS LABELED)
- MAIL BOX
- GUARD POST
- SOIL BORING
- MONITORING WELL
- CLEAN OUT
- DOWN SPOUT
- EDGE OF PAVEMENT
- FLOOR DRAIN
- FINISH FLOOR ELEVATION
- FLAG POLE
- ROOF DRAIN
- YARD DRAIN
- SPOT ELEV. TOP & BOTTOM OF CURB



**ZONING**

I-1 LIGHT INDUSTRIAL  
FRONT YARD SETBACK: 60'  
REAR/SIDE YARD SETBACK: 0' UNLESS ADJ. TO RES. DISTRICT THEN 50'

**PARKING**

REQUIRED: 1/200 SQ. FT. GROSS FLOOR AREA  
6348 SQ. FT./200 SQ. FT. = 32 SPACES

PROVIDED: 30 REGULAR SPACES  
6 GARAGE SPACES  
2 H.C. SPACES  
38 TOTAL PARKING SPACES

**DATA USED:**

TAX MAP - MASSILLON 21  
DEEDS - VOL. 3123, PG. 246  
O.R. VOL. 256, PG. 343

**BASIS OF BEARING:**

N 67°30' E THE NORTH LINE OF A 20 FOOT ALLEY AS RECORDED IN VOLUME 3123, PAGE 246 OF THE STARK COUNTY DEED RECORDS.




**BENCHMARK: (B.M. #1)**

INTERSECTION OF CENTERLINES OF GUY STREET AND CABLE COURT FROM STARK COUNTY TOPO MAP.  
**ELEV. = 1040.00**

**BENCHMARK: (B.M. #2)**

RAILROAD SPIKE 1'± UP EAST SIDE OF POWER POLE #82BM4A-265T NORTH SIDE OF CABLE COURT, 100'± EAST OF GUY STREET. (SHOWN ON MAP)  
**ELEV. = 1042.45**

7°30'00" W 553.30'



- 1) ITEM 452 8" PLAIN CONCRETE
- 2) ITEM 204 COMPACTED SUBGRADE

CONTRACTOR TO SUBMIT SHOP DRAWINGS OF PAVEMENT JOINT LOCATIONS.  
ALL ITEMS FROM STATE OF OHIO DEPARTMENT OF TRANSPORTATION, CONSTRUCTION & MATERIAL SPECIFICATIONS, JAN. 1, 2002.


**CONCRETE PAVEMENT SECTION DETAIL**

NTS

- NOTES**
1. EXISTING GRAVEL AND FAILED AREAS IN RIGHT-OF-WAY SHOULD BE EXCAVATED AND REPLACED WITH MASSILLON STANDARD PAVEMENT AS SPECIFIED (6" 304 SUB BASE, 4" 301 BITUMINOUS BASE, 1 1/2" 404 SURFACE COURSE).
  2. PAVING AND DRIVEWAY CONTRACTOR IS TO OBTAIN A DRIVE PERMIT FOR THIS SITE. CONTACT CITY OF MASSILLON ENGINEERING DEPARTMENT FOR LICENSE AND PERMIT REQUIREMENTS.


RECEIVED  
09-07-05  
Revised Set

DESIGN	BY	CHKD.	BY	DATE	REVISION	DATE
JDS	BHB					
LJP	RWD					




9/7/05

**STATE DIMENSION PLAN**  
MASSILLON CABLE TV, INC.  
LOCATED IN THE CITY OF MASSILLON, STARK COUNTY, OHIO ALSO BEING PART OF OUTLOT 83 AND ALL OF LOT 15901



7'30'00" W 553.30'



**PIPE CHART**

PIPE	SIZE	*TYPE	LENGTH	GRADE	ℓ IN	ℓ OUT
P <sub>1</sub>	12"	B	76'	1.0%	1037.96	1037.20
P <sub>2</sub>	12"	B	74'	1.1%	1037.20	1036.39
P <sub>3</sub>	8"	B	20'	0.5%	1031.67	1031.57

\* USE R.C.P. (706.02), CORRUGATED POLYETHYLENE SMOOTH LINED PIPE (707.33) OR APPROVED EQUAL.

**SITE INFORMATION**

**SITE DESCRIPTION** - EXISTING - OPEN FIELD  
PROPOSED - BUILDING ADDITION & PARKING AREA

TOTAL AREA OF SITE - 5.13 AC.  
AREA OF SITE TO UNDERGO EXCAVATION - 1± AC.

PRE-CONSTRUCTION RUNOFF COEFFICIENT - 0.40  
POST-CONSTRUCTION RUNOFF COEFFICIENT - 0.65



**SCHEDULE OF MAJOR CONSTRUCTION**  
COMMENCEMENT - FALL 2005  
COMPLETION - WINTER 2005

**RECEIVING STREAM AND SURFACE WATERS**  
TUSCARAWAS RIVER

**EXISTING SOILS ON SITE**  
LuB LOUDONVILLE-URBAN LAND COMPLEX, UNDULATING QUARRIES  
Qu QUARRIES

**BENCHMARK: (B.M. #1)**  
INTERSECTION OF CENTERLINES OF GUY STREET AND CABLE COURT FROM STARK COUNTY TOPO MAP.  
ELEV. = 1040.00

**BENCHMARK: (B.M. #2)**  
RAILROAD SPIKE 1± UP EAST SIDE OF POWER POLE #B2BM4A-265T NORTH SIDE OF CABLE COURT, 100± EAST OF GUY STREET.  
(SHOWN ON MAP) ELEV. = 1042.45




THE FRAME AND GRATE SHALL BE NEENAH R-4990-AX TYPE A, EAST JORDAN IRON WORKS 6951 TYPE M2 OR APPROVED EQUAL.

A PRECAST OPTION MAY BE PROVIDED AT THE OPTION OF THE CONTRACTOR. IT SHALL BE INSTALLED PER THE MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS UTILIZING A FRAME AND GRATE SUITABLE FOR HIGHWAY TRAFFIC.

**ITEM SPECIAL - TRENCH DRAIN**


N 67'30"00" E 434.26' CABLE COURT (20' ALLEY)



- LEGEND**
- R/W - RIGHT-OF-WAY
  - W - WATER LINE
  - S - SANITARY SEWER LINE
  - ST - STORM SEWER LINE
  - G - GAS LINE
  - UE - UNDERGROUND ELECTRIC
  - OE - OVERHEAD ELECTRIC
  - UT - UNDERGROUND TELEPHONE
  - OT - OVERHEAD TELEPHONE
  - DET&C - OVERHEAD ELECTRIC, TELEPHONE & CABLE
  - X - FENCE
  - ANCHOR
  - SIGN
  - CATCH BASIN (C.B.)
  - MAN HOLE (AS LABELED)
  - TRAFFIC CONTROL BOX
  - FIRE HYDRANT
  - VALVE (AS LABELED)
  - CLEAN OUT
  - DS - DOWN SPOUT
  - EOP - EDGE OF PAVEMENT
  - FD - FLOOR DRAIN
  - FF - FINISH FLOOR ELEVATION
  - FP - FLAG POLE
  - RD - ROOF DRAIN
  - YD - YARD DRAIN
  - SPOT ELEV. TOP & BOTTOM OF CURB
  - (RCE) - ROCK CONSTRUCTION ENTRANCE
  - (SF) - SILT FENCE
- FOR SOIL EROSION CONTROL NOTES & DETAILS SEE SHEET 3

**2 WORKING DAYS BEFORE YOU DIG**  
CALL TOLL FREE 800-362-2764  
OHIO UTILITIES PROTECTION SERVICE

**ISSUED**  
NOV 16 2005  
HAMMONTREE & ASSOC., LTD.




**HAMMONTREE & ASSOCIATES, LTD.**  
ENGINEERS, PLANNERS, SURVEYORS  
CANTON, OHIO  
5233 STONEHAM ROAD, NORTH CANTON, OHIO 44720  
PHONE: CANTON (330) 499-8817 AKRON (330) 453-7274  
TOLL FREE: 1-800-394-8817 FAX: (330) 499-0149  
www.hammontree-engineers.com

DESIGN: JDS CHKD. BY: BHB  
DRAWN: LJP RWD. BY: BHB  
F.B. PAGE:  
COPYRIGHT: 2005 DATE: 7/7/05  
LAWYER: LAURENCE W. LARSON, 1313 COLUMBIAN BUILDING, STARK COUNTY, OHIO ALSO BEING PART OF OUTLOT 83 AND ALL OF LOT 15901

**MASSILLON CABLE TV, INC.**  
LOCATED IN THE CITY OF MASSILLON, STARK COUNTY, OHIO ALSO BEING PART OF OUTLOT 83 AND ALL OF LOT 15901

SITE GRADING, UTILITY & SOIL EROSION CONTROL PLAN  
SCALE: HORIZ: 1"=20'  
CONTOUR INTERVAL=1'



- STONE SIZE - TWO-INCH STONE SHALL BE USED, OR RECYCLED CONCRETE EQUIVALENT.
- LENGTH - THE CONSTRUCTION ENTRANCE SHALL BE AS LONG AS REQUIRED TO STABILIZE HIGH TRAFFIC AREAS BUT NOT LESS THAN 50 FT. (EXCEPT ON SINGLE RESIDENCE LOT WHERE A 30-FT. MINIMUM LENGTH APPLIES).
- THICKNESS - THE STONE LAYER SHALL BE AT LEAST 6 IN. THICK.
- WIDTH - THE ENTRANCE SHALL BE AT LEAST 10 FT. WIDE, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- BEDDING - A GEOTEXTILE SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL HAVE A GRAB TENSILE STRENGTH OF AT LEAST 200 LB. AND A MULLEN BURST STRENGTH OF AT LEAST 190 LB.
- CULVERT - A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE FROM BEING DIRECTED OUT ONTO PAVED SURFACES.
- WATER BAR - A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF NEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.
- MAINTENANCE - TOP DRESSING OF ADDITIONAL STONE WALL SHALL BE APPLIED AS CONDITIONS DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING.
- CONSTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND PREVENT OFF-SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION SITE SHALL BE RESTRICTED FROM MUDDY AREAS.


**CONSTRUCTION ENTRANCE**  
N.T.S. (RCE)

TEMPORARY SEEDING SPECIES SELECTION			
SEEDING DATES	SPECIES	LB./1,000 FT. <sup>2</sup>	PER ACRE
MARCH 1 TO AUGUST 15	OATS	3	4 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	PERENNIAL RYEGRASS	1	40 LB.
AUGUST 16 TO NOVEMBER 1	RYE	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	WHEAT	3	2 BUSHEL
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
NOVEMBER 1 TO SPRING SEEDING	PERENNIAL RYEGRASS	1	40 LB.
	TALL FESCUE	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.
	ANNUAL RYEGRASS	1	40 LB.

NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.

- STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SUCH AS DIVERSIONS AND SEDIMENT TRAPS SHALL BE INSTALLED AND STABILIZED WITH TEMPORARY SEEDING PRIOR TO GRADING THE REST OF THE CONSTRUCTION SITE.
- TEMPORARY SEED SHALL BE APPLIED BETWEEN CONSTRUCTION OPERATIONS ON SOIL THAT WILL NOT BE GRADED OR RE-WORKED FOR 21 DAYS OR MORE. THESE IDLE AREAS SHOULD BE SEED AS SOON AS POSSIBLE AFTER GRADING OR SHALL BE SEED WITHIN 7 DAYS. SEVERAL APPLICATIONS OF TEMPORARY SEEDING ARE NECESSARY ON TYPICAL CONSTRUCTION PROJECTS.
- THE SEED BED SHOULD BE PULVERIZED AND LOOSE TO ENSURE THE SUCCESS OF ESTABLISHING VEGETATION. HOWEVER, TEMPORARY SEEDING SHALL NOT BE POSTPONED IF IDEAL SEED BED PREPARATION IS NOT POSSIBLE.
- SOIL AMENDMENTS - APPLICATIONS OF TEMPORARY VEGETATION SHALL ESTABLISH ADEQUATE STANDS OF VEGETATION WHICH MAY REQUIRE THE USE OF SOIL AMENDMENTS. SOIL TESTS SHOULD BE TAKEN ON THE SITE TO PREDICT THE NEED FOR LIME AND FERTILIZER.
- SEEDING METHOD - SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SEEDER, DRILL, CULTIPACKER SEEDER, OR HYDROSEEDER. WHEN FEASIBLE, SEED THAT HAS BEEN BROADCAST SHALL BE COVERED BY RAKING OR DRAGGING AND THEN LIGHTLY TAMPED INTO PLACE USING A ROLLER OR OF CULTIPACKER. IF HYDROSEEDING IS USED, THE SEED AND FERTILIZER WILL BE MIXED ON-SITE AND THE SEEDING SHALL BE DONE IMMEDIATELY AND WITHOUT INTERRUPTION.

**TEMPORARY SEEDING** (TS)



- DETAILS:**
- NOTES:**
- SILT FENCE SHALL BE CONSTRUCTED BEFORE UPSLOPE LAND DISTURBANCE BEGINS.
  - ALL SILT FENCE SHALL BE PLACED AS CLOSE TO THE CONTOUR AS POSSIBLE SO THAT WATER WILL NOT CONCENTRATE AT LOW POINTS IN THE FENCE AND SO THAT SMALL SWALES OR DEPRESSIONS WHICH MAY CARRY SMALL CONCENTRATED FLOWS TO THE SILT FENCE ARE DISSIPATED ALONG ITS LENGTH.
  - TO PREVENT WATER PONDED BY THE SILT FENCE FROM FLOWING AROUND THE ENDS, EACH END SHALL BE CONSTRUCTED UPSLOPE SO THAT THE ENDS ARE AT A HIGHER ELEVATION.
  - WHERE POSSIBLE, SILT FENCE SHALL BE PLACED ON THE FLATTEST AREA AVAILABLE.
  - WHERE POSSIBLE, VEGETATION SHALL BE PRESERVED FOR 5 FT. (OR AS MUCH AS POSSIBLE) UPSLOPE FROM THE SILT FENCE. IF VEGETATION IS REMOVED, IT SHALL BE RE-ESTABLISHED WITHIN 7 DAYS FROM THE INSTALLATION OF THE FENCE.
  - SOIL STOCKPILES OR OTHER SOURCES OF SEDIMENT SHALL HAVE SILT FENCE PROTECTION.
  - THE SILT FENCE SHALL BE PLACED IN A TRENCH CUT A MINIMUM OF 6" DEEP. THE TRENCH SHALL BE CUT WITH A TRENCHER, CABLE LAYING MACHINE, OR OTHER SUITABLE DEVICE WHICH WILL ENSURE AN ADEQUATELY UNIFORM TRENCH DEPTH.
  - THE SILT FENCE SHALL BE PLACED WITH THE STAKES ON THE DOWNSLOPE SIDE OF THE GEOTEXTILE AND SO THAT 8" OF CLOTH ARE BELOW THE GROUND SURFACE. EXCESS MATERIAL SHALL LAY ON THE BOTTOM OF THE 8" DEEP TRENCH. THE TRENCH SHALL BE BACKFILLED AND COMPACTED.
  - SEAMS BETWEEN SECTION OF SILT FENCE SHALL BE OVERLAPPED WITH THE END STAKES OF EACH SECTION WRAPPED TOGETHER BEFORE DRIVING INTO THE GROUND.
  - MAINTENANCE - SILT FENCE SHALL ALLOW RUNOFF TO PASS ONLY AS DIFFUSE FLOW THROUGH THE GEOTEXTILE. IF RUNOFF OVERTOPS THE SILT FENCE, FLOWS UNDER OR AROUND THE ENDS, OR IN ANY OTHER WAY BECOMES A CONCENTRATED FLOW, ONE OF THE FOLLOWING SHALL BE PERFORMED, AS APPROPRIATE:
    - THE LAYOUT OF THE SILT FENCE SHALL BE CHANGED.
    - ACCUMULATED SEDIMENT SHALL BE REMOVED.
    - OTHER PRACTICES SHALL BE INSTALLED.

FABRIC PROPERTIES	VALUES	TEST METHOD
GRAB TENSILE STRENGTH	90 LB. MINIMUM	ASTM D 1682
MULLEN BURST STRENGTH	190 P.S.I. MINIMUM	ASTM D 3786
SLURRY FLOW RATE	0.3 GAL./MIN./FT. <sup>2</sup> MAXIMUM	
EQUIVALENT OPENING SIZE	40-80	US STD. SIEVE CW-02215
ULTRAVIOLET RADIATION STABILITY	90% MINIMUM	ASTM-G-26

**SILT FENCE**  
N.T.S. (SF)

SEED MIX	PERMANENT SEEDING		NOTES:
	SEEDING RATE		
	LB./AC.	LB./1,000 FT. <sup>2</sup>	
GENERAL USE			
CREeping RED FESCUE	20-40	1/2-1	
DOMESTIC RYEGRASS	10-20	1/4-1/2	
KENTUCKY BLUEGRASS	10-20	1/4-1/2	
TALL FESCUE	40	1	
DWARF FESCUE	40	1	
STEEP BANKS OR CUT SLOPES			
TALL FESCUE	40	1	
CROWN VETCH	10	1/4	DO NOT SEED LATER THAN AUGUST.
TALL FESCUE	20	1/2	
FLAT PEA	20	1/2	DO NOT SEED LATER THAN AUGUST.
TALL FESCUE	20	1/2	
ROAD DITCHES AND SWALES			
TALL FESCUE	40	1	
DWARF FESCUE	90	2 1/4	
KENTUCKY BLUEGRASS	5		
LAWNS			
KENTUCKY BLUEGRASS	60	1 1/2	
PERENNIAL RYEGRASS	60	1 1/2	
KENTUCKY BLUEGRASS	60	1 1/2	FOR SHADED AREAS.
CREeping RED FESCUE	60	1 1/2	

NOTE: OTHER APPROVED SEED SPECIES MAY BE SUBSTITUTED.

**PERMANENT SEEDING** (S)

**EROSION CONTROL NOTES**

- ALL PROPERTIES ADJACENT TO THE SITE OF SOIL-DISTURBING ACTIVITY SHALL BE PROTECTED TO THE MAXIMUM EXTENT PRACTICABLE, FROM SOIL EROSION AND SEDIMENT RUNOFF AND DRAINAGE, INCLUDING, BUT NOT LIMITED TO PRIVATE PROPERTIES, NATURAL AND ARTIFICIAL WATERWAYS, WETLANDS, STORM SEWERS AND PUBLIC LANDS.
- CONSTRUCTION SITE EROSION AND SEDIMENT CONTROL PRACTICES USED TO SATISFY THIS REQUIREMENT SHALL CONFORM, AS A MINIMUM, TO STATE OF OHIO STANDARDS AS SET FORTH IN THE MOST-CURRENT EDITION OF THE RAINWATER AND LAND DEVELOPMENT MANUAL, DEFINED BY THE OHIO DEPARTMENT OF NATURAL RESOURCES DIVISION OF SOIL AND WATER CONSERVATION AND NATURAL RESOURCE CONSERVATION SERVICE AND SHALL CONFORM TO THE MOST CURRENT OHIO ENVIRONMENTAL PROTECTION AGENCY, OHIO REVISED CODE CHAPTER 6111 REQUIREMENTS.
- EROSION AND SEDIMENT CONTROL PLAN APPROVALS ISSUED IN ACCORDANCE WITH THESE RULES DO NOT RELIEVE THE OWNER OF RESPONSIBILITY FOR OBTAINING ALL OTHER NECESSARY PERMITS AND OR APPROVALS FROM FEDERAL STATE, AND/OR COUNTY AGENCIES. IF REQUIREMENTS VARY, THE MOST STRINGENT REQUIREMENTS SHALL BE FOLLOWED.
- EROSION AND SEDIMENT CONTROL PRACTICES AT THE SITE, AND AS IDENTIFIED IN THE ESC PLAN SHALL COMPLY WITH THE FOLLOWING:
  - AN APPROVED EROSION AND SEDIMENT CONTROL PLAN OR APPROVAL LETTER FROM THE STARK SWCD SHALL BE LOCATED ON SITE FOR REVIEW.
  - LIMITS TO CLEARING AND GRADING SHALL BE SHOWN ON ESC PLANS. LIMITS TO CLEARING AND GRADING SHALL BE CLEARLY MARKED ON SITE WITH SIGNAGE, FLAGGING, AND/OR FENCING ETC.
  - INSTALL EROSION AND SEDIMENT PERIMETER CONTROLS AS A FIRST ACTION OF CONSTRUCTION AS SPECIFIED BY CONSTRUCTION SEQUENCE. THIS SHALL INCLUDE AND IS NOT LIMITED TO PROTECTIVE BMP'S FOR STREAM CORRIDORS AND CROSSINGS, WETLANDS, SITE ENTRANCE, SEDIMENT TRAPS & BASINS, BARRIERS, AND DIVERSION DIKES.
  - CONCENTRATED STORM WATER RUNOFF SHALL PASS THROUGH A SEDIMENT CONTROL DEVICE BEFORE EXITING THE SITE BOUNDARIES. CONCENTRATED RUNOFF FROM BARE SOIL AREAS SHALL BE DIVERTED INTO A SETTLING POND OR SEDIMENT CONTROL STRUCTURE, OR OTHER APPROVED SEDIMENT BARRIER BEFORE LEAVING THE SITE.
  - EARTHEN STRUCTURES SUCH AS DAMS, BASINS, STREAM MODIFICATIONS AND WATER DIVERSIONS SHALL BE SEED AND MULCHED WITHIN SEVEN (7) DAYS OF THE COMPLETION OF INSTALLATION. DAMS SHALL CONFORM TO THE OHIO DAM LAWS (ORC 1521.06).
  - STABILIZATION OF CRITICAL AREAS WITHIN 50 FEET OF ANY STREAM OR WETLAND SHALL BE TEMPORARILY STABILIZED WITHIN TWO (2) DAYS OF DISTURBANCE IF AREA WILL REMAIN INACTIVE FOR SEVEN (7) DAYS OR LONGER. CONSTRUCTION VEHICLES SHALL AVOID STREAM AND THE 50 FOOT BUFFER AREAS. IF AN ACTIVE DRAINAGEWAY MUST BE CROSSED BY CONSTRUCTION VEHICLES REPEATEDLY DURING CONSTRUCTION, A TEMPORARY STREAM CROSSING SHALL BE CONSTRUCTED ACCORDING TO THE SPECIFICATIONS IN PARTICULATE MATERIAL INTO OR CLOSE TO THE WATER RESOURCE IN SUCH A MANNER THAT IT MAY SLOUGH, SLIP OR ERODE.
  - STORM SEWER INLETS (AND SANITARY) SHALL BE PROTECTED SO THAT SEDIMENT-LOADED RUNOFF WILL NOT ENTER THE STORM SEWER SYSTEM WITHOUT FIRST BEING FILTERED AND/OR TREATED.
  - RE-VEGETATE SOIL. TEMPORARY SOIL STABILIZATION SHALL OCCUR WITHIN SEVEN (7) DAYS AFTER ROUGH GRADING IF THE AREA WILL REMAIN IDLE LONGER THAN TWENTY-ONE (21) DAYS. PERMANENT SOIL STABILIZATION SHALL BE INSTALLED WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. PERMANENT VEGETATION IS A GROUND COVER DENSE ENOUGH TO COVER 80% OF THE SOIL SURFACE AND MATURE ENOUGH TO SURVIVE WINTER WEATHER CONDITION.
  - SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED TO PREVENT SOIL LOSS. STABILIZATION SHALL BE REQUIRED IF STOCKPILES ARE LOCATED WITHIN CRITICAL AREAS NEAR STREAMS OR WETLANDS, OR IF DETERMINED BY THE STARK SWCD THAT SEDIMENT FROM STOCKPILES WILL LEAVE THE SITE.
  - UNSTABLE SOILS PRONE TO SLIPPING OR SLOUGHING SHALL NOT BE CLEARED, GRADED, EXCAVATED, FILLED OR HAVE LOADS IMPOSED UPON THEM UNLESS THE WORK IS PLANNED BY A QUALIFIED PROFESSIONAL ENGINEER AND INSTALLED IN ACCORDANCE WITH THE ESC PLAN. CUT AND FILL SLOPES SHOULD BE DESIGNED TO MINIMIZE EROSION PROBLEMS. ADEQUATE SLOPE DESIGN INCLUDES USE OF ROUGH SOIL SURFACE ALONG THE FACE OF THE SLOPE; WATER DIVERSIONS ALONG THE TOP OF THE SLOPE AWAY FROM THE FACE; TERRACES TO REDUCE SLOPE LENGTH; DELIVERED CONCENTRATED STORM WATER FLOWS TO THE BASE OF THE SLOPE VIA ADEQUATE CHANNEL OR PIPE; AND DRAINAGE FOR WATER SEEPS IN THE SLOPE THAT ENDANGER SLOPE STABILITY.
  - SOIL SHALL BE REMOVED FROM PAVED SURFACES AND/OR PUBLIC ROADS AT THE END OF EACH DAY IN SUCH A MANNER THAT DOES NOT CREATE OFF-SITE SEDIMENTATION IN ORDER TO ENSURE SAFETY AND ABATE OFF-SITE SOIL LOSS. COLLECTED SEDIMENTS SHALL BE PLACED IN A STABLE LOCATION ON SITE OR TAKEN OFF-SITE TO A STABLE LOCATION.
  - STABILIZE DISTURBED OR MODIFIED DRAINAGE WAYS. REDUCE EROSION EFFECTS OF STORM WATER BY USING AND/OR MAINTAINING GRASSED SWALES, INFILTRATION STRUCTURES, OR WATER DIVERSIONS.
  - SEDIMENT AND EROSION CONTROLS SHALL BE INSPECTED ONCE EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF A 0.5" OR GREATER RAINFALL EVENT. A WRITTEN LOG OF THESE INSPECTIONS AND IMPROVEMENTS TO CONTROLS SHALL BE KEPT ON SITE. THE INSPECTIONS SHALL INCLUDE THE DATE OF INSPECTION, NAME OF INSPECTOR, WEATHER CONDITIONS, ACTIONS TAKEN TO CORRECT ANY PROBLEMS AND THE DATE CORRECTIVE ACTIONS WERE TAKEN.
  - TRENCHES FOR UNDERGROUND UTILITY LINES AND PIPES SHALL BE TEMPORARILY STABILIZED WITHIN SEVEN (7) DAYS IF THEY ARE TO REMAIN INACTIVE FOR THIRTY (30) DAYS. TRENCH Dewatering DEVICES SHALL DISCHARGE IN A MANNER THAT FILTERS SOIL-LOADED WATER BEFORE DISCHARGING IT TO A RECEIVING DRAINAGE DITCH OR POND. IF SEEDING, MULCHING, OR OTHER EROSION AND SEDIMENT CONTROL MEASURES WERE PREVIOUSLY INSTALLED, THESE PROTECTIVE MEASURES SHALL BE REINSTALLED.
  - DISTURBED AREAS WHICH WILL REMAIN UNWORKED FOR A PERIOD OF 21 DAYS OR MORE SHALL BE STABILIZED WITH SEEDING AND MULCHING OR OTHER APPROPRIATE MEANS WITHIN 7 DAYS.
  - DISTURBED AREAS WHICH WILL REMAIN UNWORKED FOR A PERIOD OF 21 DAYS OR MORE SHALL BE STABILIZED WITH SEEDING AND MULCHING OR OTHER APPROPRIATE MEANS WITHIN 7 DAYS.
  - NO SOLID OR LIQUID WASTE SHALL BE DISCHARGED INTO STORM WATER RUNOFF.
  - OFF-SITE VEHICLE TRACKING SEDIMENT SHALL BE MINIMIZED. CONSTRUCTION VEHICLES ARE LIMITED TO THE CONSTRUCTION ACCESS ROAD(S) NOTED ON THE PLAN.
  - ALL EROSION AND SEDIMENT CONTROL PRACTICES MUST MEET THE STANDARDS AND SPECIFICATIONS OF THE OHIO RAINWATER AND LAND DEVELOPMENT HANDBOOK (1996).
  - OTHER EROSION AND SEDIMENT CONTROL ITEMS MAY BE NECESSARY DUE TO ENVIRONMENTAL CONDITIONS.
  - WINTERIZATION - ANY DISTURBED AREA THAT IS NOT GOING TO BE WORKED FOR 21 DAYS OR MORE MUST BE SEED AND MULCHED BY NOVEMBER 1 OR MUST HAVE A DORMANT SEEDING OR MULCH COVER APPLIED BETWEEN NOVEMBER 1 AND MARCH 1.
  - CONCRETE CEMENT IS TO BE TAKEN BACK TO PLANT FOR WASHOUT AND RECYCLING.
- CONTRACTOR'S CONSTRUCTION SEQUENCE:
  - CONTRACTOR TO SETUP A PRE-CONSTRUCTION MEETING WITH STARK SWCD TO REVIEW THE PLAN AND CONSTRUCTION SEQUENCING BEFORE EARTHWORK IS PERMITTED. CALL STARK SWCD AT (330) 830-7700.
  - INITIAL CLEARING AND GRUBBING TO GAIN ACCESS, AND INSTALLATION OF SILT FENCE AS SHOWN ON PLANS WITHIN SEVEN (7) DAYS OF CLEARING AND GRUBBING.
  - FINAL CLEARING AND GRUBBING FOLLOWED BY EARTH MOVING TO BRING SITE TO SUBGRADE ELEVATIONS.
  - CONTRACTOR TO PROVIDE REGULAR MAINTENANCE INSPECTION AND REPAIR OF EROSION AND SEDIMENT CONTROL DEVICES.
  - PRE-WINTER STABILIZATION MEETING IF PROJECT IS TO BE THROUGH THE WINTER.
  - FINAL GRADING AND PERMANENT SOIL STABILIZATION WITHIN 30 DAYS OF FINISHING FINAL GRADE.
  - REMOVAL OF TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES.

- PERMANENT SEEDING SHALL NOT BE CONSIDERED ESTABLISHED FOR AT LEAST 1 FULL YR. FROM THE TIME OF PLANTING. SEEDING AREAS SHALL BE INSPECTED FOR FAILURE AND VEGETATION RE-ESTABLISHED AS NEEDED. DEPENDING ON SITE CONDITIONS, IT MAY BE NECESSARY TO IRRIGATE, FERTILIZE, OVER SEED, OR RE-ESTABLISH PLANTINGS IN ORDER TO PROVIDE PERMANENT VEGETATION FOR ADEQUATE EROSION CONTROL.
- MAINTENANCE FERTILIZATION RATES SHALL BE ESTABLISHED BY SOIL TEST RECOMMENDATIONS OR BY USING THE RATES SHOWN IN THE FOLLOWING

MAINTENANCE FOR PERMANENT SEEDINGS FERTILIZATION AND MOWINGABLE.					
MIXTURE	FORMULA	LB./AC.	LB./1,000 FT. <sup>2</sup>	TIME	MOWING
CREeping RED FESCUE RYEGRASS	10-10-10	500	12	FALL YEARLY OR AS NEEDED.	NOT CLOSER THAN 3"
TALL FESCUE	10-10-10	500	12		NOT CLOSER THAN 4"
DWARF FESCUE	10-10-10	500	12	SPRING, YEARLY FOLLOWING ESTABLISHMENT AND EVERY 4-7 YR. THEREAFTER	NOT CLOSER THAN 2"
CROWN VETCH FESCUE	0-20-20	400	10		DO NOT MOW
FLAT PEA FESCUE	0-20-20	400	10		DO NOT MOW

NOTE: FOLLOWING SOIL TEST RECOMMENDATIONS IS PREFERRED TO FERTILIZER RATES SHOWN ABOVE.

**MAINTENANCE OF PERMANENT SEEDING** (S)

**SOIL EROSION CONTROL NOTES & DETAILS**

**MASSILLON CABLE TV, INC.**

LOCATED IN THE CITY OF MASSILLON, STARK COUNTY, OHIO ALSO BEING PART OF OUTLOT 85 AND ALL OF LOT 15901

DESIGN BY: JDS CHKD. BY: BHB  
 DRAWN BY: LJP RWD. BY: BHB  
 F.B. \_\_\_\_\_  
 COPYRIGHT: 2005 DATE: 7/7/05  
 REV. BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 REV. BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 REV. BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 REV. BY: \_\_\_\_\_ DATE: \_\_\_\_\_

SCALES:  
 HORIZ: 1"=20'  
 CONTOUR INTERVAL=1'

3  
3

HAMMONTREE & ASSOCIATES, LTD.  
 ENGINEERS, PLANNERS, SURVEYORS  
 CANTON PITTSBURGH AKRON  
 5623 STONEHAM ROAD, NORTH CANTON, OHIO 44720  
 PHONE: CANTON (330) 499-8817 AKRON (330) 633-7274  
 TOLL FREE: 1-800-394-8817 FAX: (330) 499-0149  
 www.hammontree-engineers.com