2021 RJ MATTHEWS PLANT ADDITION

INDEX OF SHEETS:

1	TITLE SHEET
2	ABBREVIATIONS AND LEGEND
3	EXISTING CONDITIONS AND DEMOLITION PLAN
4	SITE PLAN
5	grading and drainage plan
6	TYPICAL DETAILS AND NOTES
7	STORMWATER PREVENTION PLAN - COVER SHEET
8	STORMWATER PREVENTION PLAN – SITE PLAN
9	stormwater prevention plan – details

SITE INFORMATION:

ADDRESS:	2780 RICHVILLE DRIVE Massillon, ohio 44646
PROPERTY	/.
	PARCEL #10006004 -5.82± AC PARCEL #701287 - 1.96± AC

ZONE: I1 – LIGHT INDUSTRIAL

SETBACKS (BUILDING) REQUIRED MINIMUM

FRONT:	60 FT
REAR:	N/A
SIDE:	N/A

TOTAL EXISTING PARKING: TOTAL EMPLOYEES: TOTAL REQUIRED PARKING SPACES: TOTAL PROPOSED PARKING: 95 SPACES75 EMPLOYEES81 SPACES89 SPACES

TOTAL PERVIOUS AREA: ± 2.56 TOTAL BUILDING AREA: ± 1.64 TOTAL IMPERVIOUS AREA: ± 2.43

2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-362-2764 OHIO UTILITIES PROTECTION SERVICE





CITY OF MASSILLON STARK COUNTY, OHIO

	D COUNTY/CITY REVIEW 9/28/2021 D COUNTY/CITY REVIEW 9/28/2021 D Image: Color of the state of the stateof the state
APPROVALS BY:	A BARTNERS 31100 Solon Road, Suite G Solon, Ohio 44139 PH: 1(800)763-1363
ONLY APPROVED SIGNED PLANS BY THE CITY ENGINEER ARE TO BE USED FOR CONSTRUCTION PARTNERS ENVIRONMENTAL CONSULTING, INC.	
DATE	COVER SHEET 2021 RJ MATTHEWS PLANT ADDITION LOCATED IN THE CITY OF MASSILLON STARK COUNTY, OHIO FOR: IVAN WEAVER CONSTRUCTION, INC.
P.O. BOX 258 FREDRICKSBURG, OHIO 44627 CONTACT: MARK YODER PH: 330-695-3461 MARKY@WEAVERCONSTRUCTION.COM	DRAWN BY: CHECKED BY: DATE 08-12-2021 SHEET 1 OF 9

	<u>EXISTING</u>	¢
	2–2A CATCH BASIN	ф
	No. 3 CATCH BASIN	<u>۔</u> ب
(\bigcirc)	ROUND CATCH BASIN	MB
(CB)	ROUND INLET	[PB]
(<u>-</u>)	FLOOR DRAIN	(OT)
ري، م	CLEAN OUT	
CO	DOWNSPOUT	
•	YARD DRAIN	PM:
	TRENCH DRAIN	
(S·T)	STORM MANHOLE	-
(SA)	SANITARY MANHOLE	*
	COMDINATION MANITOLE	11:10
Ē	TELEPHONE LIGHT POLE	\neg
Þ	TELEPHONE LIGHT POWER POLE	0
ΗT	TELEPHONE LINE MARKER	
Ð	TELEPHONE MANHOLE	
$\overline{\phi}$	TELEPHONE POLE	P
$\overline{\phi}$	TELEPHONE POWER POLE	1
T·V	TELEPHONE VAULT	لمبر بطر
ITEL BIH	TELEPHONE BOOTH	-∕~►
	PAY TELEPHONE	
۶G	GAS LINE MARKER	С Ф
۵G	GAS LINE VENT	Ψ 売
Q	GAS METER	(U) v
(<u>G</u>)	GAS MANHOLE	Î
ی (ق)	GAS VALVE	*
°GTW	GAS TEST WIRE	*
	GAS WELL	R
(∰)	WATER GATE VALVE	\wedge
ЧW	WATER LINE MARKER	
\mathfrak{W}	WATER METER	Л
(\widehat{W})	WATER MANHOLE	A.
ي. ج	FIRE HYDRANT ASSEMBLY	
T WS	WATER SERVICE STOP	A
	WATER WELL	
×~	FIRE DEPARTMENT CONNECTION	(
(Ī)	SPRINKLER HEAD	\wedge
-ICEI	CEI MARKER	
HCPP	CPP MARKER	A NI V
E	ELECTRIC BOX	UNGI
Ð	ELECTRIC METER	STOP
(<u>E</u>)	ELECTRIC MANHOLE	
+E Γ⊂ν7	ELECTRIC MARKER	361199
正·V」 网	PULL BOX-JUNCTION BOX	$\sqrt{7}$
AC	AIR CONDITION UNIT	R).R
 [[s]	TRAFFIC SIGNAL BOX	
	STFAM MANHOLF	0
	SEPTIC TANK	G
	MONITORING WELL	
P	MONTONINO MELL	•
φ	POWER POLE	

•	DETAIL NUMBER SHEET DETAIL TAKEN FROM
	SHEET DETAIL IS FOUND ON
	SECTION NUMBER
	SHEET SECTION IS FOUND ON

<u>SYMBOLS</u>

<u>PROPOSED</u>

	2–2A CATCH BASIN
	No. 3 CATCH BASIN
\oplus	ROUND CATCH BASIN
D	FLOOR DRAIN
	TRENCH DRAIN
$igodoldsymbol{igo$	STORM MANHOLE
\bullet	STORM MANHOLE ADJUST
SA	SANITARY MANHOLE
(C) (C)	SANITARY MANHOLE ADJUST TO GRADE COMBINATION MANHOLE
Ī	TELEPHONE MANHOLE
E	ELECTRIC BOX
E	ELECTRIC MANHOLE
Ε·V	ELECTRIC VAULT
	PULL BOX-JUNCTION BOX
Τ·V	TELEPHONE VAULT
é	LIGHT POLE
Þ	POWER POLE
Ŧ	TELEPHONE POLE
Ē	TELEPHONE LIGHT POLE
Þ	TELEPHONE LIGHT POWER POLE
P	TELEPHONE POWER POLE
Ġ	GAS VALVE
Ŵ	WATER GATE VALVE
(W)	WATER METER
W	WATER MANHOLE
Ý	FIRE HYDRANT ASSEMBLY
Ś	WATER SERVICE STOP
WELL	WATER WELL
	SPRINKLER HEAD
SEP	SEPTIC TANK
PB	PAPER BOX
(PM)	MAIL BOX
ريم کي	TREE
*	EVERGREEN TREE
£~}	SHRUB
-~	SIGN
•	PK NAIL SET
Μ	MONUMENT BOX

5
$\mathbf{4}$
1
≜
ONLY
STOP
SCHOOL
K K K

LANE ARROW LEFT
LANE ARROW LEFT THRU
LANE ARROW LEFT THRU RIGHT
LANE ARROW RIGHT THRU
LANE ARROW RIGHT
LANE ARROW THRU
"ONLY" PAVEMENT MARKING
"STOP" PAVEMENT MARKING
"SCHOOL" PAVEMENT MARKING
RR CROSSING PAVEMENT MARKING
ACCESSIBLE PARKING SYMBOL

BOTT

CL CLEAR CM CO COL COMB CONC CONST CONT CONTN CONTR

COORD CPP

CTR

СҮ

DATUR

DC DCDC

EXPAN

EXT

ABUT AB	ABUTMENT ANCHOR BOLT	FD FDC
ACCESS A.C.	ACRE (S) ACCESSIBLE AIR CONDITIONER (ING)	FDN FIN
AD ADD'L ADJ	AREA DRAIN ADDITIONAL ADJUST / ADJACENT	FL FM FO
AFF AFN Aggr	ABOVE FÍNISHED FLOOR AUDITORS FILE NUMBER AGGREGATE	F.O. FP FPHB
ALUM ALT	ALUMINUM ALTERNATE	FT FTG FTR
APPROX	AUDITOR'S PARCEL NUMBER APPROXIMATE	G
ARCH ASPH AVE	ARCHITECTURAL ASPHALT AVENUE	GALV GC
AW ©	ACID WASTE AT	GEN GND GR
B-? B/C Bl	BORING BACK OF CURB BASE LINE	HB HDCP HDPE
BETWN BFF	BETWEEN BELOW FINISHED FLOOR	HDWL HORIZ
BOP BIT	BEGINNING OF PROJECT BITUMINOUS	HP HPS HR
BLVD BM	BOILDING BOULEVARD BENCHMARK	HT HTWR
BOL BOTT BR	BOLLARD BOTTOM BRICK	HTWS
BRG BSMT	BEARING BASEMENT	HYD
CAB CATV CALC	CABINET CABLE TELEVISION CALCULATED	HWR HWS HWY
CB CEM	CATCH BASIN CEMENT	 .
CF CH CH.B	CHORD LENGTH CHORD BEARING	IB ID IN
CHW CIP CJ	CHILLED WATER CAST-IN-PLACE CONTROL JOINT	INT INV IPF
CL CLEAR CM	CENTER LINE CLEARANCE CONSTRUCTION MANAGER	IPS
CMP CO COL	CORRUGATED METAL PIPE CLEANOUT COLUMN	L/A
COMB CONC CONST	COMBINED SEWER CONCRETE CONSTRUCTION	L/S LBS LF
CONT CONTN CONTR	CONTINUOUS CONTRACTION	LG LT
COORD CPP	COORDINATE CORRUGATED	LP LPS
CR CTE	CONDENSATE RETURN CONNECT TO EXISTING	MATL
CTW CTR CY	COOLING TOWER WATER CENTER CUBIC YARD (S)	MAX MB MBA
D DATUR	DEED DEPICTED ACCORDING TO	MECH MEAS
DC DCDC	UTILITY RECORD DOUBLE CHECK DOUBLE CHECK DETECTOR	MFR MIN MISC
DEMO DET	CHECK DEMOLISH / DEMOLITION DETAIL	MH MOD MON. BOX
DF DIA DIAG	DRINKING FOUNTAIN DIAMETER DIAGONAI	MSL MW
DIM DIP DOM	DIMENSION DUCTILE IRON PIPE	N/A N NVD
DN DR	DOWN DRIVE	NE
DWG	DRAWING	NO NOM
E EA EF	EACH EACH FACE	NW
EL EJ ELEC	elevation Expansion joint Electric	OC OD
EOP EQ ESMT	END OF PROJECT EQUAL EASEMENT	ODOT OH
EX EW FXPAN	EXISTING EACH WAY EXPANSION	OL OPNG OPP
EXT	EXTERIOR	OR OUPS

FOUND FIRE DEPARTMENT CONNECTION FOUNDATION FINISHED FLOOR FORCE MAIN FIBER OPTIC FUEL OIL FIRE PROTECTION FREEZE-PROOF HOSE BIB FEET / FOOT FOOTING	PC PCF PERF PG PI PIV PL POB POC PP
FOOTER GUTTER / GAS GALLON GALVANIZED GENERAL CONTRACTOR GENERAL GROUND GRADE HOSE BIB HANDICAPPED HIGH DENSITY POLYETHYLENE HEADWALL HORIZONTAL HIGH POINT HIGH PRESSURE STEAM HOUR	PPN PPOB PRV PSF PSI PROP PT PVC PVMT PWR QTY QUAL R
HEIGHT HIGH TEMPERATURE HOT WATER RETURN HIGH TEMPERATURE HOT WATER SUPPLY HEATING, VENTILATING & AIR CONDITIONING HYDRANT HOT WATER RETURN HOT WATER RETURN HOT WATER SUPPLY HIGHWAY INTERSTATE ROUTE IRON INLET BASIN INSIDE DIAMTER INCH	(R) RCP RD REBAR REC REF REINF RELOC REQ'D RET REV R/W RND RPP RRF
INTERSECTION INVERT IRON PIN FOUND IRON PIN SET JOINT LIMITED ACCESS LANDSCAPE POUNDS LINEAR FOOT / FEET LONG LEFT LOCATION	RRS RT R/W S (S) SAN SCHED SE SEC SHT SIM SOG SPA
LIGHT POLE / LOW POINT LOW PRESSURE STEAM LOW STRENGTH MORTAR MATERIAL MAXIMUM MAIL BOX MICHAEL BENZA AND ASSOCIATES, INC MECHANICAL MEASURED MANUFACTURER MINIMUM / MINUTE MISCELLANEOUS MANHOLE MODIFIED MONUMENT BOX MEAN SEA LEVEL MONITORING WELL	SPEC SQ SR SQ FT SQ IN SQ YD ST STA STD STL STM STRUCT SW ST SURF SYM T&B T/C
NOT APPLICABLE NORTH NATIONAL VERTICAL DATUM NORTHEAST NOT IN CONTRACT NUMBER NOMINAL NOT TO SCALE NORTHWEST	T/G T/W TBD TE TEMP TEL THK TYP UG UNO
ON CENTER OUTSIDE DIAMETER OHIO DEPARTMENT OF TRANSPORTATION OVERHEAD ORIGINAL LOT OPENING OPPOSITE OFFICIAL RECORD OHIO UTILTY PROTECTION SERVICES	VAR VC VCP VERT VIF VOL VPC VPI VPT

STANDARD ABBREVIATIONS

SCHED SE SEC SHT SIM SOG SPA SPEC SQ SR SQ FT SQ IN SQ YD ST STA STD STL STM STRUCT SW ST SURF SYM T&B T/C T/G T/W TBD ΤE TEMP TEL THK ΤΥΡ UG UNO VAR VC VCP VERT VIF VOL VPC VPI VPT W W/ W/O WD WΤ WWF XFMR YD

<u>LINETYPES</u> POINT OF CURVATURE POUNDS PER CUBIC FOOT EX. ELEC. ______ PERFORATED EX. FENCE - X X X IRON PIPE FOUND ц**г**р PAGE POINT OF INTERSECTION EX. GAS — · — · — · — · — POST INDICATOR VALVE EX. SAN. — · — · — · — PROPERTY LINE EX. STM. — · · · — · · · — PLUMBING POINT OF BEGINNING POINT OF EX. TELE. ______ COMMENCEMENT EX. WATER ______ · · · ____ POWER POLE EX. GUARDRAIL — • • • PERMANENT PARCEL NUMBER\ PRINCIPAL PLACE OF PROP. ELEC. ______ BEGINNING PRESSURE REGULATING PROP. FIBER OPTIC -----VALVE PROP. GAS — . — . — . — . — POUNDS PER SQ FT POUNDS PER SQ IN PROP. SAN. — — · — — · — PROPOSED PROP. STM. — · · · — · · — · · — POINT OF TANGENCY PROP. STEAM -----POLYVINYL CHLORIDE PAVEMENT POWER PROP. WATER ------PROP. GUARDRAIL -QUANTITY quality / qualify RADIUS / RANGE RETURN 0000000 REINFORCED CONC PIPE ROAD REINFORCING BAR RECORDED S REFER / REFERENCE REINFORCE / REINFORCED R RELOCATE /RELOCATED REQUIRED RETURN REVISION / REVISED RIGHT-OF-WAY ROUND C REDUCED PRESSURE \longrightarrow PRINCIPLE RAILROAD SPIKE FOUND Road, 44139 763—13 RAILROAD SPIKE SET K RIGHT RIGHT-OF-WAY noic C(OC SOUTH Sol Sol 80 SUPPLY SANITARY 311 Sol PH: SCHEDULE SOUTHEAST SECTION / SECOND SHEET SIMILAR SLAB ON GRADE SPACE SPECIFICATION SQUARE STATE ROUTE SQUARE FEET / FOOT SQUARE INCH /INCHES TE OF BA SQUARE YARD (S) STEAM STATION STANDARD STEEL STORM STRUCTURAL SOUTHWEST / SWALE STREET SURFACE SYMMETRICAL **ADDITION** TOP & BOTTOM TOP OF CURB TOP OF GRATE TOP OF WALL TO BE DETERMINED THICKENED EDGE TEMPORARY ANT TELEPHONE THICK / THICKNESS TYPICAL Δ UNDERGROUND UNLESS NOTED THEWS OTHERWISE N VARIES VERTICAL CURVE VITRIFIED CLAY PIPE М VERTICAL MΑ VERIFY IN FIELD Ζ VOLUME VERTICAL POINT OF RJ CURVE VERTICAL POINT OF INTERSECTION 2021 VERTICAL POINT OF TANGENCY WEST / WATER WITH WITHOUT WOOD DRAWN BY:___^{CM}___ WEIGHT CHECKED BY:____RN___ WOVEN WIRE FABRIC DATE <u>08-12-2021</u> TRANSFORMER SHEET 2 _{OF} 9 YARD DRAIN NOTES AND LEGEND PROJ.# 2156.01







GENERAL

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE CODES, ORDINANCES, AND STANDARD SPECIFICATIONS OF THE MASSILLON. IN LIEU OF ANY LOCAL SPECIFICATIONS WORK SHALL BE DONE IN CONFORMANCE WITH THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS MOST RECENT EDITION.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS FOR CONSTRUCTION.
- IT SHALL BE CONTRACTOR'S SOLE RESPONSIBILITY TO CONSTRUCT ALL ITEMS ON THESE PLANS USING 3. CONSTRUCTION MEANS AND METHODS THAT WILL PROTECT PROPERTY AND PREVENT BODILY INJURY AND/OR DEATH. THE CONTRACTOR SHALL TAKE ANY NECESSARY SAFETY PRECAUTIONS TO COMPLY WITH THE SAFETY REQUIREMENTS OF CITY, STATE, AND FEDERAL GOVERNMENTS.
- 4. ALL EXISTING FIELD CONDITIONS SHALL BE FIELD CHECKED AND VERIFIED BY CONTRACTORS PRIOR TO BIDDING AND CONSTRUCTION. SHOULD THERE BE ANY DISCREPANCY BETWEEN PLANS AND ACTUAL FIELD CONDITIONS; CONTRACTOR HAS TO SEEK WRITTEN CLARIFICATION FROM THE OWNER'S REPRESENTATIVE PRIOR TO COMMENCEMENT OF WORK.
- SHOULD THE CONTRACTOR ENCOUNTER CONFLICT BETWEEN THESE PLANS AND SPECIFICATIONS. EITHER AMONG THEMSELVES OR WITH THE REQUIREMENTS OF ANY AND ALL REVIEWING AND PERMIT-ISSUING AGENCIES, HE SHALL SEEK CLARIFICATION IN WRITING FROM THE OWNER'S REPRESENTATIVE BEFORE COMMENCEMENT OF CONSTRUCTION.
- 6. THE CONTRACTOR SHALL PERFORM ALL OF THE WORK AND FURNISH ALL OF THE LABOR & MATERIALS NECESSARY FOR THE FINAL COMPLETION OF THIS CONTRACT IN THE MANNER AND UNDER THE CONDITIONS HEREIN SPECIFIED AND PROVIDED AND IN ACCORDANCE WITH THE CONTRACT DRAWINGS.
- 7. ALL SHOP DRAWINGS WILL BE SUBMITTED TO THE OWNER'S ENGINEER FOR APPROVAL.
- 8. THE CONTRACTOR SHALL NOTIFY THE CITY OF MASSILLON POLICE & FIRE DEPARTMENTS AT LEAST 48 HOURS IN ADVANCE OF ANY STREET CLOSING OR TRAFFIC CHANGE.
- THE CONTRACTOR SHALL PERFORM WORK AS TO NOT DISTURB, DAMAGE OR DESTROY AND MAILBOX, PAPERBOX, TELEPHONE OR POWER POLES, SIGNS, LANDSCAPING ITEMS, ETC. ANY ITEM DAMAGED OR DESTROYED SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. ANY ITEM DISTURBED OR IN CONFLICT WITH THE WORK TO BE PERFORMED SHALL BE REMOVED AND RESET AT THE CONTRACTOR'S EXPENSE. PRIOR ENGINEER APPROVAL IS REQUIRED BEFORE ANY OF THE ABOVE ITEMS ARE PERFORMED.
- 10. CONSTRUCTION SHALL BE PERFORMED, AND EQUIPMENT STORED, IN A MANNER THAT PERMITS EXISTING FACILITIES TO PERFORM WITHOUT INTERRUPTION.
- 11. THE CONTRACTOR WILL CAREFULLY PRESERVE BENCH MARKS, PROPERTY CORNERS REFERENCE POINTS, AND STAKES AND IN CASE OF DISTURBANCE, HE SHALL ENGAGE A REGISTERED SURVEYOR TO REPLACE THEM AT HIS EXPENSE AND SHALL BE RESPONSIBLE FOR ANY MISTAKES THAT MAY BE CAUSED BY THEIR LOSS OR DISTURBANCE.

EXCAVATION. BACKFILL. EMBANKMENT. & COMPACTION

- 1. NO SOIL BORINGS WERE ACQUIRED FOR THIS PROJECT. THE CONTRACTOR MAY PERFORM HIS OWN SOILS INVESTIGATION AFTER OBTAINING APPROVAL FROM THE OWNER.
- EMBANKMENT CONSTRUCTION AND SUBGRADE COMPACTION SHALL BE IN GENERAL CONFORMANCE WITH ODOT SPECIFICATIONS AND MORE SPECIFICALLY AS FOLLOWS: STANDARD PROCTOR WITHIN BUILDING LIMITS (TO 5' OUTSIDE BUILDING LINE) AND UNDER
 - PAVEMENT = 100%STANDARD PROCTOR IN UTILITY TRENCHES = 95%.
- STANDARD PROCTOR IN YARD AREAS = 90%. 3. ALL EXCESS EXCAVATION MATERIALS SHALL BE DISPOSED OF ON-SITE AS APPROVED BY THE OWNER.
- 4. ALL UTILITY LINES (I.E. STORM SEWERS, STORM LATERALS, SANITARY LATERALS, WATER MAINS, WATER SERVICE CONNECTIONS, GAS MAINS, GAS SERVICE CONNECTIONS, UNDERGROUND OBT CONDUITS, CABLE TV LINES) CROSSING THE PROPOSED IMPROVEMENTS, WHETHER SHOWN OR NOT SHOWN ON THE PLANS, SHALL BE PROTÉCTED AND SUPPORTED WITH HARDWOOD PLANKS OR REMOVED AND REPLACED, RECONNECTED AND SUPPORTED ACROSS THE ENTIRE WIDTH OF THE TRENCH. NO ADDITIONAL COMPENSATION WILL BE PAID FOR THE ABOVE WORK. IF ANY OF THESE LINES ARE DAMAGED DURING CONSTRUCTION, THEY SHALL BE REPLACED.

PROTECTION AGAINST VANDALISM

1. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE SUFFICIENT SITE SECURITY MEASURES AND/OR PERSONNEL TO PROTECT HIS MATERIALS AND EQUIPMENT. CONTRACTOR SHALL ALSO PROTECT ALL NEW CONCRETE WORK FROM VANDALISM UNTIL THE CONCRETE IS SUFFICIENTLY CURED AT NO ADDITIONAL COST TO THE OWNER.

SANITARY, STORM, & WATER SERVICE CONNECTIONS

- 1. THE FOLLOWING NOTES APPLY TO SANITARY, STORM, AND WATER CONNECTIONS. LOCATIONS OF EXISTING SERVICE CONNECTIONS ARE APPROXIMATE. THE CONTRACTOR SHALL
 - FIELD LOCATE ALL EXISTING CONNECTIONS AS APPLICABLE. IF APPLICABLE, THERE SHALL BE NO ADDITIONAL COSTS TO THE OWNER FOR SAW CUTTING.
 - EXCAVATION OR BACKFILL, INCLUDING MATERIALS AND LABOR FOR PIPING, CAPS. BULKHEADS AND APPURTENANCES PLACED FOR LATERALS WHICH ARE DETERMINED TO BE INACTIVE AND THUS ARE TO BE ABANDONED.
- AS APPLICABLE, EXISTING SEWER & WATER SERVICE CONNECTIONS SHALL BE PROTECTED AND MAINTAINED IN SERVICE. ANY EXISTING WATERLINE, SANITARY SEWER, AND GAS LINE, IN OR OUTSIDE OF THE CONSTRUCTION LIMITS, DAMAGED DURING CONSTRUCTION OF THE PROPOSED PROJECT, SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

ROADWAY EXCAVATION & PAVEMENT

- 1. CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUISITION OF PERMITS (AND PAYMENT OF ANY PERMIT & INSPECTION FEES) FOR PERFORMANCE OF ANY WORK WITHIN THE PUBLIC ROADWAYS.
- ALL EXISTING PAVEMENT REMOVAL & REPLACEMENT OR NEW PAVEMENT AND ASSOCIATED ROADWAY WORK 2. SHALL BE IN ACCORDANCE WITH THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS, STANDARD CONSTRUCTION DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS, MOST RECENT EDITION, WITH THE MODIFICATIONS AS SET FORTH IN THESE SPECIFICATIONS.
- 3. PROPOSED DRIVE APRONS SHALL BE IN ACCORDANCE WITH CITY OF MASSILLON REGULATIONS.

METER BOXES. VALVES BOXES. STRUCTURES ADJUSTED TO GRADE

1. AS APPLICABLE ALL EXISTING MANHOLES, CATCH BASINS, MONUMENT BOXES, WATER METER BOXES. WATER VALVE BOXES, GAS VALVE BOXES, OR OTHER EXISTING UTILITY APPURTENANCES WITHIN THE WORK LIMITS SHALL BE ADJUSTED TO THE PROPOSED GRADE AND FLUSH WITH THE NEW SURFACE. ANY METER OR VALVE BOX ENCOUNTERED WITHIN THE WORK SITE SHALL BE EXPOSED.

STORM SEWER

- 1. THE FOLLOWING MATERIALS ARE APPROVED FOR THE STORM SEWER UNLESS OTHERWISE DESIGNATED ON THE PLAN. INSTALLATION TO BE IN ACCORDANCE WITH ODOT TYPE 'B' UNLESS OTHERWISE NOTED. REINFORCED CONCRETE PIPE PER ODOT ITEM 603
 - HIGH DENSITY POLYETHYLENE CORRUGATED PIPE WITH SMOOTH INTERIOR PER ODOT ITEM 707.33 C. PVC (SDR 35) IN ACCORDANCE WITH ASTM D-3034

EXISTING UTILITIES

- THE CONTRACTOR SHALL VISIT THE SITE PERSONALLY TO ASCERTAIN THE NATURE OF THE WORK AND THOROUGHLY FAMILIARIZE HIMSELF WITH THE SITE.
- THE LOCATIONS OF THE UNDERGROUND UTILITIES ARE PER SURVEY OR PLOTTED ACCORDING TO THE 2. INFORMATION FURNISHED BY THE UTILITIES CONCERNED. THE CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL APPLICABLE UTILITY COMPANIES.
- IN THE EVENT OF DAMAGE TO EXISTING PUBLIC AND/OR PRIVATE UTILITIES, THE AGENCY CONCERNED SHALL BE NOTIFIED IMMEDIATELY AND ALL REPAIR WORK SHALL BE EXECUTED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE RESPECTIVE AGENCY AT NO ADDITIONAL EXPENSE TO THE OWNER INCLUDING ANY INSPECTION FEES OR MAINTENANCE CREWS.
- WHERE EXISTING POWER OR TELEPHONE POLES ARE IN CLOSE PROXIMITY TO WORK, THE CONTRACTOR SHALL 4. COORDINATE HIS WORK EFFORTS WITH THOSE OF THE UTILITY COMPANIES SUCH THAT THEIR EXISTING FACILITIES CAN BE MAINTAINED AND PROTECTED DURING THE TIME WORK IS GOING ON ADJACENT TO THE POLE. THE COST FOR ANY REQUIRED PROTECTION SHALL BE BY THE CONTRACTOR.
- BEFORE ANY WORK IS STARTED THAT WILL INTERFERE WITH THE EXISTING UTILITIES, THE CONTRACTOR SHALL CALL THE "OHIO UTILITIES PROTECTION SERVICE" AT 1-800-362-2764, FORTY-EIGHT (48) HOURS IN ADVANCE OF THE WORK. NON-MEMBER UTILITIES MUST BE CONTACTED DIRECTLY. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO AVOID DAMAGE TO EXISTING UNDERGROUND AND OVERHEAD UTILITY LINES DURING THE ENTIRE PROJECT. IN THE EVENT OF DAMAGE TO EXISTING PUBLIC AND/OR PRIVATE UTILITIES, THE AGENCY CONCERNED SHALL BE NOTIFIED IMMEDIATELY AND ALL REPAIR WORK SHALL BE EXECUTED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE RESPECTIVE AGENCY AT NO ADDITIONAL EXPENSE TO THE OWNER.

EXISTING UTILITIES (CONTINUED)

THE UTILITY OWNERSHIPS ARE AS FOLLOWS:

AT&T 50 W. BOWERY ST AKRON, OHIO 44308 PH: 330-384-3651 ATT: CINDY T ZUCHEGNO

MASSILLON CABLE TV 814 CABLE CT. NW MASSILLON, OHIO 44648 PH: 330-438-4134 ATT: JEFF CAMBELL

FIRST ENERGY 2600 ERIE ST. S MASSILLON, OHIO 44646 PH: 330-830-7056 ATT: LUKE SAGE

NORTHEAST OHIO NATURAL GAS CORP. 9081 STATE ROUTE 250 STRASBURG, OHIO 44680 PH: (330) 878-5589 WWW.NEOGAS.COM

- 6. BOTH AS TO LINE AND GRADE BEFORE STARTING TO LAY THE PROPOSED CONDUIT.
- 7. IF IT IS DETERMINED THAT THE PROPOSED CONDUIT WILL INTERSECT AN EXISTING SEWER OR UNDERGROUND WITH AN EXISTING FACILITY.

RESTORATION

- SAME WORKDAY.
- TO THE OWNER.

ENVIRONMENTAL PROTECTION

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ON-SITE EROSION CONTROL IN CONFORMANCE WITH REQUIREMENTS OF THE CITY OF MASSILLON AND AS PRESENTED ON THE IMPROVEMENT PLANS.

- 2. THE CONTRACTOR SHALL TAKE PRECAUTION TO PERFORM ALL ACTIVITIES IN CONFORMANCE WITH CITY, STATE, AND WHICH ARE PROHIBITED FOLLOW:
 - A. LOCATING STOCKPILE STORAGE AREAS IN ENVIRONMENTALLY SENSITIVE AREAS.
 - WETLANDS, SURFACE WATERS OR OUTSIDE THE EASEMENT LIMITS.

LOCAL ORDINANCES OR REGULATIONS.





4TH	FLOOR		
8			
1			
IF ON	^		

AQUA OHIO INC.

DOMINION EAST OHIO 320 SPRINGSIDE DRIVE; SUITE 320 AKRON, OHIO 44333 PH: (800)362-7557

870 THIRD STREET NW MASSILLON, OHIO 44647 PH: 330-832-7600 ATT: DON SNYDER CITY OF MASSILLON ENGINEERING DEPARTMENT 151 LINCOLN WAY EAST

MASSILLON, OHIO 44646

PH: 330-830-1722

WHERE PLANS PROVIDE FOR A PROPOSED CONDUIT TO BE CONNECTED TO, OR CROSS OVER OR UNDER AN EXISTING SEWER OR UNDERGROUND UTILITY, THE CONTRACTOR SHALL LOCATE THE EXISTING PIPES OR UTILITIES

UTILITY IF CONSTRUCTED AS SHOWN ON THE PLAN, THE ENGINEER SHALL BE NOTIFIED BEFORERE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WOULD BE AFFECTED BY THE INTERFERENCE

THE CONTRACTOR SHALL CLEAN UP ALL DEBRIS AND MATERIALS RESULTING FROM HIS OPERATION AND RESTORE ALL SURFACES, STRUCTURES, DITCHES AND PROPERTY TO ITS ORIGINAL CONDITION TO THE SATISFACTION OF THE OWNER'S ENGINEER. ANY DITCHES DISTURBED DURING CONSTRUCTION SHALL BE REGRADED BY THE END OF THE

2. ALL EXISTING STORM AND SANITARY SEWER FACILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED, RPLACED OR RECONNECTED TO THE EXISTING OR PROPOSED SYSTEM AS DIRECTED BY THE ENGINEER AT NO COST

FEDERAL LAWS RELATIVE TO THE PROTECTION TO THE ENVIRONMENT. SOME SPECIFIC ITEMS (NOT INCLUSIVE)

INDISCRIMINATE, ARBITRARY OR CAPRICIOUS OPERATION OF EQUIPMENT IN ANY STREAM CORRIDORS, PUMPING OF SEDIMENT-LADEN WATER FROM TRENCHES OR OTHER EXCAVATIONS DIRECTLY INTO ANY SURFACE WATERS, STREAM CORRIDORS, WETLANDS OR STORM SEWERS; ALL SUCH WATER WILL BE PROPERLY FILTERED OR SETTLED TO REMOVE SILT PRIOR TO RELEASE. DISCHARGING POLLUTANTS SUCH AS CHEMICALS, FUELS, LUBRICANTS, BITUMINOUS MATERIALS, RAW SEWAGE AND OTHER HARMFUL WASTE INTO OR ALONGSIDE OF RIVERS, STREAMS, WETLANDS, SURFACE WATERS, IMPOUNDMENTS OR INTO NATURAL OR MAN-MADE CHANNELS LEADING THERETO. OPERATIONS ENTAILING THE USE OF VIBRATORY HAMMERS OR COMPACTORS OUTSIDE THE HOURS OF 8:00 AM AND 4:30 PM OR OUTSIDE THE HOURS ALLOWED FOR CONSTRUCTION BY



STORM/SANITARY SEWER TRENCH SCALE: NONE

- I. BRICK, CONCRETE BLOCK OR CAST-IN-PLACE WALLS HAVING NOMINAL THICKNESS OF 8 INCHES. PRECAST WALLS SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES AND BE REINFORCED SUFFICIENTLY TO PERMIT SHIPPING AND HANDLING WITHOUT DAMAGE.
- 2. CB 2-2B GRATE ELEVATION TO BE PLACED 1 TO 2 INCHES BELOW PAVEMENT GRADE. CONCRETE CAST-IN-PLACE TO BE CLASS C. ALL CONCRETE SHALL MEET THE REQUIREMENTS OF ODOT 708.13 WITH 6± 2% AIR VOID CONTENT IN THE HARDENED CONCRETE AND BE MARKED WITH CATCH BASIN NUMBER.
- 3. ALL GRATE EDGES TO BE ROUNDED 1/4" RADIUS.
- 4. OPENINGS FOR PIPE SHALL BE MADE TO ACCOMMODATE THE TYPE(S) OF PIPES USED FOR THE PROJECT. LOCATION AND ELEVATION WHEN GIVEN ON THE PLANS IS TOP CENTER OF THE GRATE. GRATING AND FRAME - THE DESIGN SHALL BE ESSENTIALLY THE SAME AND EQUALLY AS STRONG AS THE ONE SHOWN HEREON.





SCALE: NONE



BASIN/FOREBAY UNDERDRAIN

SCALE: NONE



NOTES AND DETAILS ^{ROJ.#} 2165.01

STORMWATER POLLUTION PREVENTION PLAN RJ MATTHEWS – 2021 BUILDING ADDITION CITY OF MASSILLON, STARK COUNTY, OHIO

GENERAL REQUIREMENTS:

STARK SOIL & WATER CONSERVATION DISTRICT MUST RECEIVE TWO (2) SETS OF THE STORM WATER POLLUTION PREVENTION PLAN (SWP3) AND ONE (1) FULL SET OF CONSTRUCTION PLANS. IN A VILLAGE OR MUNICIPALITY, THE VILLÀGE OR MUNICIPALITY ENGINEER MUST RECEIVE A COPY OF THE SWP3 PLAN. THE DISTRICT WILL REVIEW, RETURN, OR APPROVE THE SWP3 WITHIN 30 WORKING DAYS AFTER RECEIPT OR SUBMITTAL OF THE PLAN. THE APPROVED SWP3 WILL BE VALID FOR TWO (2) YEARS. THE DEVELOPER MUST APPLY FOR A NOTICE OF INTENT (NOI) FROM THE OHIO EPA IF APPLICABLE AND A COPY OF THE NOI AND SUBSEQUENT PERMIT LETTER SENT TO THE STARK SWCD OFFICE. AN APPROVED PLAN AND PRE-CONSTRUCTION MEETING ARE REQUIRED BEFORE ANY EARTH MOVING IS PERMITTED. IT IS THE DEVELOPER'S RESPONSIBILITY TO CONTACT THE STARK SWCD OFFICE (330-451-7645) TO SCHEDULE THE PRE-CONSTRUCTION MEETING.

SITE INFO:

TOTAL DRAINAGE AREA = 11.74 AC. TOTAL DISTURBED AREA = 3.61 AC NPDES PERMIT = IN PROGRESS LOCATION = CITY OF MASSILLONLATITUDE = N $40^{\circ}46'07''$ PRE-DEVELOPMENT C = 0.35WATERSHED = TUSCARAWAS RIVER

CONTRACTOR = IVAN WEAVER CONST.MS4 OPERATOR = CITY OF MASSILLON LONGITUDE = $W 81^{\circ}28'58''$ POST-DEVELOPMENT C = 0.37

INTRODUCTION:

THIS PLAN HAS BEEN PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE NPDES PERMIT FOR CONSTRUCTION SITES IN OHIO AND WITH THE APPLICABLE LOCAL STORMWATER POLLUTION PREVENTION PLAN REGULATIONS. THIS PLAN ADDRESSES THE THREE SIGNIFICANT WATER QUALITY & QUANTITY ASPECTS OF THE LAND DEVELOPMENT CONSTRUCTION PROCESS:

1. EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION, 2. POST-CONSTRUCTION STORMWATER MANAGEMENT, AND

THE CONTRACTOR SHALL INSTALL & MAINTAIN THE PRACTICES INDICATED IN ACCORDANCE WITH THE INCLUDED SEQUENCE OF CONSTRUCTION AND THE DETAILS AND SPECIFICATIONS CONTAINED IN RAINWATER AND LAND DEVELOPMENT ODNR. DIV. OF SOIL AND WATER CONSERVATION, AND OTHER REFERENCED MANUALS AND HANDBOOKS. THOSE PRACTICES THAT ARE INTENDED TO BE USED ARE:

1. SFF - SILT FENCE

3. NON-SEDIMENT POLLUTANT CONTROLS.

- 2. CE CONSTRUCTION ENTRANCE 3. GIP - GEOTEXTILE INLET PROTECTION
- 4. CWA CONCRETE WASH WATER CONTAINMENT AREA

PROJECT DESCRIPTION:

THE PROJECT IMPROVEMENTS CONSIST OF A BUILDING ADDITION TO THE EAST SIDE OF THE EXISTING BUILDING + PAVED STANDARD PARKING ON THE EAST SIDE OF THE ADDITION. EXISTING DRAINAGE FROM THE NORTH BYPASSES THE SITE IMPROVEMENT AREA AND DISCHARGE INTO AN EXISTING STORM SEWER ON THE

EAST SIDE OF RICHVILLE ROAD. PROPOSED STORM RUNOFF FROM THE BUILDING ADDITION AND THE DRAINAGE FROM THE PROPOSED PAVED PARKING LOT TO THE EAST OF THE EXISTING BUILDING WILL FLOW OVERLAND TO, AND THRU, A GRASSED SWALE WHERE IT WILL THEN DISCHARGE INTO THE EXISTING SWM BASIN LOCATED NEAR THE SW CORNER OF THE PROPERTY. THE OVERLAND SHEET FLOW AND FLOW THRU THE GRASSED SWALE SHALL PROVIDE THE WQ TREATMENT AND THE EXISTING SWM BASIN PROVIDES THE DETENTION FOR SAME. ALL DRAINAGE FROM HIS DEVELOPMENT WORKS ITS WAY WEST AND EVENTUALLY DISCHARGES INTO THE TUSCARAWAS RIVER.

EROSION AND SEDIMENT CONTROL MEASURES:

EROSION AND SEDIMENT CONTROL PRACTICES INDICATED ON THIS PLAN SHALL MEET THE STANDARDS AND SPECIFICATIONS CONTAINED IN THE CURRENT EDITION OF RAINWATER & LAND DEVELOPMENT MANUAL. STARK COUNTY METROPOLITAN SEWER DISTRICT SHALL BE RESPONSIBLE FOR THE INSTALLATION OF PERIMETER CONTROLS AND FOR THE MAINTENANCE OF PERIMETER CONTROLS UNTIL FINAL STABILIZATION IS ACHIEVED.

SEQUENCE OF EROSION AND SEDIMENT CONTROL PRACTICE IMPLEMENTATION:

- PRIOR TO THE BEGINNING OF DISTURBANCE, THE CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE APPLICABLE SWCD OFFICE. SEE ABOVE FOR DESIGNATION AND CONTACT NUMBER. FOR POST-CONSTRUCTION STORMWATER POLLUTION PREVENTION SPECIFICS
- SEE THE PLAN & CONTROL SHEETS LISTED IN THE SWP3 SHEET INDEX. 2. INSTALL CONSTRUCTION ENTRANCES AT EVERY POINT OF ACCESS FOR CONSTRUCTION VEHICLES ONTO PAVED PUBLIC ROADWAYS.
- PRIOR TO ANY GRADING ACTIVITIES TAKING PLACE, SILT FENCING AND OTHER SEDIMENT BARRIERS INDICATED ON THE PLAN, OR AS SHALL BE DEEMED NECESSARY UPON INSPECTION, SHALL BE INSTALLED AND FUNCTIONAL.
- 4. PRIOR TO ANY MAJOR GRADING ACTIVITY TAKING PLACE, THE APPROPRIATE SEDIMENT TRAPPING FACILITIES INDICATED ON THIS PLAN SHALL BE IMPLEMENTED BY ADDING A CHECK DAM ACROSS THE EXISTING BASIN OUTLET, AND GRADING IN THE PROPOSED FOREBAY.
- 5. ALL TOPSOIL STOCKPILES SHALL BE STABILIZED WITH IN 14 DAYS OF THE STOCKPILING ACTIVITY COMPLETION.
- 6. ALL DISTURBED AREAS SHALL BE TEMPORARILY OR PERMANENTLY SEEDED WITHIN 14 DAYS OF ACTIVITY COMPLETION IN SAID AREA, AS INDICATED ON THE PLAN, IN ACCORDANCE WITH THE SPECIFICATIONS UNDER NON-STRUCTURAL PRACTICES.
- 7. DROP INLET PROTECTION SHALL BE INSTALLED IN ALL LOCATIONS WHERE PRESENTED ON THE PLAN.
- DITCHES OR SWALES SHALL BE STABILIZED AS INDICATED ON THE PLAN BEFORE THE CHANNEL BEGINS TO RECEIVE ITS DESIGN FLOW. 9. TEMPORARY CONTROL MEASURES MAY BE REMOVED & DISPOSED OF AT THE TIME THAT THE ENTIRE CONTRIBUTING AREA HAS BEEN STABILIZED.
- TRAPPED SEDIMENTS SHALL BE REMOVED & DISPOSED OF AT A LOCATION AND IN A MANNER WHICH WILL PREVENT THEIR FURTHER EROSION. 10. FINAL SITE STABILIZATION IS ACHIEVED ONCE ALL OF THE TEMPORARY EROSION & SEDIMENT CONTROL MEASURES HAVE BEEN REMOVED & DISPOSED OF AND ALL TRAPPED SEDIMENT HAS BEEN PERMANENTLY STABILIZED (NO REMAINING EXPOSED GROUND ON THE SITE WITH ALL SURFACES BEING PROTECTED BY EITHER PAVEMENT, ROOF AREA, OR PERMANENT 70% MINIMUM VEGETATIVE COVER.

NON-STRUCTURAL PRACTICES:

WHEREVER FEASIBLE, THE NATURAL CONDITION SHOULD BE PRESERVED. THIS IS ACCOMPLISHED BY PRESERVING RIPARIAN AREAS ADJACENT TO SURFACE WATERS OF THE STATE, PRESERVING EXISTING VEGETATION AND VEGETATED BUFFER STRIPS, PHASING CONSTRUCTION TO MINIMIZE DISTURBANCE, AND DESIGNATION OF TREE PRESERVATION AREAS. NOTE: UNDISTURBED RIPARIAN AREAS AND BUFFERS SHOULD BE A MINIMUM OF 25 FEET WIDE AS MEASURED FROM THE ORDINARY HIGH WATER MARK OF THE SURFACE WATER. DESIGNATED AND/OR JURISDICTIONAL WETLANDS ARE CONSIDERED TO BE SURFACE WATERS.

C. EROSION CONTROL PRACTICES:

THE CONTRACTOR SHALL INITIATE TEMPORARY SEEDING OR PERMANENT SEEDING ON ALL DISTURBED AREAS IN ACCORDANCE WITH THE TIMING REQUIREMENTS DESIGNATED ON THIS PLAN. WHEN SEASONAL CONDITIONS PROHIBIT THE APPLICATION OF TEMPORARY OR PERMANENT SEEDING, NON-VEGETATIVE SOIL STABILIZATION PRACTICES SUCH AS MATTING & MULCHING SHALL BE USED.

D. <u>STRUCTURAL PRACTICES:</u>

- 1. TIMING THROUGHOUT ANY EARTH DISTURBING ACTIVITY, PROPOSED SEDIMENT PONDS & PERIMETER SEDIMENT BARRIERS SHALL BE IMPLEMENTED AS THE FIRST STEP OF GRADING AND WITHIN SEVEN DAYS OF THE START OF GRUBBING. THEY SHALL REMAIN UNTIL THE UPSLOPE DEVELOPMENT AREA S RESTABILIZED.
- 2. SETTLING PONDS CONCENTRATED STORM WATER RUNOFF FROM DISTURBED AREAS SHALL PASS THROUGH A SEDIMENT SETTLING POND. THE FACILITY'S SEDIMENT TRAPPING CAPACITY SHALL BE 67 CUBIC YARDS PER ACRE OF THE TOTAL CONTRIBUTING AREA.
- 3. SEDIMENT BARRIERS SHEET FLOW RUNOFF FROM DENUDED AREAS SHALL BE INTERCEPTED BY SEDIMENT BARRIERS. SEDIMENT BARRIERS, SUCH AS SILT FENCES OR DIVERSIONS DIRECTING RUNOFF TO SETTLING FACILITIES, SHALL PROTECT ADJACENT PROPERTIES AND WATER RESOURCES FROM SEDIMENT TRANSPORTED BY SHEET FLOW.
- 4. OTHER EROSION AND SEDIMENT CONTROL PRACTICES SHALL PREVENT SEDIMENT LADEN WATER FROM ENTERING STORM DRAIN SYSTEMS, UNLESS THE STORM DRAIN SYSTEM DRAINS INTO A SETTLING POND. THESE PRACTICES SHALL DIVERT RUNOFF FROM DISTURBED AREAS AND STEEP SLOPES WHERE PRACTICABLE AND STABILIZE CHANNELS & OUT FALLS FROM FROSIVE FLOWS.

POST-CONSTRUCTION STORMWATER POLLUTION PREVENTION:

STRUCTURAL & NON-STRUCTURAL POST-CONSTRUCTION POLLUTION PREVENTION PRACTICES ARE REQUIRED BY FEDERAL, STATE, (AND LOCAL) GUIDELINES AND REGULATIONS FOR ALL PROJECTS WHERE THE DISCHARGE FOLLOWING DEVELOPMENT EXCEEDS THE PRE-DEVELOPMENT DISCHARGE. THE PURPOSE OF THESE STORMWATER MANAGEMENT PRACTICES IS TO ENSURE THAT THERE IS NO SIGNIFICANT CHANGE IN THE HYDROLOGICAL REGIME OF THE RECEIVING WATER.

THE PROPOSED IMPROVEMENTS WILL BE REQUIRED POST-CONSTRUCTION POLLUTION PREVENTION MEASURES INCLUDING PERMANENT WATER QUALITY STORAGE VOLUME IN THE PROPOSED SWM BASIN. PRIOR TO THE BASIN'S CONVERSION TO PERMANENT SWM & WQ THE OUTLET CONTROL STRUCTURE WILL BE MODIFIED TO PROVIDE SEDIMENT CONTROL. AT TIME OF THE BASIN'S CONVERSION THE DEVELOPER SHALL BE RESPONSIBLE FOR REMOVAL OF SEDIMENT FROM THE BASIN, CONVERSION OF THE CONTROL STRUCTURE, AND SEEDING OF IMPACTED AREAS. THE PROPOSED SWM BASIN IS DESIGNED AS A RAIN GARDEN.

NOTE: STORMWATER MANAGEMENT IS INTEGRAL TO THE DEVELOPMENT OF THE IMPROVEMENT PLANS FOR THE SITE. STORMWATER MANAGEMENT PRACTICES SHOWN ON THIS PLAN ARE FOR REFERENCE ONLY. CONSTRUCTION MUST BE IN ACCORDANCE WITH THE DETAILS AND SPECIFICATIONS CONTAINED IN THE SITE IMPROVEMENT PLANS AND OHIO EPA.

NON-SEDIMENT POLLUTION CONTROLS:

NO SOLID (OTHER THAN SEDIMENT) OR LIQUID WASTE, INCLUDING BUILDING MATERIALS, SHALL BE DISCHARGED INTO STORM WATER RUNOFF AND/OR STORMWATER CONVEYANCE FACILITIES.

A. CONSTRUCTION ROAD/PARKING AREA STABILIZATION:

IF NOT DESIGNATED ON THE PLAN & CONTROL SHEETS OF THIS PLAN THEN THE CONTRACTOR SHALL DESIGNATE AREAS FOR CONSTRUCTION VEHICLE ACCESS AND PARKING AND ENSURE THAT SAID USES WILL BE RESTRICTED. THE CONTRACTOR SHALL DESIGNATE AREAS FOR CONSTRUCTION VEHICLE ACCESS AND PARKING AND ENSURE THAT THE DESIGNATED USES WILL BE RESTRICTED TO THOSE AREA. THE DESIGNATED ACCESS AND PARKING AREAS SHALL BE STABILIZED WITH A 6-INCH LAYER OF 2— TO 4—INCH CRUSHED ROCK OR GRAVEL BASE PRIOR TO VEHICLES BEING PERMITTED TO USE THE AREAS. IT IS RECOMMENDED THAT THE SAME AREA BE USED FOR MAINTENANCE AND FUELING OPERATIONS AND MATERIAL STORAGE, WITH THE APPROPRIATE DIKING AND OTHER RAINFALL RUNOFF CONTROLS.

B. WASTE MATERIAL:

NO WASTE MATERIALS SHALL BE EITHER BURNED OR BURIED, OR ALLOWED TO ENTER SURFACE WATERS OR STORM DRAINAGE SYSTEMS ON THE SITE. LIDDED CONTAINERS MUST BE PROVIDED FOR COLLECTION OF A WASTE MATERIAL INCLUDING CONSTRUCTION DEBRIS, TRASH, PETROLEUM PRODUCTS AND ANY HAZARDOUS MATERIAL ON SITE. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THAT MATERIAL.

C. <u>HAZARDOUS OR TOXIC MATERIAL HANDLING:</u>

CONSTRUCTION VEHICLE MAINTENANCE, FUELING AND LUBRICATING, AND FUEL AND LUBRICANT STORAGE SHALL BE RESTRICTED TO A SINGLE LOCATION ON THE SITE AT ANY ONE TIME AND THAT SITE SHALL BE ADEQUATELY DIKED TO PREVENT ANY SPILLED CHEMICALS FROM ENTERING THE DRAINAGE SYSTEM. MIXING, PUMPING, TRANSFERRING, OR OTHERWISE HANDLING CONSTRUCTION CHEMICALS SUCH AS FERTILIZER, LIME, ASPHALT, CONCRETE CURING COMPOUNDS, AND ALL OTHER POTENTIALLY HAZARDOUS MATERIALS SHALL BE PERFORMED IN A DESIGNATED AREA AWAY FROM ANY SURFACE WATER, STREAM, DITCH, OR STORM DRAIN. THE AREA SHALL BE ADEQUATELY DIKED TO PREVENT RAINFALL RUNOFF FROM TRANSPORTING THE MATERIALS ONTO ADJACENT SOILS.

D. HAZARDOUS SUBSTANCE SPILL HANDLING:

- 1. IF HAZARDOUS SUBSTANCES SUCH AS OIL, DIESEL FUEL, HYDRAULIC FLUID, ANTIFREEZE, ETC., ARE SPILLED, LEAKED, OR OTHERWISE RELEASED ONTO THE SOIL, THE ENTIRE VOLUME OF CONTAMINATED SOIL SHALL BE DUG UP AND DISPOSED OF AT A LICENSED SANITARY LANDFILL (NOT A CONSTRUCTION/ DEMOLITION DEBRIS LANDFILL). IN NO CASE MAY THE CONTAMINATED SOIL BE BURIED.
- 2. SPILLS ON ADJACENT PAVEMENT SHALL BE ABSORBED WITH SAWDUST, KITTY LITTER, OR A COMMERCIAL CHEMICAL ABSORBENT AND DISPOSED OF AT A LICENSED SANITARY LANDFILL.
- 3. HAZARDOUS OR INDUSTRIAL WASTES SUCH AS MOST SOLVENTS, GASOLINE, OIL-BASED PAINTS, AND CEMENT CURING COMPOUNDS REQUIRE SPECIAL HANDLING. FOR SUCH MATERIALS, CALL OHIO OEPA (1-800-282-9378).
- 4. SPILLS OF 25 GAL. OR MORE OF PETROLEUM PRODUCTS SHALL BE REPORTED TO OHIO EPA (1-800-282-9378), THE LOCAL FIRE DEPARTMENT, AND THE LOCAL EMERGENCY PLANNING COMMITTEE WITHIN 30 MINUTES OF THE DISCOVERY OF THE RELEASE.

PROJECT SITE DESCRIPTION

EROSION AND SEDIMENT CONTROL, POST-CONSTRUCTION STORMWATER POLLUTION PREVENTION, AND NON-SEDIMENT POLLUTION CONTROL PRACTICES AND PROCEDURES OWNER CERTIFICATION

E. SAWCUTTING AND SURFACING POLLUTION PREVENTION:

SLURRY AND CUTTINGS SHALL BE VACUUMED DURING CUTTING AND SURFACING OPERATIONS. THEY SHALL NOT REMAIN ON PERMANENT CONCRETE OR ASPHALT PAVEMENT OVERNIGHT. THEY SHALL NOT DRAIN INTO ANY NATURAL OR CONSTRUCTED DRAINAGE CONVEYANCE. COLLECTED SLURRY AND CUTTINGS SHALL BE DISPOSED OF IN A MANNER THAT DOES NOT VIOLATE GROUNDWATER OR SURFACE WATER QUALITY STANDARDS.

F. <u>CONCRETE HANDLING:</u>

- UNUSED CONCRETE REMAINING IN THE TRUCK AND PUMP SHALL BE RETURNED TO THE ORIGINATING BATCH PLANT FOR RECYCLING. IT SHALL
- NOT BE DISPOSED OF ON SITE. CONCRETE TRUCK CHUTES, PUMPS & INTERNALS SHALL BE WASHED OUT ONLY INTO PREPARED AREAS AWAITING INSTALLATION OF CONCRETE OR ASPHALT. IF NO PREPARED AREAS ARE AVAILABLE, WASHWATER AND LEFTOVER PRODUCT SHALL BE HELD IN A LINED SUMP. CONTAINED CONCRETE SHALL BE DISPOSED OF IN A MANNER THAT DOES NOT VIOLATE GROUNDWATER OR SURFACE WATER QUALITY STANDARD. SEE THE CWA DESIGNATIONS ON THE PLAN & CONTROL SHEETS OF THIS PLAN.

TRENCH AND GROUND WATER CONTROL: G.

- TRENCH DEWATERING TRENCH WATER IS USUALLY CONTAMINATED WITH SEDIMENT AND CANNOT BE ALLOWED TO MIX WITH SURFACE WATER WITHOUT APPROPRIATE TREATMENT. IF TRENCH DEWATERING IS REQUIRED, THE CONTRACTOR SHALL ENSURE THAT THE DISCHARGE PASSES THROUGH A CONSTRUCTED TEMPORARY SEDIMENT TRAP OR A FILTERING DEVICE SUCH AS AN AFC ENVIRONMENTAL, INC., "DIRT BAG".
- GROUND WATER DISCHARGE GROUND WATER IS NOT USUALLY CONTAMINATED WITH SEDIMENT AND MAY BE PUMPED AND DISCHARGED WITHOUT TREATMENT IF THE PROPER PRECAUTIONS ARE TAKEN. GROUND WATER MAY ONLY BE DISCHARGED DIRECTLY INTO SURFACE WATERS, STORM DRAINS, OR PERMANENTLY STABILIZED SURFACES. GROUND WATER THAT IS DISCHARGED ONTO UNSTABILIZED SURFACES OR THAT IS ALLOWED TO FLOW ACROSS UNSTABILIZED SURFACES MUST BE TREATED TO REMOVE SEDIMENT BEFORE BEING ALLOWED TO ENTER ANY SURFACE WATER OR STORM WATER CONVEYANCE SYSTEM.

OTHER CONSIDERATIONS:

A. <u>SURFACE WATER PROTECTION:</u>

NO CONSTRUCTION ACTIVITY OF ANY KIND SHALL BE PERFORMED IN ANY SURFACE WATERS (STREAMS, RIVERS, LAKES, WETLANDS, OR OTHER) ON THE SITE UNLESS THE CONSTRUCTION PLANS FOR THE PROJECT ARE IN COMPLIANCE WITH SECTIONS 404 AND 401 OF THE CLEAN WATER ACT AND THE APPROPRIATE PERMITS HAVE BEEN ACQUIRED FROM THE U.S. ARMY CORPS OF ENGINEERS (SECTION 404 REGULATION) AND/OR THE OHIO ENVIRONMENTAL PROTECTION AGENCY (SECTION 401 REGULATION).

B. INSPECTIONS:

INSPECTIONS ARE TO BE PERFORMED BY QUALIFIED PERSONS PROVIDED BY THE PERMITTEE AND THE INSPECTION LOGS ARE TO BECOME A PART OF THIS PLAN. INSPECTIONS SHALL BE CONDUCTED AT LEAST ONCE IN EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH OF RAIN PER 24 HOUR PERIOD. FROM THE BEGINNING OF CONSTRUCTION THROUGH THE FINAL INSPECTION PRIOR TO THE NOTICE OF TERMINATION. A WRITTEN LOG OF OF THESE INSPECTIONS MUST BE MAINTAINED UNTIL THE SITE HAS BEEN DESIGNATED AS COMPLETE AND STABILIZED BY THE SWCD. THE LOG SHOULD INDICATE THE DATES OF INSPECTIONS, INSPECTOR, WEATHER CONDITIONS, OBSERVATIONS ACTIONS TAKEN /NEEDED TO CORRECT THE PROBLEMS AND DATE THE CORRECTIVE MEASURE(S) WAS COMPLETED. ANY NEEDED REPAIRS SHALL BE MADE WITHIN 3 DAYS OF INSPECTION OBSERVANCE.

C. MAINTENANCE:

ALL TEMPORARY AND PERMANENT CONTROL PRACTICES SHALL BE REPAIRED AND MAINTAINED IN ACCORDANCE WITH THE TIME REQUIREMENTS SHOWN ON THIS SHEET TO ASSURE THE CONTINUED PERFORMANCE OF THEIR FUNCTION. IN ORDER TO ACCOMPLISH THIS, THERE SHALL BE SUFFICIENT EQUIPMENT, MATERIALS, AND PERSONNEL AVAILABLE AT ALL TIMES TO MAKE ANY REPAIRS OR REPLACEMENTS THAT ARE NECESSARY.

D. <u>SUB-LOTS WITHIN THE DEVELOPMENT:</u>

NOT APPLICABLE

E. TEMPORARY STABILIZATION:

DISTURBED AREAS MORE THAN 50 FEET FROM A STREAM AND REMAINING DORMANT FOR 14 DAYS OR MORE MUST BE SEEDED TO A TEMPORARY COVER WITHIN 7 DAYS OF LAST DISTURBANCE.

F. PERMANENT STABILIZATION:

DISTURBED AREAS REMAINING DORMANT FOR OVER A YEAR AND AT FINAL GRADE WILL HAVE A PERMANENT VEGETATIVE COVER APPLIED WITHIN 7 DAYS OF LAST DISTURBANCE.

G. STRUCTURAL EROSION CONTROL:

ALL PERIMETER CONTROLS AND SEDIMENT BASINS MUST BE INSTALLED WITHIN 7 DAYS OF THE COMMENCEMENT OF GRUBBING ACTIVATES AND PRIOR TO GRADING THE AREAS THEY WILL ADDRESS.

H. <u>TEMPORARY SEEDING:</u> (SEE TABLE ON SHEET 9)

TEMPORARY SEEDING SHALL BE APPLIED ON EXPOSED SOIL WHERE ADDITIONAL WORK IS NOT SCHEDULED FOR MORE THAN 14 DAYS. IF THE AREA IS TO REMAIN IDLE FOR MORE THEN ONE YEAR PERMANENT SEEDING MEASURES SHALL BE TAKEN.

BEFORE SEEDING IS APPLIED THE SEEDBED SOIL SHALL CONSIST OF LOOSE PULVERIZED SOIL CLEANED OF AND LARGE ROCKS AND DEBRIS THAT WOULD INTERFERE WITH THE SEEDING OPERATIONS.

THE SEED SHALL BE APPLIED UNIFORMLY WITH A CYCLONE SPREADER, FRILL, CULTI-PACKER SEEDER OR HYDROSEED. IF POSSIBLE THE SEED SHALL BE COVERED AND LIGHTLY TAMPED INTO PLACE.

IF AN AREA FAILS TO HAVE ADEQUATE COVERAGE TO PREVENT EROSION THEN RESEEDING SHOULD BE DONE AS SOON AS THE PROBLEM AREA IS IDENTIFIED.

IF SEEDING IS PLACED DURING DRY/HOT SUMMER DAYS THEN THE AREA SHALL BE WATERED AT 1 INCH PER WEEK.

I. MULCHING:

MULCH MAY BE REQUIRED THROUGHOUT CONSTRUCTION TO LIMIT EROSION IN AREAS THAT ARE BARE OF VEGETATION. IT MAY BE USED IN CONJUNCTION WITH SEEDING OR ALONE TO PROVIDE EROSION CONTROL WHEN THE SEASON DOES NOT ALLOW GRASS TO GROW.

PERMANENT SEEDING: (SEE TABLE 7.10.1 ON SHEET 9)

PERMANENT SEEDING SHALL BE APPLIED TO ANY DISTURBED AREA OR PORTION OF DISTURBED AREA THAT HAS REACHED FINAL GRADE. PERMANENT SEEDING MAY BE COMPLETED IN PHASES IF WORK IS REQUIRED IN OTHER AREAS BUT HAVE REACH COMPLETION IN SOME. IF WORK SHALL REMAIN IDLE FOR ONE YEAR OR GREATER THEN PERMANENT SEEDING SHALL APPLIED.

K. INSPECTION:

EROSION AND SEDIMENT CONTROL MUST BE INSPECTED ONCE EVERY 7 DAYS AND FOLLOWING STORM EVENTS WITH 0.5 INCH OR GREATER RAINFALL DURING A 24 HOUR PERIOD. A WRITTEN LOG OF THESE INSPECTIONS MUST BE MAINTAINED THROUGHOUT CONSTRUCTION. THE LOG SHOULD INDICATE THE DATES OF INSPECTIONS, INSPECTOR, INSPECTION WEATHER CONDITIONS, OBSERVATIONS, ACTIONS TAKEN TO CORRECT PROBLEMS, AND THE DATE THE ACTION WAS TAKEN.

- IF THE INSPECTION REVEALS THAT A CONTROL PRACTICE IS IN NEED OF REPAIR OR MAINTENANCE, WITH THE EXCEPTION OF A SEDIMENT SETTLING POND. IT SHALL BE REPAIRED OR MAINTAINED WITHIN 3 DAYS OF THE INSPECTION. SEDIMENT SETTLING PONDS SHALL BE REPAIRED OR MAINTAINED
- WITHIN 10 DAYS OF THE INSPECTION. IF THE INSPECTION REVEALS THAT A CONTROL PRACTICE FAILS TO PERFORM ITS INTENDED FUNCTION AND THAT ANOTHER, MORE APPROPRIATE CONTROL PRACTICE IS REQUIRED, THE SWP3 SHALL BE AMENDED AND THE NEW CONTROL PRACTICE SHALL BE INSTALLED WITHIN 10 DAYS OF THE
- INSPECTION. IF THE INSPECTION REVEALS THAT A CONTROL PRACTICE HAS NOT BEEN IMPLEMENTED IN ACCORDANCE WITH THE SCHEDULE CONTAINED IN PART III.G.1.H OF THIS PERMIT, THE CONTROL PRACTICE SHALL BE IMPLEMENTED WITHIN 10 DAYS FROM THE DATE OF THE INSPECTION. IF THE INSPECTION REVEALS THAT THE PLANNED CONTROL PRACTICE IS NOT NEEDED. THE RECORD SHALL CONTAIN A STATEMENT OF EXPLANATION AS TO WHY THE CONTROL PRACTICE IS NOT NEEDED.

DESIRABLE CONSTRUCTION SEQUENCE

CONTACT STARK SOIL & WATER CONSERVATION DISTRICT TO SCHEDULE A PRE-CONSTRUCTION MEETING AT (303) 451-7645 PRIOR TO ANY EARTH MOVING ACTIVITY.

- 1. INSTALL SOIL STABILIZATION AND SEDIMENT CONTROL PRACTICES CONSTRUCTION ROAD ENTRANCE(S)
- DIVERSIONS APPROPRIATE SEDIMENT BARRIERS
- 2. GRADE SITE/STOCKPILE TOPSOIL RIGHT OF WAY DIVERSIONS/WATER BARS APPLY VEGETATIVE COVER TO AREAS TO BE DORMANT FOR 14
- DAYS OR MORE 3. PRESERVE AND PROTECT EXISTING VEGETATION
- 4. INSTALL STORMWATER MANAGEMENT MEASURES
- DITCHES AND DITCH LININGS TEMPORARY VEGETATIVE STABILIZATION TEMPORARY SEEDING
- VEGETATIVE FILTERS MULCHING
- 6. INSTALL ROAD SUBGRADE AGGREGATE COVER
- NOT USED
- 8. SURFACE ROADS (PAVING)
- 9. PERMANENT VEGETATIVE STABILIZATION PERMANENT OR DORMANT SEEDING SODDING (WHERE REQUIRED)
- 10. FINAL SITE STABILIZATION
- FINAL LANDSCAPING
- REMOVE TEMPORARY SEDIMENT CONTROL MEASURES

11. FINAL SITE INSPECTION 45 DAYS AFTER FINAL SITE STABILIZATION IS COMPLETE

TYDICAL SOIL DEOTECTION CHAPT

		11	PICAL	SOIL	PRUI	ECHO		ARI				
STABILIZATION TYPE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	D
PERMANENT			A						А			
SEEDING						*	*					
DORMANT SEEDING	в		в									
TEMPORARY SEEDING			С			С	D		D			
						*	*					
SODDING			E						E			
			**									
MULCHING	F											
A = KENTUCKY BLUEGE	RASS AT	90 LB//	AC MIXE	D WITH			E =	SOD				
PEREINIAL RIEGRAS	S AI JU) LB/AC					F =	STRAW	MULCH	AT 2 T	DNS/AC	
B = KENTUCKY BLUEGE	RASS_AT	135 LB,	AC MIX	ED WITH								

PERENIAL RYEGRASS AT 45 LB/AC PLUS 2 TONS/AC STRAW MULCH

C = SPRING OATS AT 100 LB/AC

* = IRRIGATION NEEDED DURING JUNE AND JULY ** = IRRIGATION NEEDED FOR 2-3 WEEKS AFTER APPLYING SOD

HARDENA VIORAL

HEALTH CARE

CERTIFICATION:

D = WHEAT OR CEREAL RYE AT 150 LB/AC

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR THE GATHERING OF THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.







I TRAVIOLET RADIATION STABILIT

90% MINIMUM

ASTM-G-26

ormula	Lbs./ Acre	Lbs./1,000 sq.ft.	Time	Mowing
10-10	500	12	Fall, yearly or as needed	Not closer than 3"
10-10	500	12		Not closer than 4"
10-10	500	12		
0-20	400	10	Spring, yearly follow-	Do not mow
0-20	400	10	ing establishment and every 4-7 years thereafter	Do not mow

le	c	tik	an	c.	

	Lb/1000 ft2	Lb/Acre	
tue Ayegrass	3 1 1	128 (4 Bushel) 40 40	
d Ryegrass - sue tyrgrass	1 1 1 1	40 40 40	
tyograss Il Ryograss g Red Fascue y Bluegrass	1.25 3.25 0.4 0.4	55 142 17 17	
ue tyegrass	3 1 1	128 (3 bushel) 40 40	
we Iyegrass	3 1 1	112 (2 bushel) 40 40	
lug Iyegrass	3 1 1	120 (2 bushel) 40 40	
d Rye suo tyegrass	1 1 1	40 40 40	
lyograss Il Ryograss	1.25 3.25	40 40 40	

ices such talied and ding the rest	4.	Soil Amendments—Temporary vegetation seeding rates shall establish adequate stands of vegetation, which may require the use of soil amendments. Base rates for lime and fertilizer shall be used.
istruction eworked be seeded	5.	Seeding Method—Seed shall be applied uniformly with a cyclone spreader, drill, cultipacker seeder, or hydroseeder. When feasible, seed that has been broadcast shall be covered by raking or dragging and then lightly tamped
to ensure the y seeding paration is		into place using a roller or cultipacker. If hydroseeding is used, the seed and fertilizer will be mixed on-site and the seeding shall be done immediately and without interruption.



THIS "TYPICAL LOT" IS REPRESENTATIVE ONLY. EROSION AND SEDIMENT CONTROL FOR SPECIFIC LOTS MUST ACCOUNT FOR THE ACTUAL SIZE AND SHAPE OF THE LOT, THE ACTUAL GROUND SLOPES THAT EXIST AS WELL AS THE FINISHED SLOPES, THE ACTUAL LIMITS OF NECESSARILY DISTURBED AREAS, AND ACCESS TO THE PUBLIC ROADWAY FOR BOTH CONSTRUCTION VEHICLES AND STORM WATER RUNOFF.