



Flooring Legend		
	LVT-1	Luxury Vinyl Tile
	LVT-2	Luxury Vinyl Tile
	LVT-3	Luxury Vinyl Tile
	LVT-4	Luxury Vinyl Tile
	LVT-5	Luxury Vinyl Tile
	LVT-6	Luxury Vinyl Tile
	LVT-7	Luxury Vinyl Tile
	LVT-8	Luxury Vinyl Tile
	LVT-9	Luxury Vinyl Tile
	LVT-10	Luxury Vinyl Tile
	CPT-1	Carpet Tile
	CPT-2	Carpet Tile
	CPT-3	Carpet Tile
	CPT-4	Carpet Tile
	CPT-5	Carpet Tile
	CPT-6	Carpet Tile
	LIN-1	Linoleum
	LIN-2	Linoleum
	LIN-3	Linoleum
	LIN-4	Linoleum
	LIN-5	Linoleum
	LIN-6	Linoleum
	LIN-7	Linoleum
	LIN-8	Linoleum
	PFT-1	Porcelain Floor Tile
	CG	Stainless Steel Corner Guard

GENERAL FINISH NOTES	
1.	ALL LVT MUST BE PROVIDED BY SAME MANUFACTURER TO KEEP A CONSISTENT MATERIAL PATTERN
2.	SEE INTERIOR ELEVATIONS FOR ACCENT WALL LOCATOR
3.	SEE INTERIOR PLANS AND ELEVATIONS FOR WALL TILE PATTERN
4.	SEE FINISH PLAN FOR WALL TILE PATTERN REQUIREMENTS
5.	ALL EXPOSED SIDES OF WALL TILE TO BE FINISHED WITH 1" TRIM, SEE A-452
6.	ALL PRODUCTS SHOWN ON MATERIAL SCHEDULE ARE SHOWN FOR ASSESS OF DESIGN. OTHER MANUFACTURERS THAT MEET OR EXCEED REQUIREMENTS MAY BE SUBSTITUTED PENDING ARCHITECT APPROVAL
7.	SEE FINISH PLAN FOR SEATED CINETE CONTROL JOINTS
8.	UNFLEXIBLE SEAMS SHALL BE NETT IT SEAMS IN LIEU OF HEAT WELDED
9.	SHOWER CLEARANCE MUST BE 36" MINIMUM FROM FINISH FLOOR TO FINISH FACE
10.	ALL FINISH FLOORING AND ACCESSORIES SHALL MAINTAIN ACCESSIBILITY REQUIREMENTS FOR FINISH DIMENSIONS
11.	CONTRACTOR TO PROVIDE BLOCKING BEHIND STUD WALLS WHERE CASEWORK, SHELVING, TECHNOLOGY RESTROOM ACCESSORIES, ETC. MOUNT
12.	WOOD DOOR COLOR TO BE SELECTED BY ARCHITECT FROM MANUFACTURER'S FULL RANGE OF COLORS
13.	SEE DRAWING P-100 FOR DRAWING P-100
14.	HOLLOW METAL DOOR AND FRAME COLOR TO BE PT-1 UNLESS NOTED OTHERWISE ON INTERIOR ELEVATIONS
15.	CORNER GUARDS INDICATED ON FINISH PLAN AS CG
16.	ALL FLOOR CONTROL JOINTS AS INDICATED ON FINISH PLAN ARE TO BE 1/4" DEPTH OF 3/8" THICKNESS. IF JOINT IS GREATER THAN 1/2" DEPTH, FILL WITH FOAM BACKER ROD 1/8" WIDER THAN JOINT. FILL ALL JOINTS WITH SOLID POLYURETHANE CAULK
17.	CONTRACTOR TO PROVIDE WALK OFF MATS AT ALL BUILDING ENTRANCES
18.	SEE A-451 FOR FINISH SCHEDULE
19.	SEE INTERIOR ELEVATIONS FOR GYPSUM CONTROL JOINT LOCATIONS, SEE A-452 FOR DETAIL
20.	CONTINUE FINISH FLOOR UNDER OPEN CASEWORK, TYP
21.	SEE A-452 FOR DETAIL REGARDING THE FLOORING MATERIAL

