

SECTION 233115 - FLEXIBLE DUCTWORK

PART 1-GENERAL

1.1 SECTION INCLUDES

- A. Flexible insulated HVAC ductwork.
- B. Flexible ductwork joint connections.

1.2 SUBMITTALS

- A. Submit shop drawings and product data per applicable Division I Specifications.
- B. Shop drawings shall include material pressure ratings and dimensions.

1.3 QUALITY ASSURANCE

- A. SMACNA HVAC Duct Construction Standards-Metal and Flexible.
- B. UL 181
- C. NFPA 90A and 90B.
- D. ASHRAE Handbook, HVAC Systems and Equipment.
- E. UL 191.
- F. Ductwork shall be sealed and leak tested as required by ASHRAE standard 90.1.

PART 2-PRODUCTS

2.1 MANUFACTURERS – FLEXIBLE DUCT CONNECTORS

- A. Duro Dyne
- B. Ventfabrics
- C. Elgen
- D. Ductmate

2.2 COMPONENTS

- A. Flexible Duct Connectors
 - 1. Minimum 30 ounce neoprene coated fabric secured by bolted angles or band iron.
 - 2. Metal to metal contact shall not be permitted.

2.3 FLEXIBLE DUCTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Flexmaster U.S.A., Inc.
 - 2. Thermaflex.
 - 3. Hart & Cooley Commercial.
- B. Non-insulated, Flexible Duct: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire.
 - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 10 to plus 160 deg F.
- C. Insulated, Flexible Duct: UL 181, Class 1, black polymer film supported by helically wound, spring-steel wire; fibrous-glass insulation; fire resistive vapor-barrier film.
 - 1. Pressure Rating: 4-inch wg positive and 0.5-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 20 to plus 175 deg F.
 - 4. Insulation R-Value: Comply with ASHRAE/IESNA 90.1.
- D. Insulated, Flexible Duct: UL 181, Class 1, multiple layers of aluminum laminate supported by helically wound, spring-steel wire; fibrous-glass insulation; fire resistive vapor-barrier film.
 - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 20 to plus 210 deg F.
 - 4. Insulation R-value: Comply with ASHRAE/IESNA 90.1.

PART 3-EXECUTION

3.1 INSTALLATION

- A. Provide the flexible connections at ductwork connections to vibrating or rotating equipment, including fans.
- B. Install in accordance with manufacturer's instructions.
- C. Locate ducts with sufficient space around equipment to allow normal operating and maintenance activities.
- D. Provide "Flexible" connections as noted on drawings between ducts and fans with 1" slack.
- E. No pipes or other obstructions shall pass through air ducts.

- F. All ducts at ceilings shall be run in such a manner as to maintain a maximum headroom in all rooms and corridors.
- G. Ducts must be installed at such times as the construction alterations of the building will permit or as required by the Architects.
- H. Connect diffusers to low pressure ducts with 5 feet maximum length of flexible duct held in place with strap or clamp.
- I. Connect flexible ducts to metal ducts with adhesive, plus stainless- steel draw bands. Maximum length shall be 5'-0" with no more than two 90 degrees elbows as installed. Connect to ducts with fittings with integral air extractor and balancing damper.

END OF SECTION 233115

THIS PAGE IS INTENTIONALLY LEFT BLANK