ROOM FINISH SCHEDULE

NUMBER	NAME	FLOOR	BASE	WALL	CEILING	HEIGHT	Area	COMMENTS
A-001	VESTIBULE	CPT-6	VWB-1	PT-1	ACT-2	12' - 0"	242 SF	SEE ELEVATION FOR BRICK AND GLASS
A-002	STAIRS/ ENTRY WAY	LVT-1, LVT-2, LVT-3, LVT-4, LVT-5, LVT-6, LVT-7, LVT-8, LVT-9	VWB-1	PT-1, PT-3, PT-4, PT-5, PT-6, PT-10, PT-17	GYP/ PT-1, ACT-2	22' - 8"	1097 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE CLG. PLAN FOR CEILING HEIGHT AND LOCATION
A-003	CORRIDOR	LVT-1, LVT-2, LVT-3, LVT-4, LVT-5, LVT-6, LVT-7, LVT-8, LVT-9	VWB-1	PT-1, PT-3, PT-4, PT-5, PT-6, PT-10, PT-17	ACT-1	9' - 4"	1852 SF	SEE FINISH PLAN FLOR FLOOR PATTERN, SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
A-004	CORRIDOR	LVT-2	VWB-1	PT-1	ACT-1	9' - 4"	104 SF	
A-005	1ST GRADE ELA	LIN-2, LIN-7	VWB-1	PT-1, PT-4, PT-12, PT-13	EXP PT-1, ACT-2 CLOUDS, PT-4 ACCENT COLOR ON DUCT	0' - 0"	1788 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-5
A-006	1ST GRADE ELA	LIN-2, LIN-7	VWB-1	PT-1, PT-4, PT-12, PT-13	EXP PT-1, ACT-2 CLOUDS, PT-4 ACCENT COLOR ON DUCT	0' - 0"	760 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-4. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
A-007	STAIRS	LVT-1, RST-1	VWB-1	PT-1	EXP/ PT-1	0' - 0"	288 SF	LVT-1 ON FIRST FLOOR; RUBBER STAIR TREAD RISERS, AND LANDING
A-008	CORRIDOR	LVT-2	VWB-1	PT-1	ACT-1	9' - 4"	129 SF	
A-009	VESTIBULE	CPT-6	VWB-1	PT-1	ACT-2	9' - 4"	178 SF	SEE ELEVATION FOR BRICK AND GLASS
A-101	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	806 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-102	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	806 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-103	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	805 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-104	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	805 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-105	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	802 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-106	1ST GRADE SELF-CONTAINED CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	452 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-107	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	803 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-108	TEACHER'S LOUNGE	LVT-1, LVT-4	VWB-1	PT-1	ACT-1	9' - 4"	326 SF	SEE FINISH PLAN FOR FLOOR PATTERN.
A-108A	RR	PFT-1	PWB-1	PT-1, CWT-1,CWT-3	ACT-1	9' - 4"	54 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-108B	I.M.S	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	127 SF	
A-109	1ST GRADE CLASSROOM	LVT-1, LVT-4	VWB-1	PT-1, PT-4	ACT-1	9' - 4"	812 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-110	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	112 SF	
A-112	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	104 SF	
A-114	BOY'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-3	GYP, PT-1	9' - 4"	178 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
A-116	GIRL'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-3	GYP, PT-1	9' - 4"	179 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
A-118	ELEVATOR					0' - 0"	57 SF	
A-120	ELEC CL	SC	VWB-1	PT-1	EXP	0' - 0"	62 SF	PAINT ENTIRE WALL TO FLOOR
A-122	TECH ROOM	SC	VWB-1	PT-1	EXP	0' - 0"	66 SF	PAINT ENTIRE WALL TO FLOOR
A-124	CUST. CL	SC	VWB-1	FRP/ PT-1	EXP	0' - 0"	124 SF	FRP TO 8'0" AFF, PT-1 ABOVE
A-125	MOTOR ROOM (OT/PT)	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	587 SF	
A-126	RECEPTION/ SECRETARY	CPT-1, CPT-2, CPT-3	VWB-1	PT-1	ACT-2	9' - 4"	481 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-126A	PRINCIPAL OFFICE	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	157 SF	
A-126B	ASST. PRINCIPAL'S OFFICE	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	155 SF	
A-126C	ITIN. OFFICE	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	124 SF	
A-126D	ITIN. OFFICE	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	124 SF	
A-126E	PARENT VOLUNTEER ROOM	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	155 SF	
A-126F	CONF. ROOM	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	268 SF	
A-126G	GUID. COUN. OFFICE	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	111 SF	
A-126H	GUID.REC./ STOR.	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	62 SF	
A-126J	HEALTH CLINIC	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	267 SF	
A-126K	RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-8	ACT-1	9' - 4"	54 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-126L	MAIN TECH ROOM	SC	VWB-1	PT-1	EXP		203 SF	PAINT ENTIRE WALL TO FLOOR
A-126M	RR	PFT-1	PWB-1	PT-1, CWT-1	ACT-1	9' - 4"	57 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-126N	RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-8	ACT-1	9' - 4"	57 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-126P	VAULT	CPT-3	VWB-1	PT-1	ACT-1	9' - 4"	83 SF	
A-126R	WORK ROOM	CPT-3, CPT-1	VWB-1	PT-1	ACT-1	9' - 4"	303 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-126S	ADMINISTRATIVE STORAGE	CPT-3	VWB-1	PT-1	EXP	0' - 0"	142 SF	PAINT ENTIRE WALL TO FLOOR
A-126T	CORRIDOR	CPT-1, CPT-3	VWB-1	PT-1	ACT-2	9' - 4"	382 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-127	INTERVENTION	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	195 SF	
A-129	SPEECH OFFICE	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	203 SF	
A-130	SPECIAL ED STORAGE	LVT-2	VWB-1	PT-1	EXP		32 SF	PAINT ENTIRE WALL TO FLOOR
A-131	TITLE	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	248 SF	
A-133	RR/ SHOWER	PFT-1	PWB-1	PT-1, CWT-1	GYP, PT-1	9' - 4"	97 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-135	SPECIAL EDUCATION RESOURCE	LVT-1, LVT-7	VWB-1	PT-1, PT-10	ACT-1	9' - 4"	791 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-137	SPECIAL EDUCATION RESOURCE	LVT-1, LVT-7	VWB-1	PT-1, PT-10	ACT-1	9' - 4"	793 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-201	CORRIDOR	LIN-3, LIN-8	VWB-1	PT-1	EXP PT-1, ACT-2 CLOUDS, PT-3 ACCENT COLOR ON DUCT	9' - 4"	552 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-3. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
A-202	LANDING	LVT-2, LVT-3, LVT-9	VWB-1	PT-1	ACT-1	9' - 4"	226 SF	SEE FINISH PLAN FLOR FLOOR PATTERN. SEE CLG PLAN FOR CEILING HEIGHT AND LOCATION
A-203	CORRIDOR	LVT-2, LVT-3, LVT-9	VWB-1	PT-1	ACT-1	9' - 4"	1345 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-204	CORRIDOR	LVT-1	VWB-1	PT-1	ACT-2	9' - 4"	105 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-205	3RD GRADE ELA	LIN-1, LIN-6	VWB-1	PT-1, PT-15, PT-16, PT-17	EXP PT-1, ACT-2 CLOUDS, PT-17 ACCENT COLOR ON DUCT	0' - 0"	1788 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-17. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
A-206	3RD GRADE ELA	LIN-1, LIN-6	VWB-1	PT-1, PT-15, PT-16, PT-17	EXP PT-1, ACT-2 CLOUDS, PT-17 ACCENT COLOR ON DUCT	0' - 0"	729 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-17. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
A-207	STAIRS	LVT-1, RST-1	VWB-1	PT-1	ACT-1	9' - 4"	288 SF	LVT-1 ON FIRST FLOOR; RUBBER STAIR TREAD RISERS, AND LANDING
A-211	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	806 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-212	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	809 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-213	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	805 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-214	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	807 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-215	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	803 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-216	3RD GRADE SELF-CONTAINED CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	452 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-217	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	803 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS

ROOM FINISH SCHEDULE

NUMBER	NAME	FLOOR	BASE	WALL	CEILING	HEIGHT	Area	COMMENTS
A-218	TEACHER'S LOUNGE	LVT-1, LVT-9	VWB-1	PT-1	ACT-1	9' - 4"	326 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-218A	RR	PFT-1	PWB-1	PT-1, CWT-1	ACT-1	9' - 4"	54 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
A-218B	I.M.S	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	127 SF	
A-219	3RD GRADE CLASSROOM	LVT-1, LVT-9	VWB-1	PT-1,PT-17	ACT-1	9' - 4"	812 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-220	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	112 SF	
A-222	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	104 SF	
A-224	BOY'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-5	GYP, PT-1	9' - 4"	177 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
A-226	GIRL'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-5	GYP, PT-1	9' - 4"	178 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
A-228	ELEVATOR		VWB-1	PT-1			57 SF	
A-230	ELEC. CL	SC	VWB-1	PT-1	EXP		62 SF	PAINT ENTIRE WALL TO FLOOR
A-232	TECH ROOM	SC	VWB-1	PT-1	EXP		66 SF	PAINT ENTIRE WALL TO FLOOR
A-234	CUST. CL	SC	VWB-1	PT-1	EXP		122 SF	FRP TO 8'0" AFF, PT-1 ABOVE
A-235	MECHANICAL ROOM	SC	VWB-1	PT-1	EXP		1789 SF	PAINT ENTIRE WALL TO FLOOR
A-235A	CUST. CL	SC	VWB-1	FRP/ PT-1	EXP		42 SF	FRP TO 8'0" AFF, PT-1 ABOVE
A-235B	ELEC. CL	SC	VWB-1	PT-1	EXP		61 SF	PAINT ENTIRE WALL TO FLOOR
A-235C	TECH. ROOM	SC	VWB-1	PT-1	EXP		93 SF	PAINT ENTIRE WALL TO FLOOR
A-236	2ND GRADE SELF-CONTAINED CLASSROOM	LVT-1, LVT-3	VWB-1	PT-1, PT-3	ACT-1	9' - 4"	453 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
A-238	TEACHER'S LOUNGE	LVT-1, LVT-5	VWB-1	PT-1	ACT-1	9' - 4"	376 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
A-238A	RR	PFT-1	PWB-1	PT-1, CWT-1	ACT-1	9' - 4"	50 SF	WALL TILE TO 4'0" AFF; VERTICAL RUNNING BOND; T-3 TILE TRIM ON ALL EXPOSED TILE EDGES
B-001	CORRIDOR	LVT-2, LVT-8	VWB-1	PT-1	ACT-1	12' - 0"	2212 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
B-002	CORRIDOR	SC	VWB-1	PT-1	ACT-1	9' - 4"	307 SF	
B-101	MEDIA CENTER	CPT-5	VWB-1	PT-1	GYP/ PT-1, ACT-2	11' - 8"	985 SF	SEE CLG. PLAN FOR CEILING HEIGHT AND LOCATION
B-102	ART	LVT-1, LVT-8	VWB-1	PT-1	EXP PT-1, ACT-2	10' - 0"	1001 SF	SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-8
B-102A	ART MATERIAL STORAGE	LVT-1	VWB-1	PT-1	EXP	0' - 0"	150 SF	PAINT ENTIRE WALL TO FLOOR
B-103	ELEMENTARY DINING	LVT-1, LVT-2, LVT-8, LVT-10	VWB-1	PT-1	EXP PT-8, ACT-2 CLOUDS, METAL PANEL GRID	12' - 0"	2956 SF	SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATIONS. SEE FINISH FLOOR PLAN FOR FLOOR PATTERN PAINT ALL VISIBLE DUCTWORK AND DIFFUSERS PT-8
B-104	MUSIC	CPT-4, LVT-2	VWB-1	PT-1	ACT-2	10' - 0"	1000 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE CLG. PLAN FOR CEILING HEIGHT AND LOCATION. SEE INTERIOR ELEVATION FOR ACCENT PAINT LOCATIONS
B-104A	MUSIC STORAGE	LVT-1	VWB-1	PT-1	EXP.	0' - 0"	98 SF	PAINT ENTIRE WALL TO FLOOR
B-105	KITCHEN PREP/ SERVING	RF-1	VWB-1	PT-1	ACT-1	9' - 4"	1961 SF	
B-105A	RR	PFT-1	VWB-1	PT-1, CWT-1	ACT-1	9' - 4"	56 SF	
B-105B	LOCKER ROOM	SC	VWB-1	PT-1	ACT-1	9' - 4"	65 SF	PAINT ENTIRE WALL TO FLOOR
B-105C	DIETICIAN OFFICE	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	85 SF	
B-105D	DRY STORAGE	RF-1	VWB-1	PT-1	EXP	0' - 0"	212 SF	PAINT ENTIRE WALL TO FLOOR
B-106	BOY'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-6	GYP, PT-1	9' - 4"	184 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
B-107	TABLE STORAGE	SC	VWB-1	PT-1	EXP	0' - 0"	237 SF	PAINT ENTIRE WALL TO FLOOR
B-108	GIRL'S RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-6	GYP, PT-1	9' - 4"	180 SF	SEE ELEVATION FOR WALL TILE PATTERN AND GRAPHIC
B-109	FAMILY RR	PFT-1	VWB-1	PT-1, CWT-1, CWT-6	ACT-1	9' - 4"	80 SF	WALL TILE TO 4'0" AFF; VERTICAL RUNNING BOND; T-3 TILE TRIM ON ALL EXPOSED TILE EDGES
B-110	GYMNASIUM	SAF-1	VWB-1	PT-1,PT-2, PT-7, PT-8, PT-9	EXP / PT-1, PT-9 ACCENT COLOR ON DUCT		7975 SF	SEE FINISH PLAN FOR COURT LINE COLORS. COLORS SUBJECT TO CHANGE DURING SHOP DRAWING PHSE. SEE ELEVATIONS FOR PAINT COLOR LOCATIONS
B-110A	P.E STORAGE	SC	VWB-1	PT-1	EXP		325 SF	PAINT ENTIRE WALL TO FLOOR
B-113	CENTRAL STORAGE	SC	VWB-1	PT-1	EXP		196 SF	PAINT ENTIRE WALL TO FLOOR
B-115	TECH ROOM	SC	VWB-1	PT-1	EXP		90 SF	PAINT ENTIRE WALL TO FLOOR
B-117	MECHANICAL	SC	VWB-1	PT-1	EXP		1202 SF	PAINT ENTIRE WALL TO FLOOR
B-117A	ELECTRICAL ROOM	SC	VWB-1	PT-1	EXP		176 SF	PAINT ENTIRE WALL TO FLOOR
B-117AB	ELECTRICAL CLOSET	SC	VWB-1	PT-1	EXP		22 SF	PAINT ENTIRE WALL TO FLOOR
B-117B	OUTDOOR STORAGE	SC	VWB-1	PT-1	EXP		135 SF	PAINT ENTIRE WALL TO FLOOR
B-119	RECEIVING/ LOADING	SC	VWB-1	PT-1	ACT-1	9' - 4"	364 SF	
B-121	RR	PFT-1	PWB-1	PT-1, CWT-1	ACT-1	9' - 4"	57 SF	
B-123	OFFICE	SC	VWB-1	PT-1	ACT-1	9' - 4"	90 SF	
B-125	CUST. WORKROOM	SC	VWB-1	PT-1	ACT-1	9' - 4"	181 SF	
C-001	PRE-K ELA	LIN-1, LIN-5	VWB-1	PT-1, PT-5, PT-6, PT-11	EXP PT-1, ACT-2 CLOUDS, PT-5 ACCENT COLOR ON DUCT		882 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-5. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
C-002	KINDERGARTEN ELA	LIN-1, LIN-4	VWB-1	PT-1, PT-5, PT-6, PT-11	EXP PT-1, GYP CLOUDS/ PT-1, PT-5 ACCENT COLOR ON DUCT	0' - 0"	1349 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-5. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
C-003	KINDERGARTEN ELA	LIN-1, LIN-4	VWB-1	PT-1, PT-5, PT-6, PT-11	EXP PT-1, GYP CLOUDS/ PT-1, PT-5 ACCENT COLOR ON DUCT	0' - 0"	713 SF	SEE FINISH PLAN FOR FLOOR PATTERN; SEE CLG. PLAN FOR CLOUD HEIGHT AND LOCATION. PAINT ALL VISABLE DUCTWORK AND DIFFUSERS PT-5. SEE INTERIOR ELEVATIONS FOR PAINT LOCATION
C-005	STAIRS	LVT-1, RST-1	VWB-1	PT-1	EXP / PT-1	9' - 4"	271 SF	LVT-1 ON FIRST FLOOR; RUBBER STAIR TREAD RISERS, AND LANDING
C-101	PRE-KINDERGARTEN CLASSROOM	LVT-1, LVT-6	VWB-1	PT-1, PT-6	ACT-1	9' - 4"	950 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-101A	PK RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	73 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-102	PRE- KINDERGARTEN CLASSROOM	LVT-1, LVT-6	VWB-1	PT-1, PT-6	ACT-1	9' - 4"	914 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-102A	PK RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	46 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-103	CUST. CL	SC	VWB-1	FRP/ PT-1	EXP		68 SF	FRP TO 8'0" AFF, PT-1 ABOVE
C-104	PRE-KINDERGARTEN CLASSROOM	LVT-1, LVT-6	VWB-1	PT-1, PT-6	ACT-1	9' - 4"	951 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-104A	PK RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	47 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-105	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	94 SF	
C-106	KINDERGARTEN CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	949 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-106A	K RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-2	ACT-1	9' - 4"	55 SF	WALL TILE TO 4'0" AFF; VERTICAL RUNNING BOND; T-3 TILE TRIM ON ALL EXPOSED TILE EDGES
C-107	TEACHERS' LOUNGE	LVT-1, LVT-5	VWB-1	PT-1	ACT-1	9' - 4"	367 SF	SEE FINISH PLAN FLOR FLOOR PATTERN
C-107A	RR	PFT-1	PWB-1	PT-1, CWT-1	ACT-1	9' - 4"	65 SF	WALL TILE TO 4'0" AFF; VERTICAL RUNNING BOND; T-3 TILE TRIM ON ALL EXPOSED TILE EDGES
C-107B	IMS	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	128 SF	
C-108	SMALL GROUP ROOM	LVT-1	VWB-1	PT-1	ACT-1	9' - 4"	111 SF	
C-109	KINDERGARTEN CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	952 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-109A	K RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	55 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-110	KINDERGARTEN SELF CONTAINED CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	454 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-112	KINDERGARTEN CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	910 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-112A	K RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	51 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-113	KINDERGARTEN CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	886 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-113A	K RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	58 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES
C-114	KINDERGARTEN CLASSROOM	LVT-1, LVT-5	VWB-1	PT-1, PT-5	ACT-1	9' - 4"	898 SF	SEE FINISH PLAN FOR FLOOR PATTERN. SEE INTERIOR ELEVATIONS FOR PAINT LOCATIONS
C-114A	K RR	PFT-1	PWB-1	PT-1, CWT-1, CWT-4	ACT-1	9' - 4"	51 SF	WALL TILE TO 5'0" AFF; VERTICAL RUNNING BOND; T-1 TILE TRIM ON ALL EXPOSED TILE EDGES

PROJECT NO
2203-1

ARCHITECTURAL VISION GROUP, LTD
ARCHITECTS • PLANNERS
23850 SPERRY DRIVE CLEVELAND, OHIO 44145

PROFESSIONAL SEAL:
SYED S. ABBAS
A-9109376
STATE OF OHIO
SYED ABBAS, LICENSE #ARC-9109376
EXPIRATION DATE 12/31/2023

CONSULTANT:

MASSILLON CITY SCHOOL
MASSILLON WEST ELEMENTARY
PK-3
250 29TH STREET NW, MASSILLON, OHIO 44646
MASSILLON CITY SCHOOL DISTRICT MASSILLON, OHIO

MARK	DATE	DESCRIPTION
	7-2-23	100% BID PHAMIT SET

ISSUED AS:

PROJECT NO	2203-1
DRAWN BY	
CHECKED BY	
DATE	

FINISH SCHEDULE

SCALE:

SHEET NO
A-651