



CODED PLAN NOTES

1. PROVIDE 18" W CABLE RUNWAY.
2. PROVIDE TELECOMMUNICATIONS MAIN GROUNDING BUSBAR "TMGB".
3. PROVIDE 4" x 8" AC GRADE PLYWOOD BACKBOARD. MOUNT BOARDS 6" AFF WITH 1" SIDE FACING TOWARDS USER (TYPICAL).
4. PROVIDE 4-POST TECHNOLOGY DISTRIBUTION RACK.
5. PROVIDE 6" WIDE VERTICAL WIRE MANAGER ON BOTH ENDS OF LINE OF RACKS AND 10" WIDE VERTICAL WIRE MANAGERS BETWEEN EACH RACK.
6. BOND EACH RACK WITH A DEDICATED BONDING CONDUCTOR WITH A CABLE SIZED AT 2 KMIL PER LINEAR FOOT OF CONDUCTOR TO TMGB. BONDING CONDUCTOR SHALL BE NO LESS THAN #6 AWG.
7. STAIRCASE ON FLOOR ABOVE INTERSECTS WITH CEILING SPACE OF THIS TELECOMMUNICATIONS ROOM. CONTRACTOR SHALL MAKE ALL NECESSARY ADJUSTMENTS TO EQUIPMENT INSTALLATION AND CABLE ROUTING TO AVOID DISRUPTING OR PENETRATING STAIRCASE.
8. 2U FIBER LULI
9. 2U HORIZONTAL WIRE MANAGER
10. 2U 48-PORT PATCH PANEL FOR BACKBONE CABLING.
11. 2U 48-PORT PATCH PANEL FOR CAT 6 UTP CABLING.
12. 2U 48-PORT PATCH PANEL FOR CAT 6A UTP CABLING.
13. SPACE FOR OWNER-PROVIDED NETWORK SWITCH
14. SPACE FOR OWNER-PROVIDED UPS.

PROJECT NO  
2203-1

ARCHITECTURAL VISION GROUP, LTD  
PLANNERS  
ARCHITECTS  
23850 SPERRY DRIVE  
CLEVELAND, OHIO 44145







OSBORN ENGINEERING  
1000 Superior Avenue, Suite 200, Cleveland, OH 44114  
216.861.0025  
www.osborn-eng.com

MASSILLON CITY SCHOOLS  
MASSILLON WEST ELEMENTARY  
PK-3  
250 20TH STREET NW, MASSILLON, OHIO 44646  
MASSILLON CITY SCHOOL DISTRICT MASSILLON, OHIO

MARK	DATE	DESCRIPTION
07/12/23	07/12/23	ISSUED FOR PERMIT SET
07/12/23	07/12/23	ISSUED AS

PROJECT NO  
2203-1

DRAWN BY  
DRK

CHECKED BY  
AMW

DATE  
07/12/23

TECHNOLOGY  
ENLARGED  
PLANS AND  
ELEVATIONS

SCALE: As indicated

SHEET NO  
T-401