




S 88° 15' E

80
Rus.

Angle Point
looks like it
is at this pt
from Rec. Plat

S 86° 03' E

NEW ENGLAND ALLOTMENT

PR 10 P 118

TREMONT ROAD LAID OUT IN 1844 as 60' WIDE
ALTERATION REESTABLISHED IN (Dec 11) 1914) PET.
from MASS BOARD OF TRADE MOVING THE ROAD
SOUTH from the org. est. Location.
See Road Rec Book #10 Page 177
Stark County Surveyor Office Canton

Look up deeds - Road Record, Tremont & New E. P.
Probate Court Christian Kestner to M Kestner
691:241: Beg for the Same at a stone in the Road
leading from the City of Mass to Canton and running
th So. ^{155.1} 21 1/4 deg W. 2.35 ch to a stone in the Trem
Road th with sd road 88 1/2° E. ~~for~~ ^{265.32} 4.02
ch to a st. in sd Mass Canton Road th with sd rd
no. 68 3/4° W. ^{247.5} 3.75 ch to place of Beg. con. 5/8 ac.
of land more or less and being the same
premises conveyed or intended to be conveyed
from Fredericke Kestner Heirs to C Louisa
Kestner as recorded in Vol 226 Page 494
nothing in above subject to legal highway
226 P 494 Same as above Herman Kestner et al
Q.C. Deed. Rec Mar 21 1887 to Christian Kestner

Marie Kestner to 695:30
Mayme Kestner
Beg for the Same at the N W Cor of Herman Kestner
tract as Rec in Vol 226 P 494 of SCDRs: th
E at the N E of sd tract 65 feet th So an 11
to the W E of sd Tr. to its So - th W at the
S - to its S.W. cor th N at ~~the~~ ^{its} W - 155.1 to
pl of Beg cont. Nine hundred (0.11) of an acre
to the same more or less but subject to all legal highways.

4101244

Christian Kestner
Mary Kestner
to

Richard Kestner

Begin for the same at a stone at the
pt of + of the mid - $\frac{1}{2}$ of the rds running easterly
from E Main St & E Tremont St. in the City of M
S C O (sd roads being the extension of sd sts)
and running th wly al the c of sd M S Rd (
(also known as the State Rd from Mass to Cant)
464 feet to a stone, which is the pt of beg
for the bounding of the pt hereby conveyed
th S $20^{\circ}45'W$ 164 feet to a st in the center
of sd Tremont St Rd, th Ely al the c of
Tremont St Rd S $89^{\circ}25'E$ - 50 feet, th
No 11 with the w - of the part hereby
conveyed to the c of sd Main St Rd.
thence W al the c of sd M S R 50 feet
to the place of Beg cont. 2 $\frac{1}{2}$ on acrs
be the same more or less subject to
all legal highways

Rec for Rec 8 Am July 1/1903
Rec Aug 6 1903

M & E Heiler & Wm Beyerly.

Begin at a st in the N of the St. Rd leading
from Mass to Can. which st is distant Wly
thereon 464 feet for a st at the pt of int. of
of sd md & of sd Rd & the N- of the Rd
at the "Fork" th. SO $20^{\circ}45'W$ 164 feet to
a st in the middle of sd Tre. rd th
No $89^{\circ}25'W$ - 65 feet to another st th
No $20^{\circ}40'E$ 187 ft to another st in the
middle of sd St Rd. and th S $68\frac{3}{4}^{\circ}E$
65 feet to the pt of Beg cont 29.00 acres

this is a deed of correction

but subject to all legal Highways
Rec for Rec 1891 Dec 21 at 9:20 a
Rec Dec 24 1891

726 Tremont Road Rec. 10 Page 177

Dec 11 1914 Alteration pushed the Road
South 15.6 at Angle 21.2 around Beyerly
alley.

361

Rd Rec C Page 300 June 1844 60 feet wide County Rd.

ON JAN

OF 1844

TOTAL

NO. 1000

NO. 1000

NO. 1000

NO. 1000

CITY OF
MASSILLON

DEPT. OF
ENGINEERING

LOCATION _____

SUBJECT _____

COMPUTED BY _____ DATE _____ CHECKED BY _____ DATE _____


JOB NO.

FILE NO.

SHEET NO.

Reason for alteration, reestablished and located because it will tender unnecessary any hardships resulting on property holders on the N side of Tremont Road when the road is opened to its proper width 60 ft.

164
50
—
414



$$\begin{array}{r} 2600 \\ 10 \overline{) 2600} \end{array}$$

$$\begin{array}{r} 155.1 \\ 680 \\ \hline 75.1 \end{array}$$

533 : 509

~~beg~~ at the new cor of a tr of land owned
by W^m Byerly thence Wly al the c of
sd rd 268 W 60 ft to a pt th
Southerly al the E - of lands now
owned by Mary Candale S 22 W 244 ft
to a pt in the c of T. Rd. th
E N 89° 30' E 65 ft to a pt
in the c of sd T. Rd at the S W
Cor of sd W^m Byerly Tract th
Wly al sd " " W - 218.8 ft
to pt. of Beg

Job J. Rypple to Merion W. Hill

beg at an S. P. in the cent of M C Rd.

known also as E Main St Ext. sd S. P. in
being at the NE cor of a tr of land now owned
by John Heesler Th Ely 60 ft to an Iron Pin
in the center of sd rd; th Sly 269.02 ft to an Iron
pin in the center of T. St. Ext. th W 65 ft
to an S. P. in the E of sd Rd. St. Ext at the
So. E. cor of sd John Heesler land; th north
along the W - of sd land 794.05 ft to pt
of Beg.

793/490

Merion W Hill to Mary Thurston

Beg at the SE cor of lot 6329 being in the middle
of E. Tremont St and th Ely at the S - of sd lot
6314 - 65 ft to the S.E. cor of lot 6314 th
Nly at the E - of sd lot 6314 105 ft to
a pt; th Wly 60 ft to a pt, th Sly at the
W - of sd lot 6314 - 130 ft to the pt. of Beg

933-472

1. Margaret Heisler to Wm Bauerle 10-19-91
Starting at a stone intersection, E Tremont & Main
thence westerly along E Tremont 375 feet to place of beginning
thence " " " " 65' thence northerly 185 feet
to E Main thence easterly along E Main 65'
thence southerly 180 feet to place of beginning containing
0.3 acre. No mention of legal highways.

2. Margaret Heisler & Emanuel Heisler to Wm Byerly
12-21-91 Beginning @ a stone in the E of State Road
from Mass to Canton which stone is distant westerly thereon 464
feet from a stone @ the pt of intersection of said E 1st road
& of Tremont Road at the fork; thence S 26° 45' W
164 ft to a stone in E Tremont road; " N 89° 25' W 65'
feet to another stone thence N 20° 40' E 187 feet to another
stone in E said state road; thence S 68° 45' E 65' to
place of beginning containing 0.26 acres ± as surveyed by
D A Miller civil eng. 12-15-91. The object of this deed is
to convey the description of premises intended to be conveyed
to said grantee by name of Wm Bauerle by one deed
of 10-1-91 wherein the description is not correct
subject to all legal highways

3. Margaret Heisler to Arthur P. Maurer 11-9-98
Beginning N 68° 47' W 539 feet from the E Canton Rd &
Tremont Road @ an iron stake on E said " Rd; thence
S 20° 45' E 190.1 feet to an iron stake in E said Tremont
Rd; thence N 89° 25' W 70 feet to an iron stake; thence
N 19° 36' W 214.8 feet to an iron stake in E said Canton
Rd; thence S 68° 47' E 70 feet to place of beginning containing
.32 acre subject to all legal highways.

4. Margaret Heisler to Wm Byerly 10-30-99
Beginning at an iron stake N 68° 45' W 519 feet from
the intersection of the Canton & Tremont Roads; thence
S 26° 45' W 187 feet to E of " Rd; thence N 89° 25' W
10.5 along E Tremont Rd; thence N 20° 45' W 190.1
feet to E Canton Rd; thence S 68° 45' E 10 feet along E
Canton Rd to place of beginning containing .43 acre
subject to all legal highways.

5. Arthur P. Maurer to Wm Byerly 10-17-1900
Beginning N 68° 47' W 539 feet from intersection of
Canton Mass Rd & Tremont Rd @ an iron stake
in E said Canton Rd; thence S 20° 45' E 190.1 feet

to an iron stake in & said Tremont St Rd. thence N
89° 25' W 70 feet to an iron stake; thence N 19° 36'
W 214.8 feet to an iron stake in & said Canton Rd.
thence S 68° 47' E 70 feet to place of beginning
containing .32 acres
No mention of highways

6. Edward Heisler et al to Wm Boyerly 9-30-1903
Beginning N 68° 47' W 539 feet from intersection
of Canton Rd & Tremont St Rd @ an iron stake in &
said Canton Rd. thence S 20° 45' E 190.1 feet to
an iron stake in & said Tremont St Rd. thence
N 89° 25' W 70 feet to an iron stake; thence N
19° 36' W 214.8 feet " " " " in & said
Canton Rd. thence S 68° 47' E 70 feet to place of beginning
containing .32 acres, Being the same property
as described in a certain deed from Arthur P. Maurer
& wife to Wm Boyerly recorded Vol 379 pg 493
recorder's office

289

028

