

East End

The estimated costs of the trunk sewers for this area are as follows:

East End and Sippo Heights--Trunk Sewer Costs

<u>Trunk #1:</u> From Manhole #21 of Sippo Trunk to angle in Tremont Street.	400 lin. ft. 8-in. Sewer	\$ 950
<u>Trunk #2:</u> From near Manhole #20 of Sippo Trunk to west end of Connecticut Street Avenue.	1530 lin. ft. 8-in. Sewer	4,400
<u>Trunk #3:</u> From Manhole #19 of Wetmore Trunk to Ravine 1,800 feet west of Jackson Lane.	1820 lin. ft. 15-in. Sewer 3170 lin. ft. 12-in. Sewer	5,650 9,150
<u>Trunk #3A:</u> From Trunk #3 to to west end of Rhode Island Avenue.	1950 lin. ft. 8-in. Sewer	3,700
<u>Trunk #3B:</u> From Trunk #3 to Conrad Avenue.	1750 lin. ft. 8-in. Sewer	3,300
<u>Trunk #3C:</u> From Trunk #3 to east end of Connecticut Avenue.	1800 lin. ft. 8-in. Sewer	2,800
<u>Trunk #4:</u> From Manhole #26 of Sippo Trunk to Outlet of Sippo Heights.	450 lin. ft. 8-in. Sewer	1,100
TOTAL--East End and Sippo Heights	12,870 lin. ft.	\$31,050

Trunks #2 and 3A are designed to serve areas allotted, but not yet developed. These sewers could be omitted for immediate construction without effect upon the general plan.