

June 26, 1923

5142

Report on
Sanitary Trunk Sewers,
Massillon, Ohio

The purpose of the investigation which this report represents is the determination and evaluation of the needs of the City of Massillon for trunk sewers to afford sanitary outlet to city areas and to some immediately contiguous.

The conclusion reached is that there should be constructed at once 6.65 miles of trunk sewer estimated to cost \$291,500. Also that as additional needs develop, there will be required an additional 4.45 miles at a cost of \$199,500.

List of Trunk Sewers recommended for Early Construction

<u>Description</u>	<u>Area Served</u>	<u>Length</u>	<u>Cost</u>
1: North End Trunk from Cherry and West Sts. to Mill and Lake Sts.	Mill and Lake St. area and Earl St. Section	5,050	\$35,300
2: Cherry St. Sub-Trunks; Cherry from West across R.R. Right of Way West St. to Clay St.	Cliff and Guy St. Cherry and Clay	1,100	\$ 9,300
3: Wooster Trunk from West St. near Cherry to Pigeon Run Road	West End of City	7,570	28,600
4: Slipco Trunk from West and Tremont Sts. to Front and Kendal	Part of N. End, Slipco Hts., Canton Rd., Oak Street	11,800	82,000
5: Wetmore St. Trunk from South Erie Street to Corporation Line	Hersh Street, East Walnut St., Little Slipco Cr.	3,979	19,700
6: Tuscarawas Trunk-part from Cherry St. to So. of West Walnut Street	the above Trunk Sewers	5,630	117,600
	TOTALS	35,120	\$291,500
		Linear Feet	