



1. CONTRACTOR TO REMOVE ALL EXISTING LIGHTING, RECEPTACLES AND ASSOCIATED CONDUIT AND WIRING.
2. CONTRACTOR TO REPLACE EXISTING CIRCUIT BREAKERS IN EXISTING LIGHTING PANEL WITH NEW 20 A. CIRCUIT BREAKERS FOR THE FOLLOWING CIRCUITS:
 - (1) DRIT ROOM LIGHTING
 - (1) SCREEN ROOM LIGHTING
 - (1) EXHAUST FAN #2-1
 - (1) DRIT ROOM RECEPTACLES
 - (1) SCREEN ROOM RECEPTACLES

GENERAL NOTES FOR SHEETS EB1 – EB6

1. LIGHT LINES (———) DESIGNATE EXISTING CONDITIONS AND EQUIPMENT.
2. HEAVY LINES (———) DESIGNATE PROPOSED WORK OR EQUIPMENT.
3. ALL HOMERUNS TO THE LIGHTING PANELS
ALL WIRE/CONDUIT BETWEEN ALL SINGLE PHASE EQUIPMENT (TYPICALLY SMALLER THAN 1/2" MOTORS AND EQUIVALENT LOADS) SHALL BE #12, #12 GND.-3/4" C. UNLESS OTHERWISE NOTED.
4. ALL HOMERUNS TO MOTOR CONTROL CENTERS AND WIRE/CONDUIT RUNS BETWEEN ALL THREE PHASE EQUIPMENT (TYPICALLY 1/2 HP AND LARGER AND EQUIVALENT LOADS) SHALL BE #12, #12 GND.-3/4" C. UNLESS OTHERWISE NOTED.
5. ALL SURFACE MOUNTED AND PENDANT MOUNTED LIGHTING FIXTURES SHALL BE MOUNTED TO AVOID INTERFERENCE WITH OTHER EQUIPMENT IN THE SAME LOCATION.
6. ALL TABLES ARE SHOWN FOR REFERENCES ONLY. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROVIDE ALL OF THE ITEMS SHOWN ON THE INDIVIDUAL DRAWINGS.
7. ALL HOMERUNS TO LIGHTING PANELS CAN BE COMBINED IN THEIR RESPECTIVE HOMERUN CONDUITS TO MINIMIZE THE TOTAL NUMBER OF CONDUITS ENTERING THE PANEL. PROVIDED THE INTEGRITY OF REDUNDANCY IS MAINTAINED AND PRIOR APPROVAL IS OBTAINED FROM THE ENGINEER. CONTRACTOR MUST CONSIDER THE CONDUCTORS IN ACCORDANCE WITH MOST RECENT NEC REQUIREMENTS.
8. REFER TO APPROPRIATE SCHEDULE FOR EQUIPMENT IDENTIFIED WITH 
9. NUMERALS ADJACENT TO RECEPTACLES, LIGHTING FIXTURES, AND MISC. EQUIPMENT DENOTE BRANCH CIRCUIT NUMBERS. e.g. 



DESIGNED BY			REVISIONS		
NO.	DESCRIPTIONS	DATE	BY	APP'D	
AEP	DRAWN BY				
AEP					
CHECKED BY					
DMO					
APPROVED BY					
DMO					