



CITY OF MASSILLON, OHIO
151 LINCOLN WAY EAST
MUNICIPAL GOVERNMENT ANNEX
CITY ADMINISTRATION BUILDING
MASSILLON, OHIO 44646
PHONE 330-830-1722 FAX 330-830-1786

PERMIT DATE:

1/31/2012

PERMIT NO.

4168

PERMIT TO TAP SANITARY SEWER

This permit is issued subject to the latest Codified Ordinances of the City of Massillon, OH. The City Engineer to be notified 24 hours in advance of start of work (330) 830-1722. All permits issued under this ordinance are void after 120 days from date of issuance.

RECEIVED OF:

PERMIT TYPE Repair

CONTRACTOR INFORMATION

SITE INFORMATION

CONTRACTOR: Miracle Plumbing & Heating

OWNER'S NAME: J. Thomas

CONTACT: Steve Brown

FULL STREET ADDRESS: 1234 Tremont Avenue SE

ADDRESS: _____

CITY: _____

CITY LOT NUMBER 9525

STATE: _____

PURPOSE OF CUT: Repair

ZIP: _____

ZONING CLASS: _____

PHONE: (330) 477-2402

STREET SIDE: _____

FAX: _____

SURETY: _____

PHONE OTHER: _____

SANITARY SEWER CONNECTION:

NOTE: This permit covers work outside of the building ONLY. Any work inside walls of the building is subject to the Massillon Board of Health Regulations.

USE: Residential

SKETCH: DRAWING #: _____

DATE INSPECTED 2/7/12

located on the north side of

Tremont Ave SE between
3rd St and
16th St

Direction from downstream Manhole: South

Distance from downstream Manhole: 60'

Connection Length: 26' (FEET)

Connection Depth: 4 (FEET)

Size of Sewer Pipe: 6" (INCHES)

Pipe Material: PVC

INSPECTORS NAME: Jason

INSPECTION REQUEST: 2/7/12

COMMENTS:

Old lateral crushed at building
Replaced 26' by Malavite

SANITARY SEWER PERMIT FEE: \$50.00

CAPACITY FEE: \$0.00

TOTAL COST: \$50.00

TWO WORKING DAYS BEFORE YOU DIG

Ohio Utilities Protection Service

Call 1-800-362-2764 Toll Free....

Non-Members must be called directly.

AUTHORIZED BY: DIRECTOR OF PUBLIC SAFETY AND SERVICE

ISSUED BY: Linda Mikutel



Ex. Manhole

Ties in either side of manhole, not sure

Ex. Clean out

This Section repaired 12/6/2011 by Holderbaum see permit 4162

Fernco w/ stainless bands
PVC to clay

Existing lateral down the hill side

5' deep tie to existing

cut off old Lateral

Old lateral crushed under deck

Ex Deck

19' from corner
4' deep at house

cutting 4" to 6" fitting

clean out up

4" ABS under block

1" of 6" PVC
1" of 6" PVC

sewer goes out back of house

Existing House Foundation
#1234
Tremont

Tremont St SE

Garage

Driveway